

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	RX-1-BR-1	VERMILION	140	15
STA. _____ TO STA. _____		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT _____		

SCHEDULE OF QUANTITIES

PIPE CULVERT REMOVAL - 50105220

STATION	O/S	FOOT
190+31.19	32.7	36.6
193+07.41		76.0
194+41.91	32.8	22.9
TOTAL =		135.5

TOTAL = 136.0 FOOT

CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS, 24" - 54215424

STATION	O/S	EACH
193+07.41	48.4	1.0
193+07.41	43.7	1.0
TOTAL =		2.0

TOTAL = 2.0 EACH

METAL END SECTIONS, 12" - 54215547

STATION	O/S	EACH
196+29.95	38.42	1.0
201+36.82	79.23	1.0
196+00.69	47.38	1.0
201+09.67	77.87	1.0
TOTAL =		4.0

TOTAL = 4.0 EACH

METAL END SECTIONS, 15" - 54215550

STATION	O/S	EACH
190+02.73	32.7	1.0
190+61.08	32.7	1.0
194+04.03	54.3	1.0
194+68.90	60.6	1.0
195+39.00	58.2	1.0
TOTAL =		5.0

TOTAL = 5.0 EACH

PIPE CULVERTS, CLASS D, TYPE 2, 15" (TEMPORARY) - 5422D015

STATION	O/S	TO	STATION	O/S	FOOT
190+02.73	32.8		192+46.33	51.3	244.0
TOTAL =					244.0

TOTAL = 244.0 FOOT

PIPE CULVERTS, CLASS A, TYPE 2, 24" - 542A1069

STATION	LT O/S	RT O/S	FOOT
193+07.41	43.7	48.4	92.2
TOTAL =			92.2

TOTAL = 92.0 FOOT

PIPE CULVERTS, CLASS D, TYPE 2, 15" - 542D1060

STATION	O/S	TO	STATION	O/S	FOOT
190+02.73	32.7		190+61.08	32.7	58.0
194+00.31	54.2		194+67.16	49.7	62.9
194+70.65	49.6		195+39.46	58.2	69.4
194+68.90	49.5				9.3
TOTAL =					199.6

TOTAL = 200.0 FOOT

PIPE DRAINS, 12" - 60100945

STATION	FOOT	
196+29.95	38.4	
201+36.88	63.7	
196+00.69	47.4	
201+09.67	82.5	
TOTAL =		232.0

TOTAL = 232.0 FOOT

INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID - 60240215

STATION	O/S	EACH
194+68.90	49.5	1.0
TOTAL =		1.0

TOTAL = 1.0 EACH

REMOVING INLETS - 60500060

STATION	EACH	
199+95.84	1.0	
199+76.26	1.0	
TOTAL =		2.0

TOTAL = 2.0 EACH

FLAP GATE, 24" - 60801024

STATION	O/S	EACH
193+07.41	48.39	1.0
TOTAL =		1.0

TOTAL = 1.0 EACH

CONCRETE THRUST BLOCKS - 60900515

STATION	O/S	EACH
196+29.95	32.8	1.0
201+36.88	69.9	1.0
196+00.69	42.9	1.0
201+09.67	68.7	1.0
TOTAL =		4.0

TOTAL = 4.0 EACH

TYPE E INLET BOX, STANDARD 610001 - 61000115

STATION	EACH	
196+29.95	1.0	
201+36.88	1.0	
196+00.69	1.0	
201+09.67	1.0	
TOTAL =		4.0

TOTAL = 4.0 EACH

STEEL PLATE BEAM GUARDRAIL, TYPE A - 63000000

STATION	TO	STATION	FOOT
191+02.30		196+27.30	525.0
201+33.77		201+96.27	62.5
201+02.05		202+02.05	100.0
TOTAL =			687.5

TOTAL = 687.5 FOOT

TRAFFIC BARRIER TERMINAL, TYPE 6 - 63100085

STATION	TO	STATION	EACH
196+27.30		196+60.45	1.0
201+00.62		201+33.77	1.0
195+93.73		196+26.88	1.0
200+67.05		201+00.20	1.0
TOTAL =			4.0

TOTAL = 4.0 EACH

TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (FLARED) - 63100169

STATION	TO	STATION	EACH
190+52.30		191+02.30	1.0
195+43.73		195+93.73	1.0
TOTAL =			2.0

TOTAL = 2.0 EACH

GUARDRAIL REMOVAL - 63200310

STATION	TO	STATION	FOOT
195+54.00		196+56.06	102.06
199+86.88		201+96.27	209.39
195+74.23		196+28.05	53.82
199+60.26		202+02.50	242.24
TOTAL =			607.51

TOTAL = 608.0 FOOT

BITUMINOUS SHOULDER CURB - 66101120

STATION	TO	STATION	FOOT
196+24.95		196+39.95	15.0
201+21.81		202+00.00	78.2
195+95.69		196+05.69	10.0
200+87.55		202+00.00	112.5
TOTAL =			215.7

TOTAL = 216.0 FOOT

CALCIUM CHLORIDE APPLIED - 66300105

STATION	TO	STATION	TONS
0+00.00		5+06.59	1.97
TOTAL =			1.97

TOTAL = 2.0 TONS

CHAIN LINK GATES, 4' X 18' DOUBLE - 66406100

STATION	EACH	
12+80.00	1.0	
TOTAL =		1.0

TOTAL = 1.0 EACH

CHAIN LINK FENCE REMOVAL - 66410300

STATION	O/S	TO	STATION	O/S	FOOT
21+17.44	28.4	RT	21+17.44	18.1	LT
TOTAL =					50.7

TOTAL = 51.0 FOOT

WOVEN WIRE FENCE REMOVAL - 66502300

STATION	O/S	TO	STATION	O/S	FOOT
194+82.30	54.0		194+65.87	154.69	102.0
TOTAL =					102.0

TOTAL = 102.0 FOOT

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS - 66600105

STATION	O/S	EACH
192+50.00	64.0	1.0
195+21.27	122.0	1.0
195+28.35	76.0	1.0
TOTAL =		3.0

TOTAL = 3.0 EACH

PERMANENT SURVEY MARKERS - 66700095

LOCATION	EACH	
SN 092-0205	1.0	
TOTAL =		1.0

TOTAL = 1.0 EACH

TEMPORARY RUMBLE STRIPS - 70106700

STATION	EACH	
44+12.00	1.0	
47+62.00	1.0	
49+62.00	1.0	
56+51.00	1.0	
58+51.00	1.0	
62+01.00	1.0	
TOTAL =		6.0

TOTAL = 6.0 EACH

TEMPORARY PAVEMENT MARKING, LINE 4" - 70300220

STATION	TO	STATION	FOOT
186+00.00		202+00.00	401.0
TOTAL =			3602.0

TOTAL = 3602.0 FOOT

TEMPORARY PAVEMENT MARKING, LINE 24" - 70300280

STATION	TO	STATION	FOOT
52+62.00			25.7
53+51.00			22.9
19+45.00			32.0
TOTAL =			80.6

TOTAL = 81.0 FOOT

WORK ZONE PAVEMENT MARKING REMOVAL - 70301000

STATION	TO	STATION	SO FT
52+62.00			51.4
53+51.00			45.8
19+45.00			64.0
TOTAL =			161.2

TOTAL = 161.0 SO FT

PAINT PAVEMENT MARKING, LINE 4" - 78001110

STATION	TO	STATION	FOOT
186+00.00		196+22.82	2045.6
201+04.68		202+00.00	190.6
TOTAL =			2515.7

TOTAL = 2515.7 FOOT

PAINT PAVEMENT MARKING, LINE 4" - 78001110

STATION	TO	STATION	FOOT
186+00.00		196+22.82	255.7
201+04.68		202+00.00	23.8
TOTAL =			2515.7

TOTAL = 2516.0 FOOT

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____

DATE: _____

DRAWN BY: _____
CHECKED BY: _____

PLOT DATE = 8/26/2006
FILE NAME = c:\projects\90841\90841.dgn
PLOT SCALE = 1/8" = 1' IN.
USER NAME = stults,jr