

## NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN 1 WITH INSTALLED PANEL 2 ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 2.3 SQ. M. (25.70 SQ. FT.)

ALL DIMENSIONS ARE IN MILLIMETERS (INCHES) UNLESS OTHERWISE SHOWN.		
REVISIONS	ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME DATE	ILLINOIS DELAKIM	ENT OF TRANSFORTATION
R. MIRS 9-15-97		
R. MIRS 12-11-97	TEMPORARY THE	ORMATION SIGNING
T. RAMMACHER 2-2-99	LEWI ORART THE ORIGINATION STORTING	
	SCALE:	DRAWN BY: BUR. OF DESIGN
	DATE 10/18/2002	CHECKED BY

REVISION DATE: 02/02/99