CONTRACT NO. 64426


FED. ROAD DIST, NO. 7 ILLINOIS FED. AID PROJECT-

SHEET NO. 21

24 SHEETS

—Ties at 4'-0" cts. Stage Construction Joint Finishing machine rail-Hardwood 4" x 4" blocks at 4'-0" cts.

> FORM BRACES FOR STAGE CONSTRUCTION



STANDARD CONSTRUCTION

When cantilever forming brackets are used, the work shall be done according to Article 503.06, except as modified below and in the details shown on this sheet.

The finishing machine rails shall be placed on the top flange of the exterior beams.

The beams or girders, supporting cantilever forming brackets, shall be fied together at 4 foot intervals.

For Standard construction, or Stage Construction the Hardwood bracing materials shall be placed as shown between webs of beams in each bay.

CANTILEVER FORMING BRACKETS IL RTE 40 OVER WINNEBAGO DITCH F.A.P. 646 SECTION (102)BR-3 WHITESIDE COUNTY STATION 558+38 S.N. 098-0109



Aug. 2005