
CONTRACT NO 64517

		00,411,6		0 101
F.A. P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
573	116R-4	DEKALB	416	258
STA.		TO STA.		
EED DOM	DOIST NO THE	INDIS FED AID	PROJECT	


WATER & SEWER TRENCH CROSS-SECTION FOR PVC PIPE



- 1.) FOUNDATION IS REQUIRED WHEN DEEMED NECESSARY BY THE ENGINEER.
- 2.) BEDDING SHALL CONFORM TO IDOT GRADATION CA-11. THICKNESS SHALL BE EQUAL TO 1/4 OF PIPE DIAMETER BUT SHALL NOT BE LESS THAN 4" IN EARTH EXCAVATION AND 6" IN ROCK EXCAVATION, COMPACTED.
- 3.) HAUNCHING SHALL BE IDOT CA-11 COMPACTED.
- 4.) INITIAL BACKFILL SHALL BE IDOT CA-11. COMPACTED TO A MINIMUM COVER OF 12".
- 5.) FINAL BACKFILL UNDER HARDSURFACED AREAS OR WHERE THE TRENCH LIES WITHIN TWO FEET OF CURB OR HARDSURFACED AREA SHALL BE IDOT CA-11 COMPACTED. MINIMUM DEPTH FOR WATER MAIN SHALL BE FIVE (5) FEET.
- 6.) INSTALLATION SHALL BE IN ACCORDANCE WITH ASTM D-2321.

REVISIONS		THE TMOTS	DEDADTMENT	ΛE	TRANSPORTATION
NAME	DATE	ILLINOIS	DEFARTMENT	OF	TRANSFORTATION
					P. Commercial Commerci
		VERT.			
		SCALE: HORIZ.			DRAWN BY
		DATE			CHECKED BY

OUTSIDE DROP MANHOLE CONNECTION



DROP CONNECTION REQUIRED WHERE INVERT DIFFERENTIAL IS GREATER THAN TWO FEET.