

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	I29K	WINNEBAGO	585	20
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

## AGGREGATE SCHEDULE

STATION	OFF	STATION	OFF	PAVEMENT					SHOULDERS		BREAKER-RUN CRUSHED STONE TON
				2020400 SUB-BASE GRANULAR MATERIAL, TYPE A TON	2100100 GEOTECHNICAL FABRIC FOR GROUND STABILIZATION SQ YD	3510100 AGGREGATE BASE COURSE, TYPE A 12" SQ YD	35101800 AGGREGATE BASE COURSE, TYPE B 6" SQ YD	35102000 AGGREGATE BASE COURSE, TYPE B 8" SQ YD	48100100 AGGREGATE SHOULDERS, TYPE A TON	48101200 AGGREGATE SHOULDERS, TYPE B TON	
IL 173											
142+33.00		156+00.00		1161	11688						2778
148+00.00		151+00.00									
156+00.00		170+00.00		14778	17129						722
161+00.00		162+00.00									
170+00.00		184+32.00		18018	15965						
184+32.00		197+95.00		17217	14238						
185+50.00		187+50.00									1764
191+54.00		193+03.90						187			
197+95.00		210+89.00		17494	13307						
210+89.00		231+14.00		14923	14549						
I-90											
411+08.60		482+50.00		15601							
438+53.43	RT	439+54.20	RT						2		
441+43.16	CL	441+50.99	CL						23		
441+94.82	RT	442+26.07	RT						1		
444+94.14	RT	455+57.02	RT						24		
445+32.30	LT	449+03.37	LT						8		
445+86.70	CL	446+13.35	CL						20		
449+93.90	6L62' to 195.97' LT	451+93.90	6D.77' to 202.79' LT								2833
478+86.12	RT	483+40.37	RT						10		
RAMP A											
799+90.00	RT	809+33.47	RT						320		
800+00.00		831+73.75		10353							
808+38.30	LT	831+73.75	LT						456		
816+25.55	RT	831+73.75	RT						343		
Ramp A & B											
				15534	13764						
RAMP B											
500+00.00		5025+81.91		8908							
500+51.54	RT	5009+68.57	RT						221		
500+57.76	LT	5020+10.01	LT						400		
5023+00.00	40' to 125' LT	5025+00.00	40' to 125' LT								2833
RAMP C											
4000+52.00		4002+00.00		9049	6013						
400+00.00	LT	4002+51.28	LT						40		
400+00.00	RT	4013+49.71	RT						334		
400+00.00		4019+75.00		6334							
4010+13.12	LT	4016+34.93	LT						151		
RAMP D											
1300+35.57	RT	1306+80.35	RT						172		
1300+35.57		1320+53.95		6535							
1307+56.04	LT	1320+53.95	LT						347		
1309+79.36	RT	1320+41.32	RT						284		
1320+00.00		1321+11.90		9361	6221						
STATE PARK ENTRANCE											
900+99.90		9003+47.00		7003	9308						
LYFORD ROAD											
2000+52.00		2001+71.40		7584	6720						
200+22.30	LT	2007+15.50	LT							49.9	
200+72.40	RT	2007+15.50	RT							38.6	
200+72.41		2007+15.60				1968					
2007+15.60		2010+40.40						507			
2007+15.50	RT	2010+40.40	RT							24.6	
2007+15.50	LT	2010+40.40	LT							24.6	
LYFORD ROAD NORTH											
10+50.00		11+74.30		7809	6919						
11+5.30	19' LT	17+03.00	8' RT							85.2	
11+51.60		16+98.86				4487					
151.9	19' RT	1703.0	8' LT							91.3	
16+98.00		19+90.7						539			
17+02.80	LT	19+68.29	8' LT							20.2	
17+02.80	RT	19+68.29	8' RT							20.2	
BIKEPATH											
557+68.92		596+68.22								884	
597+58.79	RT	599+00.63	RT							16.3	
597+58.79		599+00.63									
597+83.42	LT	599+00.63	LT							3.8	
TOTAL				197662	135821	6455	6272	1233	3156	1259	10930

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION  SCHEDULE OF QUANTITIES  SCALE: VERT. N/A HORIZ. N/A DATE: SEPTEMBER 14, 2005	DRAWN BY KRL CHECKED BY PDS
NAME	DATE		