STA. TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

GENERAL NOTES

1. THE MOUNTING HEIGHT FOR THE LUMINAIRES ON THE COMBINATION MASTARM ASSEMBILIES SHALL BE 35' -0" HORIZONTAL MOUNTED WITH A 12' ARM.

2. ALL TRAFFIC SIGNAL MAST ARM ASSEMBLIES (STANDARD, COMBINATION, OR DUAL) MUST BE DESIGNED FOR THE LOADING SHOWN ON THEHIGHWAY STANDARDS OR THESE SIGNAL PLANS, WHICHEVER IS GREATER.

3. THE "SIGNAL AHEAD" SIGN SHALL REPLACE THE EXISTING "INTERSECTION AHEAD" SIGN ON THE EXISTING POST LOCATION ON ALL FOUR LEGS OF THE INTERSECTION THE CONTRACTOR SHALL CONTACT KURT GLAZIER, 815-284-5478, AT THE ILLINOIS DEPARTMENT OF TRANSPORTATION ONE (1) WEEK PRIOR TO THE PLACEMENT AND LOCATION OF SIGNS.

4. THE DETECTOR LOOP CABLE FROM THE END OF THE SAW CUT TO THE SPLICE IN THE HANDHOLE SHALL BE CONSIDERED INCIDENTAL TO THE COST OF THE DETECTOR LOOP.

UTILITIES			
NAME AND ADDRESS OF UTILITY	TYPE	TELEPHONE	JULIE MEMBERF
MR CARL DONAHUE AT&T COMMUNICATIONS, INC. 866 ROCK CREEK ROAD PLANO, IL 60545	TELEPHONE	(630)-552-4677	YES 800-892-0123
MR MIKE LENOX COMMONWEALTH EDISON COMPANY 123 ENERGY AVE ROCKFORD, IL 61109	ELECTRIC	(815)-490-2869	YES 800-892-0123
MR KALIN HINSHAW VERIZON 112 WEST ELM STREET SYCAMORE, IL 60178	TELEPHONE	(815)-895-1515	YES 800-892-0123
MR SCOTT STOGSDILL NICOR GAS CO. 1844 FERRY RD NAPERVILLE, IL 60563-9600	GAS	(630)-983-8676	YES 800-892-0123

REVISIONS		ILL INOIC	DEDARTMENT	OF TRANSPORTATION		
	NAME	DATE	ILLINUIS	DEPARTMENT	U٢	TRANSPURTATION
			'			
						
		+				
	·					
-	···	 				
ļ	······································		VEDT			
-			SCALE: VERT.			DRAWN BY
			HORIZ.			
			DATE			CHECKED BY