GENERAL NOTE:

1. THE FOLLOWING REMOVAL OF EXISTING TRAFFIC SIGNAL EQUIPMENT COST SHALL INCLUDE ANY NECESSARY MATERIAL AND WORK TO REMOVE THE FOLLOWING EQUIPMENT. THE FOLLOWING EQUIPMENT SHALL BE REMOVED BY THE CONTRACTOR AND REMAIN THE PROPERTY OF THE CITY OF BELVIDERE.

2 - SIGNAL POSTS 1 - CONTROLLER CABINET

THE FOLLOWING WILL REMAIN THE PROPERTY OF IDOT

2 - FLASHER CONTROLLERS


2 - STROBE LIGHTS

ALL MATERIAL UNMENTIONED ABOVE INCLUDING JUNCTION BOXES, AND FXISTING ELECTRIC CABLE SHALL BE REMOVED BY THE CONTRACTOR AND RETAINED BY THE CONTRACTOR FOR SALVAGE. ANY REMAINING HOLES RESULTING FORM REMOVAL OR RELOCATION OF SIGNAL EQUIPMENT SHALL BE PLUGGED

THIS WORK SHALL BE PAID FOR AS REMOVAL OF TRAFFIC SIGNAL EQUIPMENT LUMP SUM.

- 2. NO WORK SHALL BE ALLOWED UNTIL ALL COMPONENTS NECESSARY TO COMPLETE THE SIGNAL INSTALLATION HAVE ARRIVED ON THE JOB SITE.
- 3. THE EXACT LOCATION OF ALL UTILITIES SHALL BE FIELD VERIFIED BY THE CONTRACTOR BEFORE ANY WORK IS STARTED.
- 4. ALL WORK ASSOCIATED WITH THE PLACEMENT OF THERMOPLASTIC PAVÉMENT MARKING SHALL BE ACCORDANCE WITH STANDARD SPECIFICATIONS ARTICLE 780 AND SHALL BE CONSIDERED INCIDENTAL TO THE PAY CODE ITEM. ONLY THE RESIDENT ENGINEER SHALL HAVE THE AUTHORITY TO RELOCATE PAVEMENT MARKING
- 5. EACH DETECTOR LOOP CABLE FROM THE END OF THE SAW CUT TO THE SPLICE IN THE HANDHOLE SHALL BE CONSIDERED INCIDENTAL TO THE COST OF THE DETECTOR LOOP.
- 6. EACH DETECTOR LOOP SHALL HAVE AN INDIVIDUAL CONDUIT STUB.
- 7. ALL DRAWS IN THESE PLANS ARE NOT TO SCALE AND ARE NOT BASED OFF OF SURVERY DATA.

LEGEND



WHETHER PUSHED OR TRENCHED

LOWER NUMERAL INDICATES SIZE OF CONDUIT

ILLINOIS DEPARTMENT OF TRANSPORTATION SCALE: VERT.