F.A.I. RTE.	SECTION	COUNTY	TOTAL	SHEET NO.
412	(50-8VB)[LASALLE	31	5
FED RO	FER BOAR DIST MO THE IMPLE			

	STRUCTURE EXCAVATION			
	NORTHBOUND	STRUCTURE		
CTACE I	NORTH ABUT	CU YD	18.4	
STAGE I	SOUTH ABUT	CU YD	18.4	
CTACE II	NORTH ABUT	CU YD	15.1	
STAGE II	SOUTH ABUT	CU YD	15.1	
SOUTHBOUND STRUCTURE				
STAGE I	NORTH ABUT	CU YD	18.4	
	SOUTH ABUT	CU YD	18.4	
CT.OF 11	NORTH ABUT	CU YD	15.1	
STAGE II	SOUTH ABUT	CU YD	15.1	
TOTAL		CU YD	134	

APPROACH SLAB REMOVAL				
	STAGE I			
NORTHBOUND	NORTH ABUT	68	SQ YD	
STRUCTURE	SOUTH ABUT	68	SQ YD	
SOUTHBOUND	NORTH ABUT	34	SQ YD	
STRUCTURE	SOUTH ABUT	34	SQ YD	
SUBTOTAL		204	SQ YD	
	STAGE II			
NORTHBOUND	NORTH ABUT	68	SQ YD	
STRUCTURE	SOUTH ABUT	68	SQ YD	
SOUTHBOUND	NORTH ABUT	34	SQ YD	
STRUCTURE	SOUTH ABUT	34	SQ YD	
SUBTOTAL		204	SQ YD	
TOTAL		408	SQ YD	

	BITUMINOUS SHOULDER REMOVAL			
	STAGE I			
NORTHBOUND	NORTH ABUT	13	SQ YD	
STRUCTURE	SOUTH ABUT	13	SQ YD	
SOUTHBOUND	NORTH ABUT	21	SQ YD	
STRUCTURE	SOUTH ABUT	21	SQ YD	
SUBTOTAL.	SUBTOTAL		SQ YD	
·	STAGE II			
NORTHBOUND	NORTH ABUT	13	SQ YD	
STRUCTURE	SOUTH ABUT	13	SQ YD	
SOUTHBOUND	NORTH ABUT	21	SQ YD	
STRUCTURE	SOUTH ABUT	21	SQ YD	
SUBTOTAL	SUBTOTAL		SQ YD	
TOTAL		136	SQ YD	

BR	BRIDGE APPROACH SHOULDER REMOVAL			
	STAGE I			
NORTHBOUND	NORTH ABUT	12	. SQ YD	
STRUCTURE	SOUTH ABUT	12	SQ YD	
SOUTHBOUND	NORTH ABUT	21	SQ YD	
STRUCTURE	STRUCTURE SOUTH ABUT		SQ YD	
SUBTOTAL		66	SQ YD	
	STAGE II			
NORTHBOUND	NORTH ABUT	12	SQ YD	
STRUCTURE	SOUTH ABUT	12	SQ YD	
SOUTHBOUND	NORTH ABUT	21	SQ YD	
STRUCTURE SOUTH ABUT		21	SQ YD	
SUBTOTAL		66	SQ YD	
TOTAL		132	SQ YD	

CONCRETE REMOVAL				
	STAGE I			
NORTHBOUND	NORTH ABUT	11	CU YD	
STRUCTURE	STRUCTURE SOUTH ABUT		CU YD	
SOUTHBOUND	SOUTHBOUND NORTH ABUT		CU YD	
STRUCTURE SOUTH ABUT		11	CU YD	
SUBTOTAL		44	· CU YD	
STAGE II				
NORTHBOUND	NORTH ABUT	9.5	CU YD	
STRUCTURE	SOUTH ABUT	9.5	CU YD	
SOUTHBOUND	NORTH ABUT	9.5	CU YD	
STRUCTURE	SOUTH ABUT	9.5	CU YD	
SUBTOTAL		38	CU YD	
TOTAL		82	CU YD	

REVISIO		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	IEEINOIS DEL MITTALLE DE LINNOS ONTATION
		SCHEDULES
		F.A.I. 412 OVER BNSF RAILROAD SECTION (50-8VB)I
		LASALLE COUNTY STA. 758 + 10
		OBANIN B

JULY 1, 2005