

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	RURAL ROADWAY 100% STATE 1000	RURAL BRIDGE 100% STATE X071-2A	RURAL SIDEWALK 50% STATE 50% LOCAL SFTY - 1B	RURAL 100% STATE SFTY - 3N
CODE NO	ITEM	UNIT					
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	30	30			
20200100	EARTH EXCAVATION	CU YD	274	274			
20300100	CHANNEL EXCAVATION	CU YD	610	610			
20400800	FURNISHED EXCAVATION	CU YD	1288	1288			
20600200	GRANULAR EMBANKMENT, SPECIAL	CU YD	2699	2699			
20700400	POROUS GRANULAR EMBANKMENT (SPECIAL)	CU YD	150		150		
20800150	TRENCH BACKFILL	CU YD	86	86			
25000110	SEEDING, CLASS 1A	ACRE	0.4	0.4			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	35	35			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	35	35			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	35	35			
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.8	0.8			
25100115	MULCH, METHOD 2	ACRE	0.4	0.4			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	39.3	39.3			
28000300	TEMPORARY DITCH CHECKS	EACH	8	8			
28000400	PERIMETER EROSION BARRIER	FOOT	400	400			
28000500	INLET AND PIPE PROTECTION	EACH	8	8			
28100109	STONE RIPRAP, CLASS A5	SQ YD	795.3	37.3	758		
28200200	FILTER FABRIC	SQ YD	795.3	37.3	758		
28400100	GABIONS	CU YD	4		4		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	413.8	413.8			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	602	602			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8.7	8.7			
40600300	AGGREGATE (PRIME COAT)	TON	45.6	45.6			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
40600990	TEMPORARY RAMP	SQ YD	729	729			
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	227	227			
42001300	PROTECTIVE COAT	SQ YD	867	867			
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	45	45			
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	522	522			
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	3269	560		2709	
42400800	DETECTABLE WARNING	SQ FT	152	8		144	
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	1020	1020			
44000100	PAVEMENT REMOVAL	SQ YD	1142	1142			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	785	785			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	34	34			