

| F.A.S. RTE. | SECTION    | COUNTY  | TOTAL SHEETS | SHEET NO. |
|-------------|------------|---------|--------------|-----------|
| 754         | 4RS-2, 4BR | CALHOUN | 87           | 5         |

SUMMARY OF QUANTITIES

| CODE NO    | ITEM                                               | UNIT   | TOTAL QUANTITIES | RURAL ROADWAY 100% STATE 1000 | RURAL BRIDGE 100% STATE X071-2A | RURAL SIDEWALK 50% STATE 50% LOCAL SFTY - 1B | RURAL 100% STATE SFTY - 3N |
|------------|----------------------------------------------------|--------|------------------|-------------------------------|---------------------------------|----------------------------------------------|----------------------------|
| 60240220   | INLETS, TYPE B, TYPE 3 FRAME AND GRATE             | EACH   | 3                | 3                             |                                 |                                              |                            |
| 60500060   | REMOVING INLETS                                    | EACH   | 1                | 1                             |                                 |                                              |                            |
| 60605000   | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24  | FOOT   | 2225             | 2225                          |                                 |                                              |                            |
| 60900330   | TYPE D INLET BOX, STANDARD 609001                  | EACH   | 2                | 2                             |                                 |                                              |                            |
| 60900515   | CONCRETE THRUST BLOCKS                             | EACH   | 2                | 2                             |                                 |                                              |                            |
| * 63000000 | STEEL PLATE BEAM GUARD RAIL, TYPE A                | FOOT   | 12.5             | 12.5                          |                                 |                                              |                            |
| * 63100045 | TRAFFIC BARRIER TERMINAL, TYPE 2                   | EACH   | 1                | 1                             |                                 |                                              |                            |
| * 63100085 | TRAFFIC BARRIER TERMINAL, TYPE 6                   | EACH   | 4                | 4                             |                                 |                                              |                            |
| * 63100167 | TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT) | EACH   | 3                | 3                             |                                 |                                              |                            |
| 63200310   | GUARDRAIL REMOVAL                                  | FOOT   | 139              | 139                           |                                 |                                              |                            |
| 66300105   | CALCIUM CHLORIDE APPLIED                           | TON    | 4                | 4                             |                                 |                                              |                            |
| * 66900200 | NON-SPECIAL WASTE DISPOSAL                         | CU YD  | 170              | 170                           |                                 |                                              |                            |
| * 66900450 | SPECIAL WASTE PLANS AND REPORT                     | L SUM  | 1                | 1                             |                                 |                                              |                            |
| * 66900530 | SOIL DISPOSAL ANALYSIS                             | EACH   | 2                | 2                             |                                 |                                              |                            |
| * 66901000 | BACKFILL PLUGS                                     | CU YD  | 5                | 5                             |                                 |                                              |                            |
| 67000400   | ENGINEER'S FIELD OFFICE, TYPE A                    | CAL MO | 18               | 18                            |                                 |                                              |                            |
| 67100100   | MOBILIZATION                                       | L SUM  | 1                | 1                             |                                 |                                              |                            |
| 70100405   | TRAFFIC CONTROL AND PROTECTION, STANDARD 701321    | EACH   | 1                | 1                             |                                 |                                              |                            |
| 70100460   | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306    | L SUM  | 1                | 1                             |                                 |                                              |                            |
| 70100500   | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326    | L SUM  | 1                | 1                             |                                 |                                              |                            |
| 70101800   | TRAFFIC CONTROL AND PROTECTION (SPECIAL)           | L SUM  | 1                | 1                             |                                 |                                              |                            |
| 70103815   | TRAFFIC CONTROL SURVEILLANCE                       | CAL DA | 200              | 200                           |                                 |                                              |                            |
| 70300100   | SHORT-TERM PAVEMENT MARKING                        | FOOT   | 936              | 936                           |                                 |                                              |                            |
| 70300220   | TEMPORARY PAVEMENT MARKING - LINE 4"               | FOOT   | 6125             | 6125                          |                                 |                                              |                            |
| 70300240   | TEMPORARY PAVEMENT MARKING - LINE 6"               | FOOT   | 700              | 700                           |                                 |                                              |                            |
| 70300260   | TEMPORARY PAVEMENT MARKING - LINE 12"              | FOOT   | 90               | 90                            |                                 |                                              |                            |
| 70301000   | WORK ZONE PAVEMENT MARKING REMOVAL                 | SQ FT  | 3074             | 3074                          |                                 |                                              |                            |
| 70400100   | TEMPORARY CONCRETE BARRIER                         | FOOT   | 630              | 630                           |                                 |                                              |                            |
| 70400200   | RELOCATE TEMPORARY CONCRETE BARRIER                | FOOT   | 280              | 280                           |                                 |                                              |                            |
| * 72400500 | RELOCATE SIGN PANEL ASSEMBLY - TYPE A              | EACH   | 7                | 7                             |                                 |                                              |                            |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4"           | FOOT   | 4354             | 4354                          |                                 |                                              |                            |

PLOT DATE = 9/19/2005  
FILE NAME = c:\projects\volan\final-revision.dgn  
PLOT SCALE = 50000' / IN.  
REFERENCE = SHEET 5