

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
754	4RS-2, 4BR	CALHOUN	87	10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 76269

BITUMINOUS PAVING SCHEDULE		BITUMINOUS MATERIALS, (PRIME COAT)	AGGREGATE (PRIME COAT)	BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE, IL-19.0 N50, 1 1/2" DEPTH	BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE, MIX "C" N50, 2" - 2 1/4" DEPTH
STATION to	STATION	TON	TON	TON	TON
0+38.1	3+05.8	1.814	9.550		118.6
3+05.8	5+31.0	1.966	10.347	419.0	75.9
6+86.0	12+90.0	3.850	20.267	1140.4	187.2
18+20.0	19+60.0		5.459	254.1	50.9
TOTAL		8.700	45.600	1,813.5	433

APPROACH PAVEMENT DRAIN SCHEDULE		CONCRETE THRUST	PIPE DRAINS 12"	METAL END SECTIONS	TYPE D INLET BOX STANDARD 609001 EACH
STATION	SIDE	EACH	FOOT	EACH	
5+49.5	RT.	1	24	1	1
5+57.5	LT.	1	23	1	1
TOTAL		2	47	2	2

SIDEWALK SCHEDULE			PCC SIDEWALK 4 INCH	SIDEWALK REMOVAL
STATION TO	STATION	SIDE	SQ FT	SQ FT
2+75		LT.	24	24
3+09	3+53	LT.	250	19
3+16		RT.	11.8	
4+11	4+32	LT.	80	
4+57	4+95	LT.	160	
5+19	5+72	LT.	250	
6+56	7+62	LT.	525	
7+98	8+16	LT.	70	
8+70	9+08	RT.	194	
9+33	10+08	RT.	345	
10+18	11+04	RT.		258
10+33	11+10	RT.	465	
11+22	11+72	RT.	225	
11+24	11+60	RT.		108
11+84	12+33	RT.	142	
11+93	12+13	RT.		
19+10	19+66	RT.	375	60.9
8+70.30		RT.	20	
9+81.10		RT.	50	
10+83.60		RT.	50	48
11+45.80		RT.	45	42
TOTAL			3,269	560

DETECTABLE WARNING SCHEDULE		DETECTABLE WARNING
STATION	SIDE	SQ FT
2+75	LT.	8
3+09	LT.	8
3+16	RT.	8
3+53	LT.	8
4+11	LT.	8
4+32	LT.	8
4+57	LT.	8
4+95	LT.	8
5+19	LT.	8
7+62	LT.	8
7+98	LT.	8
8+16	LT.	8
8+54	LT.	8
8+63	LT.	8
8+78	RT.	8
9+08	RT.	8
9+33	RT.	8
10+08	RT.	8
10+33	RT.	8
TOTAL		152

CURB & GUTTER SCHEDULE			COMBINATION CURB & GUTTER REMOVAL	COMBINATION CURB & GUTTER TYPE B-6.24	
STATION to	STATION	SIDE	FOOT	FOOT	COMMENTS
3+04	3+23	LT.		28	RETURN
3+06		LT.	26		
3+06		RT.	8		
3+14	3+36	RT.		40	RETURN
3+23	5+41	LT.		214	
3+36	5+33	RT.		203	
6+75	12+90	RT.		610	
6+85	8+50	LT.		170	
9+43	12+90	LT.		347	
18+45	19+30	LT.		85	N. COUNTY ROAD
18+45	19+35	RT.		90	N. COUNTY ROAD
19+30	19+95	LT.		72	N. COUNTY ROAD (RETURN)
19+35	19+65	RT.		61	N. COUNTY ROAD (RETURN)
TOTAL			34	1,920	

TEMPORARY RAMP SCHEDULE			TEMPORARY RAMP
STATION TO	STATION	SIDE	SQ YD
3+05.8	3+37.5	RAMP 1	119.0
5+05.3	5+37.0	RAMP 1	91.6
6+80.0	7+11.7	RAMP 1	91.6
12+58.3	12+90.0	RAMP 1	91.6
3+05.8	3+24.1	RAMP 2	79.0
5+18.0	5+37.0	RAMP 2	53.2
6+80.0	6+98.4	RAMP 2	53.2
12+71.6	12+90.0	RAMP 2	53.2
3+05.8	3+12.5	RAMP 3	38.4
5+30.3	5+37.0	RAMP 3	19.4
6+80.0	6+86.7	RAMP 3	19.4
12+83.3	12+90.0	RAMP 3	19.4
TOTAL			729.0

ENTRANCE SCHEDULE				DRIVEWAY PAVEMENT REMOVAL	AGGREGATE SURFACE COURSE 6" DEPTH	PCC DRIVEWAY PAVEMENT 6" DEPTH	COMBINATION CURB & GUTTER TYPE B-6.24
STATION	TYPE	SIDE	MATL.	SQ YD	TON	SQ YD	FOOT
3+63	CE	RT.	CONC.			42.7	20.0
3+82	PARKING AREA	LT.	CONC.			101.6	24.0
4+54	CE	LT.	CONC.	105		105	26.0
5+07	CE	LT.	CONC.	74.4		74.4	24.0
7+40	CE	RT.	CONC. BIT.	67.8	20.0	8.9	17.0
7+80	CE	LT.	CONC. BIT.		10.9	50.8	40.0
8+34	CE	LT.	CONC. BIT.		11.2		38.0
9+14	CE	RT.	CONC. AGG.		43.5	48.4	26.0
10+14	CE	RT.	CONC. AGG.		28.3	25.0	26.0
11+16	PE	RT.	CONC. AGG		1.3	25.0	24.0
11+78	PE	RT.	CONC.			15.2	22.0
19+41	PE	LT.	CONC. AGG.		23.6	15.2	18.0
8+34.30	PARKING AREA	LT.	CONC. AGG.		86.7	9.4	
9+13.54	PARKING AREA	RT.	CONC. AGG.		266.6		
10+13.87	PARKING AREA	RT.	CONC. AGG.		107.1		
TOTAL				247.2	601.7	522	305.0

CONCRETE STAIR SCHEDULE		CONCRETE	REINFORCEMENT BARS	PIPE HANDRAIL
STATION to	STATION	CU YD	POUND	FOOT
8+72	RT.	0.62	33	12
9+83.1	RT.	0.53	30	12
10+83.6	RT.	0.26	15	
11+45.8	RT.	0.17	12	
TOTAL		1.58*	90*	24

* SHOWN FOR INFORMATION ONLY,
ALL LOCATIONS PAID FOR AS
"CONCRETE STAIRS", 1 LUMP SUM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
F.A.S. ROUTE 754 (IL 100/Park St.)
SECTION 4RS-2, 4BR
CALHOUN COUNTY

DRAWN BY WJS
DATE MAY, 2004
CHECKED BY LLO

Rev. 11-4-05