

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
754	4RS-2, 4BR	CALHOUN	87	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 76269

SEEDING SCHEDULE		SEEDING CLASS 1A	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH METHOD 2	TEMPORARY EROSION CONTROL SEEDING
	SIDE	ACRE	ACRE	ACRE	ACRE	TON	ACRE	ACRE
PARK STREET								
3+50.8	3+55	LT	0.0028	0.252	0.252	0.005	0.0028	0.0028
4+11	4+33	LT	0.0069	0.621	0.621	0.014	0.0069	0.0069
4+47	4+80	LT	0.0083	0.747	0.747	0.017	0.0083	0.0083
4+80	4+96	LT	0.0063	0.567	0.567	0.013	0.0063	0.0063
5+19	5+72	LT	0.0149	1.341	1.341	0.030	0.0149	0.0149
6+72	7+67	LT	0.0399	3.591	3.591	0.080	0.0399	0.0399
7+93	8+21	LT	0.0031	0.279	0.279	0.018	0.0031	0.0031
8+45	8+72	LT	0.0088	0.792	0.792	0.006	0.0088	0.0088
9+22	10+80	LT	0.0697	6.273	6.273	0.139	0.0697	0.0697
10+80	12+90	LT	0.0092	0.828	0.828	0.018	0.0092	0.0092
3+05	4+80	RT	0.0066	0.594	0.594	0.013	0.0066	0.0066
3+72	3+48	RT	0.0224	2.016	2.016	0.045	0.0224	0.0224
4+80	5+67	RT	0.0237	2.133	2.133	0.047	0.0237	0.0237
6+55	7+33	RT	0.0245	2.205	2.205	0.049	0.0245	0.0245
7+48	8+70	RT	0.0410	3.690	3.690	0.083	0.0410	0.0410
8+77	9+22	RT	0.0154	1.386	1.386	0.031	0.0154	0.0154
9+33	9+81	RT	0.0218	1.962	1.962	0.044	0.0218	0.0218
9+86	10+18	RT	0.0095	0.855	0.855	0.019	0.0095	0.0095
10+32	10+80	RT	0.0131	1.179	1.179	0.026	0.0131	0.0131
10+83	11+10	RT	0.0050	0.450	0.450	0.010	0.0050	0.0050
11+22	11+73	RT	0.0032	0.288	0.288	0.006	0.0032	0.0032
11+84	12+90	RT	0.0066	0.594	0.594	0.013	0.0066	0.0066
NO. COUNTY RD.								
18+20	19+40	LT	0.0200	1.800	1.800	0.041	0.0200	0.0200
18+20	19+61	RT	0.0080	0.720	0.720	0.016	0.0080	0.0080
TOTAL			0.40	35.0	35.0	0.80	0.40	0.40

DRAINAGE AND STORM SEWER SCHEDULE			STORM SEWERS CLASS A, TYPE 1 12" DIA. FOOT	STORM SEWERS CLASS A, TYPE 1 15" DIA. FOOT	STORM SEWERS CLASS A, TYPE 1 18" DIA. FOOT	STORM SEWERS TYPE 1, WATER MAIN QUALITY 12" DIA. FOOT	STORM SEWERS TYPE 1, WATER MAIN QUALITY 15" DIA. FOOT	STORM SEWERS TYPE 2, WATER MAIN QUALITY 18" DIA. FOOT	INLETS, TY A TYPE 8 GRATE EACH	INLETS, TY A, TY 3 FRAME & GRATE EACH	INLETS, TY B, TY 3 FRAME & GRATE EACH	PRECAST REINF. CONC. FLARED END SECTION 18" DIA. EACH	PIPE CULVERTS CLASS D, TYPE 1 12" FOOT	TRENCH BACKFILL CU YD	METAL END SECTIONS 12" EACH	CONCRETE COLLAR EACH
STATION	to STATION	SIDE														
4+85		LT.							1							
4+85	5+80	LT.		94										9.2		
6+36	7+04.15	RT.	64											25.8		
6+49	7+04.15	LT.	54											25.8		
7+04.15		LT. & RT.								2						
7+10	7+55	RT.											45		2	
18+70.5		RT.								1						
18+70.5		LT. TO RT.				22								3.2		
18+70.5		LT.									1					
18+70.5	19+78.7	LT.					110							13.6		
19+35.7	19+60.7	LT.											25	3.8	2	
19+78.7		LT.									1					
19+78.7	19+80	LT.	12													
19+80		LT.							1							
19+78.7	20+20	LT.						40						4.2		
20+20		LT.									1					
20+20	20+40	LT.						20								
20+40		LT.														1
20+40	21+30.7	LT.			97											
20+30.7		LT.										1				
TOTAL			130	94	97	22	110	60	2	3	3	1	70	86	4	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
F.A.S. ROUTE 754 (IL 100/Park St.)
SECTION 4RS-2, 4BR
CALHOUN COUNTY
DRAWN BY WJS
DATE MAY, 2004
CHECKED BY LLQ

Rev. 11-4-05