



0' 10' 20'

SCALE: 1"= 20'-0"




OUTDOOR SUBSTATION PLAN @ EL. 422.0




SECTION COUNTY 70 82-(1,2)T-17 ST. CLAIR 77 45 FED. ROAD DIST. NO. | LLINGIS FED. AID PROJECT

GENERAL NOTES:

- 1. THE CONTRACTOR SHALL VISIT THE SITE IN ORDER TO FAMILIARIZE THEMSELVES WITH THE CONDITIONS UNDER WHICH THEY WILL PERFORM THE WORK.
- THE CONTRACTOR SHALL INCLUDE DISCONNECTION AND REMOVAL OF ALL RELATED ELECTRICAL EQUIUPMENT, CABLE, CONDUIT AND APPURTENENANCES AS PART OF THEIR DEMOLITION WORK.
- 3. ALL MATERIALS, EQUIPMENT & APPURTENANCES NOT SPECIFICALLY IDENTIFIED BUT WHICH REQUIRE REMOVAL FOR COMPLETION OF THE REQUIRED WORK SHALL BE REMOVED AT NO ADDITIONAL COST TO THE OWNER.
- 4. EXISTING ELECTRICAL SERVICE FEEDERS SHALL BE REMOVED BY THE CONTRACTOR, ALL OTHER ELECTRIC SERVICE EQUIPMENT OWNED BY AMEREN UE SHALL BE REMOVED BY THEM. THE CONTRACTOR SHALL COORDINATE WITH AMEREN UE.
- 5. ALL CONDUIT OPENINGS SHALL BE SEALED, FOR PATCHING REDUIREMENTS SEE SPECIFICATION SECTION 1A.
- 6. ALL SOLID STATE REDUCED VOLTAGE STARTERS FOR SWP-1 THROUGH SWP-6, SSP-1 & SSP-2 SHALL BE REMOVED AND REINSTALLED IN THE NEW MCC'S.
- 7. THE FOLLOWING EQUIPMENT SHALL BE SALVAGED:
 - A. HEALY-RUFF PUMP CONTROL PANEL
 - B. SOLID STATE MOTOR STARTERS AND THERMAL/ SEAL PROTECTION MODULES AS NOTED ON SH. 46.
 - C. SUMP PUMP NO. 1
 - D. ONAN ATS AND ZENITH ATS.
- * DENOTES EXISTING ELECTRICAL TO REMAIN.
- DENOTES EXISTING ELECTRICAL TO BE RELOCATED.
- A DENOTES EXISTING ELECTRICAL TO BE REMOVED.
- DENOTES EXISTING ELECTRICAL TO BE SALVAGED.







ILLINOIS DEPARTMENT OF TRANSPORTATION

BOWMAN AVENUE PUMP STATION REHABILITATION ELECTRICAL

DEMOLITION PLANS SH. 1

DATE: 09-12-05

DRAWN BY: LMJ CHECKED BY: KCC

PLOT DATE: *DATE ~TIME*

ALVORD, BURDICK & HOWSON, L.L.C. **ENGINEERS**