

**INDEX OF SHEETS**

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	TYPICAL SECTIONS
5	SUE INVESTIGATION OF UNDERGROUND UTILITIES
6-10	ROADWAY AND DRAINAGE PLANS
11	EROSION CONTROL AND SEDIMENT CONTROL PLAN
12-18	CROSS SECTIONS
19	TEMPORARY INFORMATION SIGNING

**STANDARDS**

000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
280001-05	TEMPORARY EROSION CONTROL SYSTEMS
602001-02	CATCH BASIN, TYPE "A"
602401-03	MANHOLE, TYPE "A"
701006-03	OFF ROAD OPERATIONS 2L, 2W, 15' TO PAVEMENT EDGE FOR SPEEDS GREATER THAN OR EQUAL TO 45 MPH
701201-04	LANE CLOSURES, 2L, 2W DAY ONLY ON RD. TO 24" OFF RD. FOR SPEEDS GREATER THAN OR EQUAL TO 45 MPH
701901-01	TRAFFIC CONTROL DEVICES

**GENERAL NOTES**

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOURS NOTIFICATION REQUIRED).
- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE VILLAGE OF BOLINGBROOK
- THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
- THE RESIDENT ENGINEER SHALL CONTACT LAWRENCE HILL AREA TRAFFIC FIELD ENGINEER AT (815) 485-6475 AT LEAST TWO(2) WEEKS PRIOR TO INSTALLATION OF FINAL PAVEMENT MARKING.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTION OF ALL OVERHEAD, SURFACE AND UNDERGROUND UTILITIES WITHIN THE PROJECT LIMITS WHETHER OR NOT THE UTILITIES ARE SHOWN ON THE PLANS. ANY UTILITY THAT IS DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED BY THE CONTRACTOR AT HIS OWN EXPENSE.
- EXISTING SEWER LOCATIONS SHOWN ARE FROM AVAILABLE INFORMATION. CONTRACTOR SHALL FIELD VERIFY ALL LOCATIONS.
- THE RESIDENT ENGINEER SHOULD CONTACT TRAFFIC CONTROL SUPERVISOR AT (847)705-4470 @ LEAST 72 HOURS PRIOR TO PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.

FILE NAME =	USER NAME = lsgaa	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>I-55 EAST OF IL 53 INDEX OF SHEETS, STANDARDS, AND GENERAL NOTES</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw\work\pw\dot\lsgaa\dms89282\010740	shl-drain.dgn	DRAWN -	REVISED -		55	29T-1	WILL	19	2				
PLOT SCALE = 50.0000' / in.	CHECKED -	REVISED -	REVISED -		CONTRACT NO. 60A56								
PLOT DATE = 8/29/2011	DATE -	REVISED -	REVISED -		SCALE: 1"=50'	SHEET NO. 2 OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			