SUMMARY OF QUANTITIES

80%. FED. /20%. STATE	
CONSTRUCTION TYPE COD	<u> </u>

				CONS	E CODE		
CODED PAY ITEM NUMBER	PAY ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0003	MINOR STRUCTURES 0040	LANDSCAPII G 0031	
88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1	1			
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	4	4			
88600700	PREFORMED DETECTOR LOOP	FOOT	76	76			
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	1			
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	185	185			
89502380	REMOVE EXISTING HANDHOLE	EACH	1	1			
A2002520	TREE, CARPINUS CAROLINIANA (AMERICAN HORNBEAM), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	3	· · · · · · · · · · · · · · · · · · ·		3	
A2002566	TREE, CARPINUS CAROLINIANA (AMERICAN HORNBEAM), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	5			5	
A2005020	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2-1/2" CALIPER,	EACH	4			4	
	BALLED AND BURLAPPED						
A2005556	TREE, NYSSA SYLVATICA (BLACK TUPELO), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	3			3	
A2005670	TREE, OSTRYA VIRGINIANA (AMERICAN HOPHORNBEAM), 8' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	3			3	
A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER,	EACH	7			7	
	BALLED AND BURLAPPED						
A2006568	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 7' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	3			3	
A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER,	EACH	3			3	
A2007620	BALLED AND BURLAPPED TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 2-1/2" CALIPER,	EACH	5			5	
A2001020	BALLED AND BURLAPPED	LACIT	3			J J	
B2000766	TREE, AMELANCHIER X GRANDIFLORA AUTUMN BRILLIANCE (AUTUMN BRILLIANCE SERVICE BERRY), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED		7			7	
B2001464	TREE, CORNUS MAS (CORNELIAN CHERRY DOG WOOD), 5' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED		5			5	
B2002216	TREE, CRATAEGUS VIRDIS WINTER KING (WINTER KING GREEN HAWTHORN), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED		5			5	
B2002364	TREE, HALESIA TETRAPTERA (CAROLINA SILVERBELL), 5' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	5			5	
		= 1.011					
C2003248	SHRUB, HAMAMELIS VERNALIS (VERNAL WITCH HAZEL), 4' HEIGHT, BALLED AND BURLAPPED	EACH	19			19	
C2003348	SHRUB, HAMAMELIS VIRGINIANA (COMMON WITCHHAZEL), 4' HEIGHT,	EACH	5			5	
C2C09636	BALLED AND BURLAPPED SHRUB, SAMBUCUS CANADENSIS (AMERICAN ELDER), 3' HEIGHT, CONTAINER	EACH	14			14	
D2002184	EVERGREEN, PICEA PUNGENS (COLORADO SPRUCE), 7' HEIGHT,	EACH	15			15	
D2002472	BALLED AND BURLAPPED EVERGREEN, PINUS FLEXILIS VANDERWOLF'S PYRAMID (VANDERWOLF'S PYRAMID LIMBER PINE), 6' HEIGHT, BALLED AND BURLAPPED		6			6	
D2002484	EVERGREEN, PINUS FLEXILIS VANDERWOLF'S PYRAMID (VANDERWOLF'S PYRAMID LIMBER PINE), 7' HEIGHT, BALLED AND BURLAPPED	EACH	6			6	
D2002772	EVERGREEN, PINUS NIGRA (AUSTRIAN PINE), 6' HEIGHT,	EACH	6			6	
	BALLED AND BURLAPPED						

CODED PAY ITEM NUMBER	PAY ITEM	UNIT	URBAN TOTAL QUANTITIES	ROADWAY 0003	MINOR STRUCTURES 0040	LANDSCAPIN G 0031
D2002784	EVERGREEN, PINUS NIGRA (AUSTRIAN PINE), 7' HEIGHT,	EACH	6			6
	BALLED AND BURLAPPED					
X0301852	DEWATERING STRUCTURE NO. 1	EACH	1		1	
X0301853	DEWATERING STRUCTURE NO. 2	EACH	1		1	
X0322453	WEED CONTROL, PRE-EMERGENT	POUND	300			300
X0426200	DEWATERING	L SUM	1	1		
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	572		572	
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	6	6	-	
X5121800	PERMANENT STEEL SHEET PILING	SQ FT	65504		65504	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		
X7030025	WET REFLECTIVE TEMPORARY TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	109	109		
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	47821	47821		
X7030040	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	FOOT	966	966		
X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	137	137		,
X5400100	BOX CULVERT REMOVAL	FOOT	51	51		
Z0030352	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	6	6		
Z0030251	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	6	6		
om 555 15 755	AGGREGATE SUBGRADE (SPECIAL)	SQ YD	40411	40411		
20001070	AGGREGATE SUBGRADE (SPECIAL)	30 10	40411	40411		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0022800	FENCE REMOVAL	FOOT	849	849		
Z0026407	TEMPORARY SHEET PILING	SQ FT	12,895	12,895		
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	124	124		
Z0033060	PREFORMED DETECTOR LOOP	FOOT	76	76		
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	9561	9561		
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	1919		1919	and the second s
	TEMPORARY CONSTRUCTION FENCE	FOOT	2817	2817		
Z0062456	TEMPORARY PAVEMENT	SQYD	8136	8136		
70073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1	1	1	1

80% FED. 20 1. STATE
CONSTRUCTION TYPE CODE

FILE NAME = ...\D16ØI35-sht-S0G3.dgn



DESIGNED	RJD	REVISED -
DRAWN	MHL	REVISED -
CHECKED	RJD	REVISED -
DATE	JUNE 30, 2011	REVISED -

								700	2 Y / I
	IL RTE 62 (A	LGONQUIN RD.) FROM EA	STING'S	WAY TO PENNY RD.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	SUMMARY OF QUANTITIES					116 Y-1-R-1	COOK	122	6
							CONTRAC	T NO.	60135
	SCALE: N.T.S.	SHEET NO. 3 OF 3 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				