

COPYRIGHT © 2010 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS PROFESSIONAL DESIGN FIRM
 5227 KIM
 1/25/2010
 ...\\dot\proj\w05\0229\424.dwg
 I:\C:\781st\l\l\DOT\100053\40-Design\W05\CADDD-SURVEY\DRAWINGS\DCNS\00053_#05-500.sht



DESIGNED -	DJS	REVISED -	1-28-11 PER IDOT REVIEW
DRAWN -	CJC	REVISED -	3-14-11 PER IDOT REVIEW
CHECKED -	LDH	REVISED -	
DATE -	09/10/10	FILE -	100153.W05-S00.sht

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL ROUTE 31 - AMES ROAD TO EDGEWOOD ROAD
SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
336	2010-049-N	MCHENRY	50	5
FED. ROAD DIST. NO. 1 ILLINOIS			CONTRACT NO. 60L25	

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE 90% FED. / 10% STATE	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0021 QUANTITY	
70300240	TEMPORARY PAVEMENT MARKING- LINE 6"	FOOT	1,900	1,900	
70300260	TEMPORARY PAVEMENT MARKING- LINE 12"	FOOT	628	628	
70300280	TEMPORARY PAVEMENT MARKING- LINE 24"	FOOT	186	186	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	7,066	7,066	
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	2	2	
* 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	10	10	
* 72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	1	1	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	276	276	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14,472	14,472	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	950	950	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	314	314	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	50	50	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	152	152	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	360	360	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	79	79	
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	5,626	5,626	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
△ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	10	10	
Z0022800	FENCE REMOVAL	FOOT	330	330	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	167	167	
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	209	209	
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	150	150	
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	22	22	
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	1	1	
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	2	2	
X4024000	TEMPORARY ACCESS (FIELD ENTRANCE)	EACH	1	1	
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	925	925	
X7030025	WET REFLECTIVE TEMPORARY TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	552	552	
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	42,944	42,944	
X7030040	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	FOOT	1,900	1,900	
X7030050	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	FOOT	186	186	
X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	7,066	7,066	
XX007391	PRECAST CONCRETE BOX CULVERT EXTENSION	FOOT	27	27	

* INDICATES SPECIALTY ITEM
 △ Non-Pact (100% SURE)

SCALE: _____ STA. _____ TO STA. _____