

m:\p\03598.00\design\misc\sheet\03598.00.03-50002.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				URBAN - 80% FEDERAL, 20% STATE		100% VILLAGE
				ROADWAY 0004	STRUCTURAL 0014	LIGHTING 0021
70400100	TEMPORARY CONCRETE BARRIER	FOOT	625	625		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	600	600		
• 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	36	36		
• 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	6,794	6,794		
• 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	165	165		
• 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FT	124	124		
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	103	103		
• 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	38	38		
• 78200530	BARRIER WALL MARKERS, TYPE C	EACH	100	100		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,510	2,510		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	141	141		
• 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1		
81000500	CONDUIT IN TRENCH, 1 1/2" DIA., GALVANIZED STEEL	FOOT	85	85	1	
• 81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	670	670		
• 81100510	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., PVC COATED GALVANIZED STEEL	FOOT	630			630
• 81100805	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL	FOOT	10			10
• 81300320	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 8" X 8" X 6"	EACH	9	6		3
• 81300810	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" X 12" X 8"	EACH	3	1		2
• 81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	280			280
• 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	2,500	2,500		
• 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	1,920			1,920
• 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	345	85		280 1
• 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	4			4
• 82200605	WATERWAY OBSTRUCTION WARNING LUMINAIRE, LED	EACH	6	6		
• 83008500	LIGHT POLE, ALUMINUM, 40 FT. M.H., 12 FT. MAST ARM	EACH	1			1

• DENOTES SPECIALTY ITEM

				CONSTRUCTION CODE		
				URBAN - 80% FEDERAL, 20% STATE		100% VILLAGE 0021
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0004	STRUCTURAL 0014	LIGHTING
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	100	100		
* Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	5			5
Z0053800	RIVET REMOVAL AND REPLACEMENT	EACH	240		240	
Z0062456	TEMPORARY PAVEMENT	SO YD	74	74		
X8260112	MAINTENANCE OF NAVIGATION LIGHTING SYSTEM	CAL MO	5	5		
X8110553	CONDUIT, FLEXIBLE NON-METALLIC, WEATHERPROOF, 1.5" DIAMETER	FOOT	100	5		95
X8110567	CONDUIT, FLEXIBLE METALLIC, WEATHERPROOF, 2.5"	FOOT	5	5		
* X8100055	CONDUIT IN TRENCH, 1 1/2" DIA. PVC COATED, GALVANIZED STEEL	FOOT	85	85		
X8110509	CONDUIT, FLEXIBLE METALLIC, WEATHERPROOF, 3"	FOOT	10			10

• DENOTES SPECIALTY ITEM

m:\p\c\103542.dgn\design\misc\sheets\0356\0003-50204.dgn

ENGINEERING CONSULTANT



Clorba Group, Inc.
CONSULTING ENGINEERS
6507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.776.4008 Fax 773.776.4014
Email: cclorba@clorba.com

USER NAME = wlancester	DESIGNED - JMV	REVISED -
	DRAWN - JMK	REVISED -
PLOT SCALE = 1.0000" / IN.	CHECKED - JMV	REVISED -
PLOT DATE = 9/9/2011	DATE - 9/2/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ILL. 50 OVER THE CAL SAG CHANNEL
STRUCTURE NO. 016-0421
SUMMARY OF QUANTITIES

SCALE: 1" = 20'

SHEET NO. OF SHEETS STA. TO STA.

Rev. 11-7-11

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	3068 A-B-R-1	COOK	57	6

CONTRACT NO. 60N88

ILLINOIS FED. AID PROJECT