INDEX OF SHEETS LIST OF STATE STANDARDS SHEET NO. DESCRIPTION STANDARD NO. DESCRIPTION COVER SHEET 701400*-05* APPROACH TO LANE CLOSURE. INDEX OF SHEETS, LIST OF STATE FREEWAY/EXPRESSWAY STANDARDS AND GENERAL NOTES SUMMARY OF QUANTITIES 701401-*0*6 LANE CLOSURE, FREEWAY/EXPRESSWAY SITE PLAN SUGGESTED STAGE IA CONSTRUCTION 701411**-07** LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS > 45 MPH SUGGESTED STAGE IB CONSTRUCTION SUGGESTED STAGE II CONSTRUCTION LANE CLOSURE, MULTILANE, FOR SPEEDS 701422**-03** 8 SUGGESTED STAGE IIIA CONSTRUCTION >= 45 MPH TO 55 MPH 9 SUGGESTED STAGE IIIB CONSTRUCTION 701446-02 TWO LANE CLOSURE FREEWAY/EXPRESSWAY DETOUR PLAN - STAGE IIIB 11 DETOUR PLAN - STAGE IIIB 701901-01 TRAFFIC CONTROL DEVICES S.N. 016-0036 704001**-06** TEMPORARY CONCRETE BARRIER 12 GENERAL PLAN & ELEVATION 13 DECK CONCRETE PATCHING 780001-02 TYPICAL PAVEMENT MARKINGS 13A PIER E12 REPAIRS S.N. 016-1045 14 GENERAL PLAN & ELEVATION 15 DECK CONCRETE PATCHING 16 PIER ES3 REPAIRS 17 PIER ES6 REPAIRS 18 PIER ES7 REPAIRS S.N. 016-1048 19 GENERAL PLAN & ELEVATION 20 DECK CONCRETE PATCHING S.N. 016-1052 21 GENERAL PLAN & ELEVATION

S.N. 016-1075 25 GENERAL PLAN & ELEVATION 26 DECK CONCRETE PATCHING

27 PIER E15 REPAIRS

S.N. 016-1055

22 DECK CONCRETE PATCHING

23 GENERAL PLAN & ELEVATION 24 DECK CONCRETE PATCHING

- 28 PIER E16 REPAIRS
- 29 BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS
- 30 EXISTING PLANS PIERS ES1, ES2 & ES3
- 31 EXISTING PLANS PIER ES6
- 32 EXISTING PLANS PIER ES7
- 33 EXISTING PLANS PIER E12
- 34 EXISTING PLANS PIERS E14 & E15
- 35 EXISTING PLANS PIERS E16 & E17
- 36 FREEWAY ENTRANCE AND EXIT RAMP CLOSURE DETAIL
- 37 TRAFFIC CONTROL DETAILS FOR FREEWAY SINGLE & MULTI-LANE WEAVE
- 38 TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES
- 39 TRAFFIC CONTROL DETAILS FOR FREEWAY CENTER LANE CLOSURE SHOULDER LANE
- 40 MULTI-LANE FREEWAY PAVEMENT MARKING DETAILS
- 41 MULTI-LANE FREEWAY PAVEMENT MARKING DETAILS

GENERAL NOTES:

- 1. THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM I.D.O.T. FIELD MAINTENANCE ENGINEERS.
- 2. THE CONTRACTOR MUST USE EXTREME CAUTION DURING FULL DEPTH DECK SLAB REPAIR AND MUST NOT NICK, CUT OR DAMAGE, IN ANY WAY, ANY OF THE STEEL BEAMS. THE EXISTING REINFORCEMENT BARS SHALL BE CLEANED. IF ANY OF THESE REINFORCEMENT BARS ARE DAMAGED THEY MUST BE REPLACED WITH AN APPROVED BAR SPLICER OR ANCHORAGE SYSTEM. THE COST OF THIS WORK IS INCLUDED WITH DECK SLAB REPAIR (FULL DEPTH, TYPE II).
- 3. THE CONTRACTOR SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4151 AT LEAST 72 HOURS PRIOR TO INSTALLATION OF THE TEMPORARY TRAFFIC CONTROL DEVICES.
- 4. THERE ARE ELECTRICAL CONDUITS AND/OR FIBERGLASS DRAIN PIPES ATTACHED TO THE BOTTOM OF THE BRIDGE DECK, THE CONTRACTOR MAY MODIFY THE FORMING AND MUST EXERCISE EXTREME CAUTION DURING FULL DEPTH REPAIR BREAK OUT AND SHALL TEMPORARILY SUPPORT THE CONDUITS AND/OR DRAIN PIPES IF NEED BE, AT NO ADDITIONAL COST TO THE DEPARTMENT.
- 5. WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR MUST EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC.
- 6. PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF THE WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED BASED UPON THE UNIT PRICE BID FOR THE WORK.
- 7. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL C.U.A.N. AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES (48 HOURS NOTIFICATION IS REQUIRED).
- 8. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
- 9. TO COORDINATE ACCESS TO THE McCORMICK PLACE PARKING LOT CALL EUGENE HARTISON AT (312) 791-6081.
- 10. DURING ANY WORK WITHIN THE MCCORMICK PLACE PARKING LOT, THE CONTRACTOR MUST COORDINATE WITH THE MCCORMICK PLACE PARKING LOT AUTHORITY AS TO AVOID ANY AND ALL CONFLICTS DURING THIS CONTRACT.
- 11. DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.
- 12. ANY DAMAGES TO THE CONDUITS OR PIPES CAUSED BY THE CONTRACTOR'S OPERATIONS SHALL BE REPLACED OR REPAIRED BY THE CONTRACTOR AT HIS/HER EXPENSE.
- 13. ALL PROPOSED RAISED REFLECTIVE PAVEMENT MARKERS (BRIDGE) SHALL BE LOW PROFILE.
- 14. THE CONTRACTOR SHALL COORDINATE AND/OR MODIFY THE WORK SCHEDULE AS DIRECTED BY THE DEPARTMENT TO ACCOMMODATE SPECIAL EVENTS.
- 15. THE CONTRACTOR SHALL PLACE TEMPORARY CONCRETE BARRIER ADJACENT TO TEMPORARY SHORING AND CRIBBING TO PROVIDE A BARRIER FROM PARKING LOT TRAFFIC. AN ESTIMATED THREE (3) SECTIONS OF TEMPORARY CONCRETE BARRIER WILL BE NEEDED AT EACH SHORING AND CRIBBING LOCATIONS.
- 16. THE CONTRACTOR SHALL USE PP3 CONCRETE FOR ALL DECK PATCHES.
- 17. AS PART OF THIS PROJECT, ALL BRIDGE DECKS SHALL BE RE-STRIPED AND RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE REMOVED AND REPLACED.
- 18. THE CONTRACTOR WILL BE ALLOWED ADDITIONAL LANE CLOSURES TO MEASURE AND SAWCUT PATCHING AREAS AND TO LAYOUT WEAVE LOCATIONS.

,		U					
	CR CHRISTIAN-ROGE &						
- 1	## ACCOCTATES INC	PI					
1	ABSOCIATES, INC.	PI					

	USER NAME = IDOT	DESIGNED	-	J.C.N./B.N.S.	REVISED			
. &c		CHECKED	~	B.N.S./J.C.N.	REVISED	-		
IC.	PLOT SCALE = 50.0000 '/ IN.	DRAWN	-	F.M.	REVISED	-		
	PLOT DATE = 10/12/2011	DATE	-	OCTOBER 12, 2011	REVISED	-		