INDEX OF SHEETS

| SHEET NO. | DESCRIPTION | | | | | | | |
|-----------|---|--|--|--|--|--|--|--|
| 1 | TITLE SHEET | | | | | | | |
| 2 | INDEX OF SHEETS, STATE STANDARDS, & GENERAL NOTES | | | | | | | |
| 3 | SUMMARY OF QUANTITIES | | | | | | | |
| 4-11 | BRIDGE REPAIR DETAILS - SN 016-2554 | | | | | | | |
| 12-13 | TRAFFIC CONTROL PLANS (STAGE I & II) | | | | | | | |
| 14 | TRAFFIC STAGING PLAN | | | | | | | |
| 15 | PAVEMENT MARKING PLAN | | | | | | | |
| 16 | TEMPORARY TRAFFIC SIGNAL INSTALLATION PLAN | | | | | | | |
| 17 | TEMPORARY CABLE PLAN, TEMPORARY PHASE DESIGNATION DIAGRAM AND TEMPORARY EMERGENCY VEHICLE PREEMPTION SEQUENCE | | | | | | | |
| 18 | TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC-10) | | | | | | | |
| 19 | TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT) (TC-11) | | | | | | | |
| 20 | TYPICAL PAVEMENT MARKING (TC-13) | | | | | | | |
| | TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC) (TC-14) | | | | | | | |
| 22 | PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC STAGING (TC-16) | | | | | | | |
| 23 | ARTERIAL ROAD INFORMATION SIGN (TC-22) | | | | | | | |
| 23A. | DRIVEWAY ENTRANCE SIGNING (TC-26) | | | | | | | |
| | | | | | | | | |

STATE STANDARDS

STANDARD NO.

| | 442201- 03 701427 | CLASS C AND D PATCHES | | | | |
|--|------------------------------------|--|--|--|--|--|
| | 701606-07 | URBAN LANE CLOSURE, MULTILANE, | | | | |
| | 701701-07 | 2W WITH MOUNTABLE MEDIAN | | | | |
| | 701801 - 04 | LANE CLOSURE, MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE | | | | |
| | 701901 -01 | TRAFFIC CONTROL DEVICES | | | | |
| | | | | | | |

DESCRIPTION

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE & GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE CITY OF PALOS HILLS.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARMENT.

BEFORE BEGINING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIP ING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE AS DIRECTED BY THE ENGINEER.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR ARTERIAL OPERATIONS (847)705-4470, A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE ENGINEER SHALL CONTACT PATRICE HARRIS AREA TRAFFIC FIELD TECHNICIAN AT (708) 597-9800 A MINIMUM OF TWO (2) WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM THE BUREAU OF MAINTENANCE.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.

ALL DAMAGE TO EXISTING PAVEMENT MARKINGS OR RAISED REFLACTIVE PAVEMENT MARKERS OUTSIDE THE REMOVAL LINE SHOWN ON THE PLANS SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGES OR COST TO REPLACE ANY PORTION OR COMPONENT OF THE EXISTING TRAFFIC SIGNAL INTERCONNECT CONDUIT ATTACHED TO THE EXISTING BRIDGE STRUCTURE. THIS RESPONSIBILITY SHALL INCLUDE ALL UNIONS, COUPLINGS, EXPANSION SLEEVES, FIBER CABLE AND JUNCTION BOXES TO MATCH THE EXISTING CONDITIONS WITH NO ASSOCIATED COSTS TO THE DEPARTMENT.

| | | | | | | | and the state of | | |
|--|-----------------------------|------------|-----------|------------------------------|-------------|----------------------------------|------------------|----------------------------|-------------|
| ILE NAME = | USER NAME = gorengautab | DESIGNED - | REVISED - | | | INDEX OF SHEETS | F.A.U | SECTION COUNTY TOTAL SHEET | <u>E</u> ET |
| :\pw_work\pwidot\gorengautab\d0273096\ | 0161711-sht-plan.dgn | DRAWN - % | REVISED - | STATE OF ILLINOIS | | | 1581 | 1355-B-I COOK 23 2 | 2 |
| | PLOT SCALE = 50.0000 '/ in. | CHECKED - | REVISED - | DEPARTMENT OF TRANSPORTATION | | STATE STANDARDS, GENERAL NOTES | 1501 | CONTRACT NO. 60P8 | RO I |
| | PLOT DATE = 9/7/2011 | DATE - | REVISED - | | SCALE: NONE | SHEET NO. OF SHEETS STA. TO STA. | | ILLINOIS FED. AID PROJECT | \tilde{H} |
| | | | | | | | | | _ |