

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	BUILDING DEMOLITION PLAN
5	LANDSCAPING AND EROSION CONTROL PLAN
6	PLAT OF HIGHWAYS (FOR INFORMATION ONLY)
7	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC-10)

HIGHWAY STANDARDS

STANDARD NO.	DESCRIPTION
000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
280001-05	TEMPORARY EROSION CONTROL SYSTEMS
701101-02	OFF-ROAD OPERATIONS, MULTILANE, 15' (4.5 M) TO 24' (600 MM) FROM PAVEMENT EDGE
701106-02	OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 15' (4.5 M) AWAY
701901-01	TRAFFIC CONTROL DEVICES

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. 48 HOUR NOTIFICATION IS REQUIRED.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, AND THE CITY OF WEST CHICAGO.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING A DEMOLITION PERMIT FROM THE CITY OF WEST CHICAGO.

THE CONTRACTOR MUST CONTACT THE CITY OF WEST CHICAGO FOR CORRESPONDING UTILITY DISCONNECTION REQUIREMENTS.

BACKFILL USED FOR ANY HOLES, SUCH AS BASEMENTS, SHALL BE FILLED WITH POROUS GRANULAR EMBANKMENT AND SHALL BE INCLUDED IN THE UNIT PRICE FOR BUILDING REMOVAL.

ALL TRAFFIC CONTROL SHALL BE INCLUDED IN THE UNIT PRICE FOR BUILDING REMOVAL AND DEBRIS REMOVAL, EXCEPT FOR TEMPORARY INFORMATION SIGNING.

CONTRACTOR SHALL INSTALL "TRUCKS ENTERING AND LEAVING HIGHWAY" SIGNS, W21-I105 (MODIFIED) IN EACH DIRECTION ON ILLINOIS ROUTE 38 APPROACHING BUILDING DEMOLITION SITE. THESE SIGNS SHALL BE PAID AS TEMPORARY INFORMATION SIGNING.

DUST CONTROL FOR EACH SITE SHALL BE IN ACCORDANCE TO ARTICLE 107.36 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, AND SHALL BE INCLUDED IN THE UNIT PRICE FOR BUILDING REMOVAL.

ALL PERMIT FEES FOR THE DISCONNECTION OF UTILITIES SHALL BE INCLUDED IN THE UNIT PRICE FOR BUILDING REMOVAL.

WATER / MONITORING WELLS SEALING

ALL WATER WELLS LOCATED ON THE PROPERTY MUST BE SEALED ACCORDING TO SECTION 920.120 OF THE ILLINOIS WATER WELL CONSTRUCTION CODE. THE CONTRACTOR SHALL CONTACT LOCAL HEALTH DEPARTMENT OR THE ILLINOIS DEPARTMENT OF PUBLIC HEALTH TO OBTAIN ADDITIONAL INFORMATION AND / OR FORMS REQUIRED FOR THE WATER WELL SEALING. ALL THE COST ASSOCIATED WITH THE WATER WELL SEALING INCLUDING ALL THE NECESSARY PERMITS SHALL BE INCLUDED IN THE UNIT PRICE FOR BUILDING REMOVAL.

ILLINOIS DEPARTMENT OF PUBLIC HEALTH
DIVISION OF ENVIRONMENTAL HEALTH
525 W JEFFERSON ST
SPRINGFIELD, IL 62761
P: (217) 782-5830

KANE COUNTY HEALTH DEPARTMENT
1240 N HIGHLAND AVE
AURORA, IL 60506
P: (630) 208-3801

SEEDING WORK ON THIS CONTRACT MAY BE PERFORMED FROM NOVEMBER 1ST TO APRIL 1ST WITHOUT THE STANDARD REQUIREMENT OF A CONTRACTOR GUARANTEE. SOIL MUST BE SUFFICIENTLY WORKABLE AT THE TIME OF SEEDING TO ALLOW PREPARATION OF AN ACCEPTABLE SEED BED.

FILE NAME =	USER NAME = pcc1eohel	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	BUILDING DEMOLITION INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S:\GR\Projsup\PLANPREP\K.Smith_Squad\LP	00000 - Building Demo\DI09012-shr-design.dgn	DRAWN -	REVISED -		347	2011-201-DM	KANE	7	2			
	PLOT SCALE = 50.0000' / 1" =	CHECKED -	REVISED -		CONTRACT NO. 60R43							
	PLOT DATE = 9/12/2011	DATE -	REVISED -		SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			