

CODE NUMBER	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL	FEDERAL 80% / STATE 20%			CITY OF STERLING 100%		CITY OF ROCK FALLS 100%	
				SAFETY 0021	Roadway 0004	Bridge 0011	LANDSCAPING 0031	SAFETY 0021	Roadway 0004	SAFETY 0021
	DRILLING AND GROUTING VOIDS	CU YD	500			500				
83057085 *	LIGHT POLE, WOOD, 40 FOOT, CLASS 3	EACH	2	2						
X8300001 *	LIGHT POLE, SPECIAL	EACH	35	15				18		2
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	424		376		48			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	60		60					
20101000	TEMPORARY FENCE	FOOT	150		150					
20200100	EARTH EXCAVATION	CU YD	1,963		1,963					
20700220	POROUS GRANULAR EMBANKMENT	CU YD	992		992					
20800150	TRENCH BACKFILL	CU YD	533		533					
20900110	POROUS GRANULAR BACKFILL	CU YD	153			153				
21101600 *	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	SQ YD	331		331					
21101685 *	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	183		183					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	75		75					
28000400	PERIMETER EROSION BARRIER	FOOT	408		408					
28000510	INLET FILTERS	EACH	5		5					
28200200	FILTER FABRIC	SQ YD	386		386					
28500400	ARTICULATED BLOCK REVETMENT MAT	SQ YD	386		386					
30103000	SHAPING AND GRADING ROADWAY	UNIT	7		7					
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	4,017		4,017					
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	50		50					
40600535	LEVELING BINDER (HAND METHOD), N70	TON	10		10					
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	478		478					
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	757		757					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	69		69					
40600990	TEMPORARY RAMP	SQ YD	69		69					
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	359		359					
40603390	HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N70	TON	594		594					
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	82		82					
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SQ YD	1,681		1,681					
42001300	PROTECTIVE COAT	SQ YD	2,240		2,240					

* SPECIALTY ITEM

FILE NAME = c:\p\work\p\dot\hansonke\dms80258\0264880-sht-S001.dgn	USER NAME = hansonke	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 40 SUMMARY OF QUANTITIES			F.A.P. RTE. 646	SECTION IB-2	COUNTY WHITESIDE	TOTAL SHEETS 257	SHEET NO. 3
PLOT SCALE = N/A	CHECKED -	REVISED -	REVISED -		SCALE: N/A	SHEET NO. 1 OF 7 SHEETS	STA.	TO STA.	CONTRACT NO. 64B80			
PLOT DATE = Tue Sep 27 13:21:45 2011	DATE - 2-22-2010	REVISED -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							