

URETHANE PAVEMENT MARKING SCHEDULE

LOCATION			REMARKS	X7800605 URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS (SQ FT)	X7800610 URETHANE PAVEMENT MARKING LINE 4" (FOOT)	X7800630 URETHANE PAVEMENT MARKING LINE 6" (FOOT)	X7800640 URETHANE PAVEMENT MARKING LINE 8" (FOOT)	X7800650 URETHANE PAVEMENT MARKING LINE 12" (FOOT)	X7800680 URETHANE PAVEMENT MARKING LINE 24" (FOOT)	
735+70.0	RT		LEFT AND THROUGH ARROW - 3 EACH	78.0						
735+70.0	RT		THROUGH ARROW - 3 EACH	34.5						
738+30.0	LT		ILL 40	21.3						
738+31.0	RT		ILL 2	16.0						
738+80.0	LT		THROUGH ARROW - 1 EACH	11.5						
738+82.0	RT		THROUGH ARROW - 1 EACH	11.5						
739+38.0	RT		RIGHT ARROW - 3 EACH	46.8						
740+15.0	LT		RIGHT ARROW - 3 EACH	46.8						
740+00.0	LT		RIGHT ARROW - 3 EACH	46.8						
740+40.0	LT		LEFT ARROW - 3 EACH	46.8						
738+23.5	LT		RIGHT AND THROUGH ARROW - 3 EACH	78.0						
738+27.0	LT		THROUGH ARROW - 3 EACH	34.5						
740+33.0	RT		LEFT ARROW - 3 EACH	46.8						
740+44.0	RT		LEFT AND RIGHT ARROW - 3 EACH	93.6						
722+75.8	RT	735+12.6	RT	SKIP DASH 4" (10' / 30')		309.2				
722+75.8	LT	736+39.1	LT	SKIP DASH 4" (10' / 30')		340.8				
740+13.9	LT	740+22.9	LT	LOCUST ST - SKIP DASH 4" (10' / 30')		22.8				
740+26.9	RT	740+26.9	RT	2ND ST - SKIP DASH 4" (10' / 30')		50.2				
740+38.5	RT	740+38.5	RT	2ND ST - SKIP DASH 4" (10' / 30')		50.2				
722+75.8	RT	723+17.1	RT	2 LINES		82.7				
722+75.8	LT	723+17.1	RT	2 LINES		82.8				
723+17.1	RT	736+39.1	RT	2 LINES		2,644.1				
740+26.8	RT	740+26.9	RT	2ND ST - 2 LINES		220.4				
723+13.0	LT			CROSSWALK - IL 40 & 2ND ST			36.1			
723+12.1	LT			CROSSWALK - IL 40 & 2ND ST			30.6			
736+55.5				CROSSWALK - IL 40 & WALLACE ST				200.0		
736+93.5	LT			CROSSWALK - IL 40 & WALLACE ST				207.0		
736+93.8	RT			CROSSWALK - IL 40 & WALLACE ST				132.0		
740+27.0	RT			CROSSWALK - IL 40 & 2ND ST				108.0		
739+81.6	LT			CROSSWALK - IL 40 & LOCUST ST				48.0		
740+46.9	LT			CROSSWALK - IL 40 & LOCUST ST				48.0		
740+66.9				CROSSWALK - IL 40				102.0		
737+60.5	RT	738+72.1	RT	SKIP DASH 8" (2' / 4')			37.4			
739+21.9	LT	739+78.0	LT	SKIP DASH 8" (2' / 4')			18.3			
739+21.9	LT	740+38.9	LT	SKIP DASH 8" (2' / 4')			51.2			
735+12.6	RT	736+38.2	RT	SOLID 8"			125.6			
737+58.8	RT	739+71.5	LT	SOLID 8"			213.4			
738+72.1	RT	740+14.2	RT	SOLID 8"			142.3			
738+72.1	RT	739+94.5	RT	SOLID 8"			122.4			
739+94.5	RT	740+25.0	RT	SOLID 8"			39.7			
740+14.2	RT	740+25.0	RT	SOLID 8"			29.6			
737+51.7	LT	739+21.9	LT	SOLID 8"			171.6			
740+38.7	RT	740+38.5	RT	SOLID 8"			108.2			
739+87.8	LT	740+13.9	LT	SOLID 8"			107.6			
740+29.9	LT	740+20.1	LT	SOLID 8"			66.2			
740+29.9	LT	740+36.6	LT	SOLID 8"			128.2			
722+75.6		723+70.3		DIAGONAL MEDIAN				14.2		
738+74.4	RT	740+25.3	RT	DIAGONAL ISLAND				99.5		
740+29.8	LT	740+36.6	LT	DIAGONAL ISLAND				119.7		
723+04.7	LT			STOP BAR - 1ST ST, ROCK FALLS					16.1	
736+39.2	RT			STOP BAR - NB IL 40					24.0	
736+82.2	LT			STOP BAR - WALLACE ST					25.3	
737+04.5	RT			STOP BAR - COMMERCIAL ENTRANCE					19.8	
737+50.5	LT			STOP BAR - SB IL 40					24.0	
739+72.6	LT			STOP BAR - NB IL 40					26.7	
739+87.1	LT			STOP BAR - LOCUST ST					34.4	
740+44.4	LT			STOP BAR - LOCUST ST					20.4	
740+38.7	RT			STOP BAR - 2ND ST					23.1	
TOTAL				612.9	3,803.2	66.7	1,361.6	1,078.4	213.8	
ROUNDED				613.0	3,804.0	67.0	1,362.0	1,079.0	214.0	

Z0000500 ADJUSTING EXISTING HANDHOLE				
STATION	OFFSET	EX RIM	PR RIM	QTY (EACH)
723+23.5	41.7 RT	647.20	647.51	1
736+58.3	45.4 LT	635.37	635.22	1
TOTAL				2

BUILDING REMOVAL  
SCHEDULE

Z0049801  
REMOVAL AND  
DISPOSAL OF FRIABLE  
ASBESTOS, BUILDING  
NO. 1

LOCATION	(L SUM)
735+16.00	40.00 RT
1	

Z0018100 DRAINAGE STRUCTURE ADJUSTMENT (SPECIAL)					
STA	OFFSET	EX RIM	PR RIM	DESCRIPTION	QTY (EACH)
735+91.29	30.7 LT	640.37	639.94	EXISTING GATE BOX - SEE DETAIL	1

RIM ELEVATIONS ARE AT THE CENTER OF THE CASTING.

Z0024476 FLEXIBLE DELINEATOR MAINTENANCE						
LOCATION	REMARKS	LENGTH (FT)	QTY (EACH)			
740+38.66	4.1 RT	740+38.66	43.8 RT	PRESTAGE	39.7	5
722+53.55	15.9 LT	737+86.91	33.95 LT	STAGE 1	1533.5	32
740+38.66	4.1 RT	740+38.66	43.8 RT	STAGE 1	39.7	5
718+60.00	9.0 LT	719+79.00	9.0 LT	STAGE 2	119.0	4
722+75.79	15.4 RT	738+52.00	0.6 RT	STAGE 2	1576.3	33
718+60.00	9.0 LT	719+79.00	9.0 LT	STAGE 3	119.0	4
740+38.66	4.1 RT	740+38.66	43.8 RT	STAGE 3	39.7	5
SUBTOTAL						88
				Z0025500 FURNISHING AND INSTALLING PROPERTY MARKERS		
				LOCATION	(EACH)	22
				TBD	5	
				Z0070150 REMOVE AND RELOCATE EXISTING MONUMENT		
				LOCATION	(EACH)	110
				724+35.88	27.55 RT	1
				TOTAL	1	132

CONTINGENCY ITEM.

Z0070150 REMOVE AND RELOCATE EXISTING MONUMENT		
LOCATION	(EACH)	
724+35.88	27.55 RT	1
TOTAL		1

Z0056608 STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH		Z0056610 STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	
LOCATION	(FOOT)	LOCATION	(FOOT)
TBD	5	TBD	5

CONTINGENCY ITEMS.

Z0056612 STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH		Z0056616 STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH		Z0056624 STORM SEWER (WATER MAIN REQUIREMENTS) 42 INCH	
LOCATION	(FOOT)	LOCATION	(FOOT)	LOCATION	(FOOT)
TBD	5	TBD	5	TBD	5

CONTINGENCY ITEMS.