

SUMMARY OF QUANTITIES				90% FED / 10% STATE				
				ACIM		ACBRI	ACBHI	
				RURAL RDWY	URBAN RDWY	006-0020 006-0021 RURAL	006-0131 RURAL	006-0176 006-0177 RURAL
CODE NO	ITEM	UNIT	TOTAL QTY	0004	0004	0011	0014	0013
40603510	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N60	TON	7706	3994	3712			
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	17681	9688	7993			
42001200	PAVEMENT FABRIC	SQ YD	54	27	27			
42001300	PROTECTIVE COAT	SQ YD	32080	32080				
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1067	1067				
42100300	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	15398	15398				
42100615	PAVEMENT REINFORCEMENT	SQ YD	16,464	16,464	▲			
42101020	WIDE FLANGE BEAM TERMINAL JOINT COMPLETE 24"	EACH	4	4				
44000100	PAVEMENT REMOVAL	SQ YD	13824	13824				
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	8431	8431				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	159223	81375	77848			
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	5191	5191				
44000186	HOT-MIX ASPHALT SURFACE REMOVAL, 9"	SQ YD	10786	9384	1402			
44004250	PAVED SHOULDER REMOVAL	SQ YD	8888	8888				
44201055	CLASS B PATCHES, TYPE II, 17 INCH	SQ YD	134	99	35			
44201057	CLASS B PATCHES, TYPE III, 17 INCH	SQ YD	48	32	16			
44201053	CLASS B PATCHES, TYPE IV, 17 INCH	SQ YD	54	27	27			
44201299	DOWEL BARS 1 1/2"	EA	360	240	120			
44213200	SAW CUTS	FOOT	996	664	332			
44213204	TIE BARS 3/4"	EACH	40	20	20			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	13435	13435				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5716	4411	1305			
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1610	1610				
48203030	HOT-MIX ASPHALT SHOULDERS, 8 1/4"	SQ YD	774	774				
48203033	HOT-MIX ASPHALT SHOULDERS, 9"	SQ YD	10786	9384	1402			
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	14384	14384				
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1					1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1					1
50101700	REMOVAL OF EXISTING SUPERSTRUCTURES NO. 1	EACH	1			1		
50101800	REMOVAL OF EXISTING SUPERSTRUCTURES NO. 2	EACH	1			1		
50102400	CONCRETE REMOVAL	CUYD	140.4			140.4		
50157300	PROTECTIVE SHIELD	SQ YD	1134			502		632
50200100	STRUCTURE EXCAVATION	CUYD	2120.4			597.4		1523
50300225	CONCRETE STRUCTURES	CUYD	907.9			273.1		634.8
50300255	CONCRETE SUPERSTRUCTURE	CUYD	1808.2			693		1115.2
50300260	BRIDGE DECK GROOVING	SQ YD	4682			1664		3016
50300280	CONCRETE ENCASEMENT	CUYD	20					20

* SPECIALTY ITEMS

FILE NAME =	USER NAME = braboypa	DESIGNED -	REVISED -
cs:\pw\work\pwidot\braboypa\08212731\036686-shr-cover.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

Rev. 11-10-11		Rev	
F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS
80	[[06-SHBR-1,VBR(06-6)RS-3&]]	BUREAU	249
		CONTRACT NO.	66686
ILLINOIS FED. AID PROJECT			