

PAVEMENT MARKING										
LOCATION			PAINT PAVEMENT MARKING -			RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	TEMPORARY PAVEMENT MARKING -		
			LINE 4"		LINE 6"			LINE 4"		LINE 6"
			WHITE	YELLOW	YELLOW			WHITE	YELLOW	YELLOW
STATION	TO	STATION	FOOT	FOOT	FOOT	EACH	EACH	FOOT	FOOT	FOOT
STAGE III										
371+90.00		379+30.00	2960	1480	380	9	9	1480	740	190
TOTALS			2960	1480	380	9	9	1480	740	190

PAINT PAVEMENT MARKING QUANTITIES ARE FOR TWO APPLICATIONS

TEMPORARY PAVEMENT MARKING					
LOCATION			LINE 4" WHITE	LINE 24" WHITE	WORK ZONE PAVEMENT MARKING REMOVAL
STATION	TO	STATION	FOOT	FOOT	SQ FT
STAGE I					
371+90.00		379+29.50	974	24	324
STAGE II					
371+90.00		379+29.50	991		378
TOTALS			1965	24	702

TEMPORARY CONCRETE BARRIER & TEMPORARY IMPACT ATTENUATORS				
LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE)	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE)
	FOOT	FOOT	EACH	EACH
STAGE I	447		4	
STAGE II		250		2
TOTALS	447	250	4	2

EARTH EXCAVATION					
LOCATION	DISTANCE	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	FEET	CU YD	CU YD	CU YD	CU YD
<b>Pre-Stage I (West side)</b>					
STA. 374+00.00 TO STA. 378+00.00	400	48.5	36.4	53.2	-16.8
<b>Stage I (East side)</b>					
STA. 374+00.00 TO STA. 378+00.00	400	25.6	19.2	0.6	18.6
<b>Stage II (West side)</b>					
STA. 374+00.00 TO STA. 378+00.00	400	46.6	35.0	52.1	-17.2
<b>Stage III (East side)</b>					
STA. 374+00.00 TO STA. 378+00.00	400	17.8	13.4	24.9	-11.6
TOTALS		139	104	131	-27

COLUMN 4 = EARTH EXCAVATION ADJUSTED USING SHRINKAGE FACTOR OF 25%

FILE NAME =	USER NAME = schwenkerg	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw_work\p\dot\schwenkerg\dms66821\066869-ah-t-schedule.DGN	66869-ah-t-schedule.DGN	DRAWN -	REVISED -					326	(121)I	LIVINGSTON	27	8
PLOT SCALE = 50.0000' / in.		CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 66869		ILLINOIS FED. AID PROJECT		
PLOT DATE = 8/19/2011		DATE -	REVISED -									