

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITIES	80% FED. / 20% STATE CONSTRUCTION TYPE CODES	
				ROADWAY 0004	EX SN 019-0013 PR SN 019-0048 0011
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	738	738	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4,153	4,153	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	206	206	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	42	42	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	940	940	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	439	439	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	403	403	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3,296	3,296	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	412	412	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	8	8	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2		2
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	571	571	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	9	9	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	96		96
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	850	850	
X5011100	FOUNDATION REMOVAL	EACH	2	2	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1
X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	5	5	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	19		19
Z0022800	FENCE REMOVAL	FOOT	310	310	
Z0026407	TEMPORARY SHEET PILING	SQ FT	1,538		1,538
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	157		157
Z0078000	WOOD RAIL	FOOT	110	110	
X4240470	PORTLAND CEMENT CONCRETE SIDEWALK 10 INCH, SPECIAL	SQ FT	152	152	

\* SPECIALTY ITEM

FILE NAME = sheets01.dgn	USER NAME = default	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE. 307	SECTION 126 (B-1)BR	COUNTY DEKALB	TOTAL SHEETS 62	SHEET NO. 4	
PLOT SCALE = 28.0000' / IN.	CHECKED -	REVISED -	SCALE: NTS			SHEET NO. 2 OF 2 SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 66987	
PLOT DATE = 8/26/2011	DATE -	REVISED -									

Rev.