

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	HENDERSON				0004
				0011		0011		100% STATE
				DIXON IL RTE 94 STR. NO. 036-0054	WOLF IL RTE 94/116 STR. NO. 036-0055	DIXON IL RTE 94 0004 ROADWAY	WOLF IL RTE 94/116 0004 ROADWAY	IL RTE 94/116 0031 MOWING
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	92,180	46,240	45,940			
50800515	BAR SPLICERS	EACH	1,054	525	529			
51200956	FURNISHING METAL SHELL PILES 12" X 0.179"	FOOT	770		770			
51201400	FURNISHING STEEL PILES HP10X42	FOOT	490	490				
51202305	DRIVING PILES	FOOT	1260	490	770			
51203200	TEST PILE METAL SHELLS	EACH	2		2			
51203400	TEST PILE STEEL HP10X42	EACH	2	2				
51500100	NAME PLATES	EACH	2	1	1			
52100520	ANCHOR BOLTS, 1"	EACH	48	24	24			
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	116			68	48	
54213447	END SECTIONS 12"	EACH	6			4	2	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1			1		
54213870	STEEL END SECTIONS 15"	EACH	6			4	2	
59100100	GEOCOMPOSITE WALL DRAIN	SQ.YD	119	59	60			
60100945	PIPE DRAINS 12"	FOOT	207			133	74	
60900140	TYPE B INLET BOX, STANDARD 609006	EACH	6			4	2	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	550			300	250	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8			4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	8			4	4	
63200310	GUARDRAIL REMOVAL	FOOT	808			404	404	
66500105	WOVEN WIRE FENCE, 4'	FOOT	395			75	320	
X6650202	WOVEN WIRE FENCE REMOVAL	FOOT	395			75	320	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	24			10	14	
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	2			1	1	

* SPECIALTY
ITEM