


When "A" is 3'-6" or less, the temporary concrete barrier shall be anchored to the new slab according to Detail I or Detail II. No anchorage is required when "A" is greater than 3'-6".



SECTIONS THRU SLAB OR DECK BEAM

NOTES

Detail I - With Bar Splicer or Couplers:
Connect one (1) 1" x 7" x "W" steel \bar{L} to the top layer of couplers with 2- $\frac{5}{8}$ " ϕ bolts screwed to coupler at approximate \bar{C} of each barrier panel.


Detail II - With Extended Reinforcement Bars:
Connect one (1) 1" x 7" x "W" steel \bar{L} to the concrete slab or concrete wearing surface with 2- $\frac{5}{8}$ " ϕ Expansion Anchors or cast in place Inserts spaced between the top layer of reinforcement at approximate \bar{C} of each barrier panel.

Cost of anchorage is included with Temporary Concrete Barrier. The 1" x 7" x "W" plate shall not be removed until stage II construction forms and all reinforcement bars are in place and the concrete is ready to be placed.


*** Dimension shown is minimum required embedment into concrete. If hot-mix asphalt wearing surface is present, minimum embedment shall be in addition to wearing surface depth.

**** If existing deck beam is to remain in place after stage construction, embedment shall only be into wearing surface and not into existing deck beam concrete.


Limits of Temporary Concrete Barrier
Sta. 213+50 North
Sta. 217+50 South



DETAIL I



DETAIL II



STEEL RETAINER \bar{L} 1" x 7" x "W"

* Required only with Detail II

** Wood blocks may be omitted when required to provide minimum stage traffic lane width. When the wood blocks are omitted, the concrete barrier shall be in direct contact with the steel retainer plate.

"W" = Top bars spacing + 4"



FILE NAME = D468883-sht-plan.dgn

| | | |
|------------------------------|------------|-----------|
| USER NAME = johnsonv | DESIGNED - | REVISED - |
| PLOT SCALE = 100.4566' / in. | DRAWN - | REVISED - |
| PLOT DATE = 8/26/2011 | CHECKED - | REVISED - |
| | DATE - | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TEMPORARY CONCRETE BARRIER
IL 94 OVER WOLF CREEK S.N. 036-0055
SCALE: SHEET NO. 3 OF 15 SHEETS STA. 216+45

| | | | | |
|---------------------------|--------------------|------------------|-----------------|--------------|
| F.A.P. RTE. 534 | SECTION 109B (BR3) | COUNTY HENDERSON | TOTAL SHEETS 88 | SHEET NO. 28 |
| CONTRACT NO. 68083 | | | | |
| ILLINOIS FED. AID PROJECT | | | | |