

HOT-MIX ASPHALT & AGG SHOULDER CALCULATIONS

		44000155	40600990	40603310	X4060637	40600100	40600300	48102100
		HMA SURF REM 1.5"	TEMPORARY RAMP	HMA SURF. CSE. 1.5"	HMA FG LVL BIND 0.75"	BIT. MAT'L PRIME COAT	AGG MAT'L PRIME COAT	AGG WEDGE SHOULDERS TYPE B
STA	STA	SQ YD	SQ YD	TON	TON	GALLON	TON	TON
523+19.97	527+48.00	1426.8	20.0	119.9	59.9	142.7	2.9	21.6
527+68.00	696+50.30	56274.3	20.0	4727.0	2363.5	5627.4	112.6	850.9
696+50.30	708+42.90	3975.3		356.2	178.1	424.0	8.5	60.1
708+42.90	732+38.09	7983.9		670.7	335.3	798.4	16.0	120.7
732+38.09	744+34.90	3989.4		335.1	167.6	398.9	8.0	60.3
744+34.90	745+27.50	308.7	20.0	25.9	13.0	30.9	0.6	4.7
748+02.50	774+32.30	8766.0	20.0	736.3	368.2	876.6	17.5	132.5
774+32.30	837+40.63	21027.8	20.0	1766.3	883.2	2102.8	42.1	324.7
ACTUAL TOTAL		103752.15	100.00	8737.39	4368.8	10401.74	208.08	1575.45
USE TOTAL		103752	100*	8738	4369	10,402	208	1576*

*SEE INCIDENTAL SCHEDULE FOR ADDITIONAL QUANTITY

SURVEY MARKERS

STATION	O/S	O/S DIR.	COMMENTS	XZ193300	Z0070202
				SURVEY MARKER, TYPE 1(SPECIAL)	SURVEY MARKER VAULT
				EACH	EACH
523+60.79	0.000	CL	PT	1	
697+73.92			PC	1	
707+23.29			PT	1	
719+03.61			POT	1	
733+57.68			PC	1	
743+14.40			PT	1	
758+52.44			POT	1	
836+04.90			POT	1	
836+24.90			POT	1	
0+996.462			SC		1
0+996.462	3.3'		SC		1
1+000			POT	1	
TOTALS				10	2

CULVERT REPAIR ITEMS

LOCATION		542A1093 PIPE CUVERT CL A, TY 2, 48"	20800150 TRENCH BACKFILL	X5427600 REM & RELOC END SECT	28100205 STONE RIPRAP CL A3
STATION	O/S	FOOT	CU YD	EACH	TON
705+66	LT	8.0	2.9	1.0	15
ACTUAL TOTAL		8.0	2.9	1.0	15
USE TOTAL		8.0	3.0	1.0	15