

GUARDRAIL ITEMS CONTINUED

LOCATION				63000025	63000005	63000001	63000003	63100169	63100167	78201000	78200420
STA	TO	STA	O/S	SPBGR ATTACH TO STR	SPBGR, TY B	SPBGR, TY A 6 FT POSTS	SPBGR, TY A 9 FT POSTS	TR BAR TRM T1 (SPL FLR)	TR BAR TRM T1 (SPL TAN)	TERMINAL MARKER D- A	GUARDRAIL MKR, TYPE B
743+26.5	TO	743+39.00	LT						1	1	
743+39.00	TO	744+14.00	LT			75					
748+16.27	TO	757+16.27	LT				900				12
757+16.27	TO	757+28.77	LT						1	1	
742+51.50	TO	742+64.00	RT						1	1	
742+64.00	TO	744+14.00	RT								
748+16.27	TO	756+53.77	RT				837.5				12
756+53.77	TO	756+66.27	RT						1	1	
TOTALS:				125.3	300	1262.5	1737.5	4	12	16	48
USE:				126	300	1263	1738	4	12	16	48

25000200	25000400	25000500	25000600	25100630	28000250
SEEDING CLASS II	NITROGEN FERT NUTR	PHOSPHORUSFE RT NUTR	POTASSIUM FERT NUTR	EROSION CONTROL BLANKET	TEMP EROS CONTR SEED
0.0156	1.406	1.406	1.406	35.625	1.562
0.0156	1.406	1.406	1.406	35.625	1.562
0.0156	1.406	1.406	1.406	35.625	1.562
0.0156	1.406	1.406	1.406	35.625	1.562
0.25	22.5	22.5	22.5	570	24.9
0.25	23	23	23	570	25

GUARDRAIL REMOVAL ITEMS

LOCATION				63200310
STA	TO	STA	O/S	GUARDRAIL REMOVAL
525+88.78	TO	527+16.78	LT	128
527+16.78	TO	527+38.78	LT	22
527+38.78	TO	529+41.78	LT	203
525+13.78	TO	527+16.78	RT	203
527+16.78	TO	527+38.78	RT	22
527+38.78	TO	528+66.78	RT	128
616+07.00	TO	617+07.00	LT	100
617+07.00	TO	617+38.25	LT	31.25
617+38.25	TO	619+07.00	LT	168.75
615+65.50	TO	617+37.38	RT	171.88
617+37.38	TO	617+68.63	RT	31.25
617+68.63	TO	618+90.50	RT	121.87
716+80.16	TO	717+57.3	LT	77.14
717+57.3	TO	717+47.9	LT	9.4
717+47.9	TO	718+43.25	LT	77.14
716+80.16	TO	717+57.3	RT	77.14
717+57.3	TO	717+47.9	RT	9.4
717+47.9	TO	718+43.25	RT	77.14
743+26.50	TO	744+14.00	LT	75
748+16.27	TO	757+31.50	LT	915.23
742+47.75	TO	744+14.00	RT	166.25
748+16.27	TO	756+68.50	RT	852.23
Total:				3667.07
Use:				3668

PAVEMENT MARKING ITEMS

LENGTH	STA	STA	78001110				70300100	70301000
			PAINT PAVEMENT MARKING LINE, 4"				SHORT-TERM PAVEMENT MARKINGS	
			EDGE LINE (WHITE)	CENTERLINE SKIP DASH (YELLOW)	NB NO PASSING (YELLOW)	SB NO PASSING (YELLOW)	CENTERLINE	WORK ZONE PAVT MKG REM
FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT		
3690.33	523+19.97	560+10.00	7380.00	922.58	0.00	0.00	1006.45	111.20
90.00	560+10.00	561+00.00	0.00	22.58	0.00	0.00	24.54	2.73
5234.00	561+00.00	613+34.00	10468.00	1308.50	0.00	0.00	1427.45	158.60
90.00	613+34.00	614+24.00	0.00	22.58	0.00	0.00	24.54	2.73
5201.00	614+24.00	666+25.00	10402.00	1300.25	0.00	0.00	1418.45	157.60
126.00	666+25.00	667+51.00	0.00	31.50	0.00	0.00	34.36	3.80
2250.00	667+51.00	690+01.00	4500.00	562.50	0.00	0.00	613.64	68.20
1279.00	690+01.00	702+80.00	2258.00	319.75	1279.00	0.00	348.82	38.80
376.00	699+04.00	702+80.00	0.00	0.00	0.00	376.00	0.00	0.00
292.00	702+80.00	705+72.00	292.00	73.00	0.00	0.00	79.64	8.80
2052.00	705+72.00	726+24.00	4104.00	513.00	0.00	0.00	559.64	62.20
1109.00	726+24.00	737+33.00	2218.00	277.25	275.00	0.00	302.45	33.60
475.00	737+33.00	742+08.00	950.00	0.00	475.00	475.00	129.55	14.40
1109.00	742+08.00	753+17.00	2218.00	277.25	1109.00	0.00	302.45	33.60
8423.63	753+17.00	837+40.63	16847.26	2105.90	0.00	0.00	2297.18	255.24
TOTAL:			61637.26	7736.64	3138.00	851.00	8569.16	951.50
USE:			61638	7737	3138	851	8570	952

ITEM	ACTUAL TOTAL
PAINT PAVEMENT MARKING LINE, 4"	73364
SHORT TERM PAVEMENT MARKINGS	8570
WORK ZONE PAVEMENT MARKING REMOVAL	952