

*I*: Non-composite moment of inertia of beam section (in.<sup>4</sup>).  
*I'*: Composite moment of inertia of beam section (in.<sup>4</sup>).  
*S<sub>b</sub>*: Non-composite section modulus for the bottom fiber of the prestressed beam (in.<sup>3</sup>).  
*S<sub>b</sub>'*: Composite section modulus for the bottom fiber of the prestressed beam (in.<sup>3</sup>).  
*S<sub>t</sub>*: Non-composite section modulus for the top fiber of the prestressed beam (in.<sup>3</sup>).  
*S<sub>t</sub>'*: Composite section modulus for the top fiber of the prestressed beam (in.<sup>3</sup>).  
*DC1*: Un-factored non-composite dead load (kips/ft.).  
*M<sub>DC1</sub>*: Un-factored moment due to non-composite dead load (kip-ft.).  
*DC2*: Un-factored long-term composite (superimposed excluding future wearing surface) dead load (kips/ft.).  
*M<sub>DC2</sub>*: Un-factored moment due to long-term composite (superimposed excluding future wearing surface) dead load (kip-ft.).  
*DW*: Un-factored long-term composite (superimposed future wearing surface only) dead load (kips/ft.).  
*M<sub>DW</sub>*: Un-factored moment due to long-term composite (superimposed future wearing surface only) dead load (kip-ft.).  
*M<sub>L + IM</sub>*: Un-factored live load moment plus dynamic load allowance (impact) (kip-ft.).


INTERIOR BEAM MOMENT TABLE		
		0.5 Span
<i>I</i>	(in. <sup>4</sup> )	545,894
<i>I'</i>	(in. <sup>4</sup> )	1,003,015
<i>S<sub>b</sub></i>	(in. <sup>3</sup> )	14,915.0
<i>S<sub>b</sub>'</i>	(in. <sup>3</sup> )	19,558.5
<i>S<sub>t</sub></i>	(in. <sup>3</sup> )	15,421.0
<i>S<sub>t</sub>'</i>	(in. <sup>3</sup> )	48,414.9
<i>DC1</i>	(k/ft)	1.50
<i>M<sub>DC1</sub></i>	(k)	2,700
<i>DC2</i>	(k/ft)	0.15
<i>M<sub>DC2</sub></i>	(k)	270
<i>DW</i>	(k/ft)	0.30
<i>M<sub>DW</sub></i>	(k)	540
<i>M<sub>L + IM</sub></i>	(k)	2,160.0

INTERIOR BEAM REACTION TABLE		
		Abuts.
* <i>R<sub>DC1</sub></i>	(k)	136.0
<i>R<sub>DC2</sub></i>	(k)	9.0
<i>R<sub>DW</sub></i>	(k)	18.0
* <i>R<sub>L + IM</sub></i>	(k)	115.6
* <i>R<sub>Total</sub></i>	(k)	278.6


\* The total *R<sub>DC1</sub>*, *R<sub>L + IM</sub>* and *R<sub>Total</sub>* include Reaction from Approach Slab.

**Notes:**  
 All material for bracing shall be hot dip galvanized according to AASHTO M111 unless otherwise noted.  
 Two hardened washers are required for each set of oversized holes.  
 All holes shall be <sup>15</sup>/<sub>16</sub>" φ unless otherwise noted.  
<sup>5</sup>/<sub>16</sub>" x 3" x 3" plate washers are required over all slotted holes.  
 All bolts shall be galvanized according to AASHTO M232.  
 Bracing shall be installed as beams are erected and tightened as soon as possible during erection.  
 Permanent bracing shall not be paid for separately, but shall be included in the cost of Furnishing and Erecting Precast Prestressed Concrete Bulb T-Beams.

\*\* Fabricator shall locate to miss strands within permissible tolerances.



**PERMANENT BRACING DETAIL "D" FOR BULB-T BEAMS**



**DETAIL A**

**HOELSCHER ENGINEERING**  
 Fairview Heights, IL  
 Springfield, IL  
 Champaign, IL

FILE NAME = IL104 over Liehr Creek.dgn	USER NAME =	DESIGNED - CMW	REVISED -
		CHECKED - SAL	REVISED -
	PLOT SCALE =	DRAWN - TJW	REVISED -
	PLOT DATE =	CHECKED - SAL	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**FRAMING PLAN**  
**F.A.P.-745 (IL 104) OVER LIEHR CREEK - S.N. 075-0512**

SHEET NO. 13 OF 22 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
745	108B-2	PIKE	64	37
CONTRACT NO. 72981				

FED. RD. DIST. NO. 6 ILLINOIS FED. AID PROJECT