

PAVED SHOULDER REMOVAL

PALM RD/ E. LAKE SHORE DR.

STATION	TO	STATION		AVG WIDTH NB	AVG WIDTH SB	QUANTITY (SQ YD)		TOTAL (SQ YD)	STATION	TO	STATION		AVG WIDTH NB	AVG WIDTH SB	QUANTITY (SQ YD)		TOTAL (SQ YD)
						NB	SB								NB	SB	
192+75.00		193+00.00	LT		2.36		6.56	6.56	199+00.00		199+25.00	RT	3.15		8.74		8.74
193+00.00		193+25.00	LT		2.29		6.36	6.36	199+25.00		199+50.00	RT	3.39		9.42		9.42
193+25.00		193+50.00	LT		2.18		6.06	6.06	199+50.00		199+75.00	RT	3.45		9.58		9.58
193+50.00		193+75.00	LT		2.20		6.10	6.10	199+75.00		200+00.00	RT	3.49		9.69		9.69
193+75.00		194+00.00	LT		2.33		6.46	6.46	200+00.00		200+25.00	RT	3.50		9.71		9.71
194+00.00		194+25.00	LT		2.31		6.40	6.40	200+25.00		200+50.00	RT	3.51		9.75		9.75
194+25.00		194+50.00	LT		2.13		5.90	5.90	200+50.00		200+75.00	RT	3.53		9.79		9.79
194+50.00		194+75.00	LT		1.85		5.14	5.14	200+75.00		201+00.00	RT	3.49		9.69		9.69
194+75.00		195+00.00		2.97	1.68	8.24	4.65	12.89	201+00.00		201+25.00	LT		1.19		3.31	3.31
195+00.00		195+25.00		3.55	2.01	9.85	5.57	15.42	201+00.00		201+25.00	RT		1.57		4.36	4.36
195+25.00		195+50.00		3.56	2.58	9.88	7.17	17.04	201+00.00		201+25.00	LT	1.70		4.71		4.71
195+50.00		195+75.00		3.57	2.70	9.92	7.50	17.42	201+00.00		201+25.00	RT	1.67		4.63		4.63
195+75.00		196+00.00		3.59	2.44	9.96	6.76	16.72	201+25.00		201+50.00	LT		2.48		6.88	6.88
196+00.00		196+25.00		3.56	2.45	9.89	6.81	16.69	201+25.00		201+50.00	RT		3.11		8.64	8.64
196+25.00		196+50.00		3.51	2.72	9.74	7.56	17.29	201+25.00		201+50.00	LT	3.45		9.57		9.57
196+50.00		196+75.00		3.55	2.72	9.85	7.56	17.40	201+25.00		201+50.00	RT	3.25		9.01		9.01
196+75.00		197+00.00		3.68	2.50	10.21	6.93	17.14	201+50.00		201+75.00	LT		2.62		7.28	7.28
197+00.00		197+25.00		3.76	2.47	10.43	6.85	17.28	201+50.00		201+75.00	RT		3.08		8.56	8.56
197+25.00		197+50.00		3.79	2.59	10.51	7.18	17.69	201+50.00		201+75.00	LT	3.44		9.54		9.54
197+50.00		197+75.00		3.58	2.71	9.93	7.51	17.44	201+50.00		201+75.00	RT	3.14		8.71		8.71
197+75.00		198+00.00		3.38	2.98	9.38	8.26	17.64	201+75.00		202+00.00	LT		2.72		7.54	7.54
198+00.00		198+25.00		3.40	3.09	9.44	8.58	18.03	201+75.00		202+00.00	RT		3.08		8.56	8.56
198+25.00		198+50.00		3.40	3.08	9.44	8.54	17.99	201+75.00		202+00.00	LT	3.34		9.26		9.26
198+50.00		198+75.00	RT	3.24	1.57	8.99	4.36	13.35	201+75.00		202+00.00	RT	3.20		8.88		8.88
198+75.00		199+00.00	RT	3.01		8.35		8.35	202+00.00		202+25.00	LT		2.72		7.54	7.54
PROJECT SUB-TOTAL (SQ YD) PG 1								324.73									203.33