

SCHEDULE OF QUANTITIES

PIPE CULVERT REMOVAL

TYP. SEC. #	LOCATION	QUANTITY (FOOT)
	[F. A. U. 7998 (CHATHAM RD)] WB	
(7)	STA. 93+98.00 TO STA. 94+23.00 RT	25
PROJECT TOTAL		25

PIPE CULVERTS, CLASS D, TYPE 1 24"

TYP. SEC. #	LOCATION	QUANTITY (FOOT)
	[F. A. U. 7998 (CHATHAM RD)] WB	
(7)	STA. 93+98.75 TO STA. 94+22.25 RT	23.50
(7)	STA. 95+55.75 TO STA. 95+84.25 RT	28.50
PROJECT TOTAL		52

STONE RIPRAP, CLASS A4

TYP. SEC. #	LOCATION	QUANTITY (SQ YD)
	[F. A. U. 8159 (OLD US 66/E. LAKE SHORE DR SB)]	
	NW QUADRANT OF INTERSECTION (MEASURED USING CADD)	
(6)	STA. 201+22.00 TO STA. 201+43.00 LT	52.91
	[F. A. U. 7998 (CHATHAM RD)] WB	
	NW QUADRANT OF INTERSECTION (MEASURED USING CADD)	
(7)	STA. 97+28.00 TO STA. 97+50.00 RT	42.44
PROJECT TOTAL		96

FILTER FABRIC

TYP. SEC. #	LOCATION	QUANTITY (SQ YD)
	[F. A. U. 8159 (OLD US 66/E. LAKE SHORE DR SB)]	
	NW QUADRANT OF INTERSECTION (MEASURED USING CADD)	
(6)	STA. 201+22.00 TO STA. 201+43.00 LT	52.91
	[F. A. U. 7998 (CHATHAM RD)] WB	
	NW QUADRANT OF INTERSECTION (MEASURED USING CADD)	
(7)	STA. 97+28.00 TO STA. 97+50.00 RT	42.44
PROJECT TOTAL		96

METAL END SECTION 24"

TYP. SEC. #	LOCATION	QUANTITY (EACH)
	[F. A. U. 7998 (CHATHAM RD)]	
(7)	STA 93+98.75, 66.76' LT	1
(7)	STA 94+22.25, 66.70' LT	1
(7)	STA 95+55.75, 65.49' LT	1
(7)	STA 95+84.25, 65.45' LT	1
PROJECT TOTAL		4

AGGREGATE BASE COURSE, TYPE B

TYP. SEC. #	LOCATION	QUANTITY (TON)
	[F. A. U. 7998 (CHATHAM RD)]	
(7)	STA. 94+10.00 LT	3.16
(7)	STA. 95+70.00 LT	3.05
PROJECT TOTAL		7