INDEX OF SHEETS

1	COVER SHEET
2	GENERAL NOTES
3 - 4	SUMMARY OF QUANTITIES
5 - 6	SCHEDULE OF QUANTITIES
7 - 8	TYPICAL SECTIONS
9 - 24	PLAN AND PROFILE SHEETS
25 - 41	CROSS SECTIONS
42	RUMBLE STRIP DETAIL

NOTES

1. ANY REFERENCE TO A STANDARD IN THE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION, AS INDICATED BY THE SUB-NUMBER LISTED IN THE INDEX OF SHEETS, OR THE COPY OF THE STANDARD INCLUDED IN THE PLANS

2. NO EXCAVATION ANTICIPATED ON THIS PROJECT WHICH WOULD AFFECT UTILITIES SHOULD ANY EXCAVATION BE REQUIRED, J.U.L.I.E SHALL BE NOTIFIED A MINIMUM OF 48 HOURS IN ADVANCE (800) 892-0123

3. ACCESS MUST BE MAINTAINED TO ALL EXISTING PROPERTIES DURING CONSTRUCTION PER ARTICLE 107.09 UNLESS ARRANGEMENTS ARE MADE IN WRITING BY THE CONTRACTOR WITH THE PROPERTY OWNERS WITH A COPY TO THE ENGINEER FOR SHORT-TERM CLOSURES

4. THE DISTRICT BUREAU OF OPERATIONS SHALL BE NOTIFIED AT LEAST 14 DAYS PRIOR TO PLACEMENT OF FINAL PAVEMENT MARKINGS. PHONE: (217) 782-7314

HIGHWAY STANDARDS

000001-06
442201-03
701001-02
701006-03
701011-02
701201-04
701301-04
701306-03
701311-03
701326-04
701901-01
781001-03

MIXTURE REQUIREMENTS

The following mixture requirements are applicable for this project:

Location(s):	FAS 1610 (Old US 36)			
Mixture Use(s):	Pavement Patching	HMA Shoulder Mix	HMA Surface Course	Incidental HMA Surfacing
PG:	PG 64-22	PG 58-22	PG 64-22	PG 64-22
Design Air Voids:	4.0% @ N50	2.0% @ N30	4.0% @ N50	4.0% @ N50
Mixture Composition:	IL 19.0	BAM	IL 9.5 or 12.5	IL 9.5 or 12.5
Friction Aggregate:	N/A	N/A	Mix C	Mix C

DISTRICT SIX

EXAMINED FEB 17 20 11
OPERATIONS ENGINEER

EXAMINED MARCH 4 20 11
PROJECT IMPLEMENTATION ENGINEER

EXAMINED FEBRUARY 17 20 11
PROGRAM DEVELOPMENT ENGINEER

FILE NAME =	USER NAME = shoultzjr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES
c:\pw_work\pwidot\katusabej-\d0222058\D72D84-sht-gennote.dgn		DRAWN -	REVISED -		
	PLOT SCALE = 40.0000 ' / in.	CHECKED -	REVISED -		
	PLOT DATE = Aug-25-2011 02:07:02PM	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1610	22RS-10	SCOTT	42	2
		CONTRACT NO. 72D84		
		ILLINOIS FED. AID PROJECT		