

STATION RANGE			WIDTH	LENGTH	AREA	1.5" HMA SURF. REM.	1.5" HMA SURF. CRS	BIT MATLS PC	SHORT TERM PAVT MKG	WORK ZONE PAVT MKG REM	RAISED PAVT MKR REM	RAISED REF PAVT. MKR	HMA SURF. REM. BUTT JT	TEMP RAMP
			(FT)	(FT)	(SQ YD)	(SQ YD)	(TON)	(TON)	(FT)	(SQ FT)	(EACH)	(EACH)	(SQ YD)	(SQ YD)
MAINLINE RESURFACING														
291+20	TO	322+95	22	3,175	7,881	7,881	662	3	318	106	79	79	37	12
322+95	TO	328+67	22	572	1,420	1,420	119	1	57	19	14	14	--	--
328+67	TO	331+05	22	238	591	591	50	0.22	24	8	6	6	--	--
331+05	TO	334+62	22	357	886	886	74	0.34	36	12	9	9	--	--
STA. EQN: 334+62 (BK) = 344+46 (AH)														
344+46	TO	344+55	22	9	22	22	2	0.01	1	0.30	1	1	37	12
Totals				4,351	10,800	10,800	907	4.10	435	145	110	110	74	25

STATION RANGE			WIDTH	LENGTH	AREA	6.5" HMA SHLDR MIX	1.5" HMA SURF. CRS
			(FT)	(FT)	(SQ YD)	(SQ YD)	(TON)
4' SAFETY SHOULDERS							
291+20	TO	322+95	8	3,175	2,822	2,822	237
322+95	TO	328+67	8	572	508	508	43
328+67	TO	331+05	8	238	212	212	18
331+05	TO	334+62	8	357	317	317	27
STA. EQN: 334+58 (BK) = 344+46 (AH)							
344+46	TO	344+55	8	9	8	8	1
TOTAL				4,351	3,868	3,868	325

PAINT PAVEMENT MKG LINE 5"	(FT)
Edge Line	8,702
Centerline	8,702
TOTAL	17,404

PAVEMENT PATCHING	(SQ YD)
TYPE I, 12 INCH	10
TYPE II, 12 INCH	170
TYPE II, 12 INCH	145
TYPE II, 12 INCH	120

GUTTER REMOVAL			(FT)
291+20	TO	322+95	3,215
328+67	TO	331+05	258
TOTAL			3,473