

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	
			80% FEDERAL / 20% STATE	
			0005	
28100207	STONE RIPRAP, CLASS A4	TON	189	
28200200	FILTER FABRIC	SQ YD	115	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	66.1	
40600300	AGGREGATE (PRIME COAT)	TON	348	
40600895	CONSTRUCTING TEST STRIP	EACH	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	72	
40600990	TEMPORARY RAMP	SQ YD	22	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	14,605	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	173,844	
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	120	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,787	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	
67100100	MOBILIZATION	L SUM	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	17,573	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,929	
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	111,567	

***SPECIALTY ITEM**

FILE NAME =	USER NAME = sparksgv	DESIGNED - RTS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ei:\pv\work\p\dot\sparksgv\d0245881\0672E14-sht-500.dgn		DRAWN - RTS	REVISED -			753	(139)RS-3, (140)RS-7	SANGAMON	13	3	
PLOT SCALE = 100.0000' / 1"		CHECKED - RTS	REVISED -			CONTRACT NO. 72E14					
PLOT DATE = Aug-19-2011 06:48:02AM		DATE - 05-20-11	REVISED -			ILLINOIS FED. AID PROJECT					
					SCALE:	SHEET NO. 1 OF 2 SHEETS		STA.	TO STA.		