

AGGREGATE SHOULDER SCHEDULE										
LOCATION			DISTANCE OF RUN	LEFT SHOULDER WIDTH	RIGHT SHOULDER WIDTH	AVERAGE DEPTH	LEFT SHOULDER AREA	RIGHT SHOULDER AREA	VOLUME (LT & RT)	AGGREGATE WEDGE TYPE B
			(FOOT)	(FOOT)	(FOOT)	(INCH)	(SQ FT)	(SQ FT)	(CU YD)	(TON)
IL RTE.104										
STA 38+99.00	TO	STA 38+89.00	10.00	3.0	3.0	1.50	30.00	30.00	0.28	0.57
STA 38+89.00	TO	STA 0+00.00	3,889.00	3.0	3.0	1.50	11,667.00	11,667.00	108.03	221.46
STATION EQUATION: STA. 0+00.00 (BACK) = STA. 0+00.00 (AHEAD)										
STA 0+00.00	TO	STA 50+00.00	5,000.00	3.0	3.0	1.50	15,000.00	15,000.00	138.89	284.72
STA 50+00.00	TO	STA 100+00.00	5,000.00	3.0	3.0	1.50	15,000.00	15,000.00	138.89	284.72
STA 100+00.00	TO	STA 150+00.00	5,000.00	3.0	3.0	1.50	15,000.00	15,000.00	138.89	284.72
STA 150+00.00	TO	STA 200+00.00	5,000.00	3.0	3.0	1.50	15,000.00	15,000.00	138.89	284.72
STA 200+00.00	TO	STA 250+00.00	5,000.00	3.0	3.0	1.50	15,000.00	15,000.00	138.89	284.72
STA 250+00.00	TO	STA 300+00.00	5,000.00	3.0	3.0	1.50	15,000.00	15,000.00	138.89	284.72
STA 300+00.00	TO	STA 350+00.00	5,000.00	3.0	3.0	1.50	15,000.00	15,000.00	138.89	284.72
STA 350+00.00	TO	STA 400+00.00	5,000.00	3.0	3.0	1.50	15,000.00	15,000.00	138.89	284.72
STA 400+00.00	TO	STA 404+00.00	400.00	3.0	3.0	1.50	1,200.00	1,200.00	11.11	22.78
STA 404+00.00	TO	STA 405+00.00	100.00	3.0	3.0	1.50	300.00	300.00	2.78	5.69
STA 405+00.00	TO	STA 412+50.00	750.00	4.0	4.0	1.50	3,000.00	3,000.00	27.78	56.94
STA 412+50.00	TO	STA 413+50.00	100.00	3.0	3.0	1.50	300.00	300.00	2.78	5.69
STA 413+50.00	TO	STA 447+72.00	3,422.00	3.0	3.0	1.50	10,266.00	10,266.00	95.06	194.86
STA 447+72.00	TO	STA 447+82.00	10.00	3.0	3.0	1.50	30.00	30.00	0.28	0.57
TOTALS:							146,793.00	146,793.00	1,359.19	2,786.34

TEMPORARY RAMPS		
LOCATION	WIDTH ACROSS PAVEMENT	TEMPORARY RAMP
	(FOOT)	(SQ YD)
IL 104		
BEGINNING OF PROJECT	24.0	10.7
END OF PROJECT	24.0	10.7
TOTALS:		
	48.0	21.4

SHORT TERM PAVEMENT MARKING						
LOCATION			DISTANCE OF RUN	SHORT TERM PAVEMENT MARKING CENTERLINE (YELLOW, 4' DASH - 36' SKIP)	SHORT TERM PAVEMENT MARKING EDGELINE DIAGONALS, LT. & RT. (WHITE, 4' DASH @ 100' CTRS)	SHORT TERM PAVEMENT MARKING REMOVAL
			(FOOT)	(FOOT)	(FOOT)	(SQ FT)
IL 104						
STA 38+99.00	TO	STA 38+89.00	10.00	4.00	8.00	4.0
STA 38+89.00	TO	STA 0+00.00	3,889.00	388.90	312.00	233.6
STA. EQUATION: 0+00.00 (BACK) = 0+00.00 (AHEAD)						
STA 0+00.00	TO	STA 50+00.00	5,000.00	500.00	400.00	300.0
STA 50+00.00	TO	STA 100+00.00	5,000.00	500.00	400.00	300.0
STA 100+00.00	TO	STA 150+00.00	5,000.00	500.00	400.00	300.0
STA 150+00.00	TO	STA 200+00.00	5,000.00	500.00	400.00	300.0
STA 200+00.00	TO	STA 250+00.00	5,000.00	500.00	400.00	300.0
STA 250+00.00	TO	STA 300+00.00	5,000.00	500.00	400.00	300.0
STA 300+00.00	TO	STA 350+00.00	5,000.00	500.00	400.00	300.0
STA 350+00.00	TO	STA 400+00.00	5,000.00	500.00	400.00	300.0
STA 400+00.00	TO	STA 447+72.00	4,772.00	477.20	384.00	287.1
STA 447+72.00	TO	STA 447+82.00	10.00	4.00	8.00	4.0
TOTALS:			48,681.00	4,874.10	3,912.00	2,928.70
TOTALS FOR TWO APPLICATIONS:				9,748.2	7,824.00	

FILE NAME =	USER NAME = sparksgw	DESIGNED - RTS	REVISED -
c:\pwork\pwork\sparksgw\0245881\0672E14-sht-schedule.dgn		DRAWN - RTS	REVISED -
PLOT SCALE = 40.0000' / in.		CHECKED -	REVISED -
PLOT DATE = Aug-19-2011 06:44:53AM		DATE - 05-9-11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 2 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
753	(139)RS-3, (140)RS-7	SANGAMON	13	9
CONTRACT NO. 72E14				
ILLINOIS FED. AID PROJECT				