

RESURFACING SCHEDULE	LENGTH	PAVEMENT WIDTH	AREA	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2"	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N90	HOT-MIX ASPHALT SHOULDERS, 1 1/2"	AGGREGATE SHOULDERS, TYPE B	TEMPORARY RAMP
163+53.00 TO 210+50.00	4697.0	25.0	13047.2	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	493.8	0.0
210+50.00 TO 211+00.00	50.0	25.0	138.9	0.0	0.0	138.9	13.9	0.3	11.7	0.0	55.6	5.7	13.9
211+00.00 TO 216+87.00	587.0	25.0	1630.6	1630.6	0.0	0.0	326.1	6.5	137.0	1001.7	652.2	66.9	0.0
216+87.00 TO 224+75.00	788.0	25.0	2188.9	2188.9	0.0	0.0	437.8	8.8	183.9	1889.5	819.4	71.4	0.0
224+75.00 TO 225+70.00	95.0	25.0	263.9	0.0	263.9	0.0	26.4	0.5	22.2	0.0	105.6	10.8	13.9
225+70.00 TO 231+45.00	575.0	25.0	1597.2	0.0	1597.2	0.0	159.7	3.2	134.2	0.0	33.7	33.7	0.0
231+45.00 TO 232+25.00	80.0	25.0	222.2	0.0	222.2	0.0	22.2	0.4	18.7	0.0	88.9	9.1	13.9
232+25.00 TO 242+50.00	1025.0	25.0	2847.2	2847.2	0.0	0.0	569.4	11.4	239.2	2453.5	1138.9	116.7	0.0
242+50.00 TO 243+70.00	120.0	25.0	333.3	0.0	333.3	0.0	33.3	0.7	28.0	0.0	133.3	9.2	13.9
243+70.00 TO 259+50.00	1580.0	25.0	4388.9	0.0	4388.9	0.0	438.9	8.8	368.7	0.0	140.3	140.3	0.0
259+50.00 TO 260+25.00	75.0	25.0	208.3	0.0	208.3	0.0	20.8	0.4	17.5	0.0	83.3	8.5	13.9
260+25.00 TO 266+25.00	600.0	25.0	1666.7	1666.7	0.0	0.0	333.3	6.7	140.0	948.2	628.3	60.5	0.0
266+25.00 TO 267+00.00	75.0	25.0	208.3	0.0	0.0	208.3	20.8	0.4	17.5	0.0	83.3	8.5	13.9
267+00.00 TO 339+01.36	7201.4	25.0	20003.8	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	621.2	0.0
339+01.36 BK= 339+00.00 AH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
339+00.00 TO 349+13.88	1013.9	25.0	2816.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	100.6	0.0
349+13.88 TO 349+46.13	32.3	25.0	89.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
349+46.13 TO 484+00.00	13453.9	25.0	37371.9	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1308.7	0.0
484+00.00 TO 530+60.00	4660.0	25.0	12944.4	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	493.6	0.0
TOTALS =				8333.0	7014.0	347.0	2403.0	48.0	1319.0	6293.0	3789.0	3559.0	83.0

EARTHWORK SCHEDULE	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EARTH FILL	EARTHWORK BALANCE, WASTE (+) OR SHORTAGE (-)
210+50.00 TO 216+87.00	116.4	87.3	679.5	-592.2
216+87.00 TO 225+70.00	215.9	161.9	900.3	-738.3
231+45.00 TO 243+70.00	336.8	252.6	1306.6	-1054.0
259+50.00 TO 267+00.00	100.1	75.1	651.7	-576.6
TOTALS =	769.0	577.0	3538.0	-2961.0

• MACON & PIATT

FILE NAME =	USER NAME = swartzrn	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pe_work\pwidot\swartzrn\d0156168\d77422-sht-schedule.dgn	PLOT SCALE = 50.0000' / in.	DRAWN -	REVISED -					741	(11,12)T	•	85	10
PLOT DATE = 9/16/2011	DATE -	CHECKED -	REVISED -		CONTRACT NO. 74422			ILLINOIS FED. AID PROJECT				
					SCALE: NA	SHEET NO. 1 OF 5 SHEETS	STA. TO STA.					