

GENERAL NOTES

Reinforcement bars shall conform to the requirements of ASTM A 706 Gr 60. See Special Provisions.

Reinforcement bars designated (E) shall be epoxy coated.

Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.

The minimum thickness of the concrete overlay shall be 5" and varies as required to adjust for the new profile grade and beam camber.

Repair of the substructure shall be completed prior to placement of the new beams.

STATION 812+14.95
REBUILT 20__ BY
STATE OF ILLINOIS
F.A.P. RT. 132 SEC. 103BR-1
LOADING HL-93
STRUCTURE NO. 076-0025

NAME PLATE

See Std. 515001


Note: The existing name plate shall be cleaned and relocated adjacent to the new plate. Cost included with Name Plates.

TOTAL BILL OF MATERIAL

ITEM	UNIT	SUPER	SUB	TOTAL
Removal of Existing Superstructures	Each	1	-	1
Concrete Removal	Cu. Yd.	-	5.3	5.3
Concrete Structures	Cu. Yd.	-	29.5	29.5
Concrete Superstructure	Cu. Yd.	103.4	-	103.4
Bridge Deck Grooving	Sq. Yd.	1143	-	1143
Protective Coat	Sq. Yd.	1221	-	1221
Precast Prestressed Concrete Deck Beams (21" Depth)	Sq. Ft.	8836	-	8836
Reinforcement Bars, Epoxy Coated	Pound	39,000	800	39,800
Bar Splicers	Each	414	80	494
Steel Railing, Type SM	Foot	585	-	585
Name Plates	Each	1	-	1
Preformed Joint Strip Seal	Foot	76	-	76
Concrete Wearing Surface, 5"	Sq. Yd.	983	-	983
Structural Repair of Concrete (Depth equal to or less than 5 inches)	Sq. Ft.	-	84	84
Asbestos Bearing Pad Removal	Each	44	-	44

INDEX OF SHEETS

- 1 General Plan
- 2 General Data
- 3 Stage Construction Details
- 4 Temporary Concrete Barrier for Stage Construction
- 5,6 Top of Approach Slab Elevations
- 7 Superstructure
- 8,9 Bridge Approach Slab Details
- 10-13 PPC Deck Beam Details
- 14,15 Superstructure Details
- 16 Steel Railing Details, Type SM with Concrete Wearing Surface
- 17 Preformed Joint Strip Seal
- 18 South Abutment Details
- 19 North Abutment Details
- 20 Pier 1 & 2
- 21 Pier 3 & 4
- 22 Bar Splicer Assembly and Mechanical Splicer Details



RAILING ELEVATION

HANSON
 PROFESSIONAL DESIGN FIRM LICENSE #184-001084
 © Copyright Hanson Professional Services Inc. 2011

FILE NAME = 0760025_78164-002-GENERAL_NOTES.dgn	USER NAME = cox01283	DESIGNED - BWC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL DATA STRUCTURE NO. 076-0025	F.A.P. RTE. 132	SECTION 103BR-1	COUNTY POPE	TOTAL SHEETS 38	SHEET NO. 18
PLOT SCALE =	DRAWN - BWC	REVISED -	CONTRACT NO. 78164							
PLOT DATE = 07/01/2011	CHECKED - MNM	REVISED -	ILLINOIS FED. AID PROJECT							
SHEET NO. 2 OF 22 SHEETS										