## INDEX OF SHEETS

SHEET NO. DESCRIPTION

COVER

- SUMMARY OF QUANTITIES, TYPICAL SECTIONS GENERAL NOTES AND TRAFFIC CONTROL PLAN
- PLAN AND PROFILE 4-7 CROSS SECTIONS
- GENERAL PLAN AND ELEVATION
- P.P.C. DECK BEAM SUPERSTRUCTURE 9 - 10
  - BEAM DETAILS
- ABUTMENT DETAILS 12
- METAL SHELL PILE DETAILS 13
  - STEEL RAILING, TYPE S-1 DETAILS

## HIGHWAY STANDARDS

515001-03 -NAME PLATES FOR BRIDGES 701901-01 -TRAFFIC CONTROL DEVICES

BLR 21-8 -TRAFFIC CONTROL DEVICES RURAL LOCAL HWYS.

BLR 23-3 -TRAFFIC BARRIER TERMINAL, TYPE 1

BLR 26-2 -STEEL PLATE BEAM GUARD RAIL (27.5" HT.)

BLR 27-1 -TRAFFIC BARRIER TERMINAL, TYPE 5A

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

DIVISION OF HIGHWAYS

BUREAU OF LOCAL ROADS / STREETS

PLANS FOR PROPOSED

SURFACE TRANSPORTATION/RURAL PROGRAM

HANCOCK COUNTY COUNTY HIGHWAY 14 PROJECT NO. RS-0067(143) SECTION 94-00091-00-BR STRUCTURE NO. 034-3141 JOB NO. C-96-264-10

## RANGE 5 WEST SEC. 94-00091-00-BR STA, 13+00 SEC. 94-00091-00-BR

LOCATION MAP 1 MI. APROX. SCALE: 1" = 1 MILE


4TH PRINCIPAL MERIDIAN


DESIGN CLASSIFICATION: RURAL LOCAL ROAD DESIGN ADT (2011) = 300 DESIGN SPEED = 40 MPH



062-032351 EXP. DATE 11/30/11 THIS SEAL COVERS SHEETS: 1-7

COUNTY TOTAL SHEET SHEETS NO. SECTION C.H. 14 94-00091-00-BR HANCOCK 14





100 SOUTH 54TH STREET QUINCY, ILLINOIS PH (217) 223-4605 FAX (217) 223-1546 DESIGN FIRM REGISTRATION

PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

## PROJECT DESCRIPTION

SEC. 94-00091-00-BR CONSIST OF THE CONSTRUCTION OF A 55.50' (B-B ABUT.) PRECAST PRESTRESSED CONCRETE DECK BEAM BRIDGE WITH THE NECESSARY BRIDGE APPROACH ADJUSTMENTS.

EXISTING STRUCTURE NO. 034-3140 A 27' X 22' CONCRETE SLAB BRIDGE WITH CLOSED ABUTMENTS AND

PROPOSED STRUCTURE NO. 034-3141 A SINGLE SPAN PRECAST PRESTRESSED CONCRETE DECK BEAM BRIDGE ON PILE BENT ABUTMENTS. 55'-6" B-B ABUTMENTS 30'-0" O-O DECK

PLAN HORZ.

PROFILE HORZ.

3. 1( CROSS SECTIONS 5: 1

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION

201

4

DALLAS RURAL WATER DIST. ----FERRIS, IL

GROSS LENGTH OF IMPROVEMENT = 600.00 FEET STRUCTURE LENGTH = 55.50 FEET NET LENGTH OF IMPROVEMENT = 600.00 FEET (0.114 MILES)