# **SCHEDULE OF QUANTITIES**

## 28000250 TEMPORARY EROSION CONTROL SEEDING

	POUND	<b>STATION</b>		<b>STATION</b>	(DIR)	<u>REMARKS</u>
	32	1207+38	TO	1207+88	EB	INCLUDES APROX. 50' ACCESS PATH TO SITE
	15	1325+05			EB	ON A FORESLOPE < 1:3 W/IN CZ INCLUDES APPROX 25' PATH
	15	1325+40			EB	ON A FORESLOPE < 1:3 W/IN CZ INCLUDES APPROX 25' PATH
	15	1510+21			WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
	15	1516+11			WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
	15	1522+10			WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
	15	1524+98			WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
	15	1524+98			WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
	15	1556+49			WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
	15	1592+13			WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
	15	1592+94			WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
	15	1630+04			WB	INCLUDES APPROX. 25' ACCESS PATH TO SITE
	15	1630+45			WB	25 UNIT SIZED TREE
	15	1631+89			WB	25 UNIT SIZED TREE
	15	1633+66			WB	32 UNIT SIZED TREE
	15	1639+17			WB	20 UNIT SIZED TREE
	8	1636+42	TO	1636+70	WB	INCLUDES APROX. 25' ACCESS PATH TO SITE
TOTAL	265					

## 28000305 TEMPORARY DITCH CHECKS

	<u>FOOT</u>	<u>STATION</u>		<b>STATION</b>	<u>(DIR)</u>	REMARKS
	40	1207+38	TO	1209+23	EB	40' SPACING FOR DISTURBANCES WITHIN TREE REMOVAL AREAS
	8	1636+42	TO	1636+70	WB	
TOTAL	48					

# 28000400 PERIMETER EROSION BARRIER

	<b>FOOT</b>	<u>STATION</u>		<b>STATION</b>	(DIR)	<b>REMARKS</b>
	205	1207+38	TO	1209+23	EB	
	48	1636+42	TO	1636+70	WB	
TOTAL	253					

## 30300001 AGGREGATE SUBGRADE IMPROVEMENT

	<u>CU YD</u>	<u>STATION</u>	(DIR)	<u>REMARKS</u>
	44	VAR.	BOTH	AS NEEDED TO REPLACE POOR SUBGRADE UNDER PATCHES
ΤΩΤΔΙ	44			

# 40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50

	<b>TONS</b>	<b>STATION</b>	(DIR)	<u>REMARKS</u>
	31	1269+28	BOTH	2.25" PAVING ON U-TURN
	31	1396+47	BOTH	2.25" PAVING ON U-TURN
	28	1500+00	BOTH	2.25" PAVING ON U-TURN
	51	1638+84	BOTH	2.25" PAVING ON U-TURN
	28	1733+50	BOTH	2.25" PAVING ON U-TURN
	28	1829+00	BOTH	2.25" PAVING ON U-TURN
TOTAL	197			

## 50105220 PIPE CULVERT REMOVAL

	<u>FOOT</u>	<u>STATION</u>	(DIR)	<u>REMARKS</u>
	16	1875+94	EB	LAST TWO SECTIONS OF 48" PIPE (ALONG W/ END SECTION)
TOTAL	16			

## 54260311 TRAVERSABLE PIPE GRATE

	<u>FOOT</u>	<u>STATION</u>	(DIR)	REMARK
	47'-9"	1875+94	EB	
TOTAL	48			

# 54261448 CONCRETE END SECTION, STANDARD 542001, 48", 1:4

	<b>EACH</b>	<u>STATION</u>	(DIR)	<u>REMARKS</u>
	1	1875+94	EB	
TOTAL	1			

#### 63500105 DELINEATORS

	<b>EACH</b>	<b>STATION</b>		<b>STATION</b>	(DIR)	<u>REMARKS</u>
	200	1020+30	TO	1929+96	BOTH	AS NEEDED TO REPLACE MISSING DELINEATORS
TOTAL	200					

## 64200116 SHOULDER RUMBLE STRIPS, 16 INCH

	<u>FOOT</u>	<u>STATION</u>		<b>STATION</b>	(DIR)	<u>REMARKS</u>
	85269	1020+30	TO	1929+96	EB	INSIDE SHOULDERS MINUS CROSSOVERS
	85456	1020+30	TO	1929+96	EB	OUTSIDE SHOULDERS MINUS RAMPS
	85269	1020+30	TO	1929+96	WB	INSIDE SHOULDERS MINUS CROSSOVERS
	85456	1020+30	TO	1929+96	WB	OUTSIDE SHOULDERS MINUS RAMPS
TOTAL	2/1/50					

#### 70300100 SHORT TERM PAVEMENT MARKING

	<u>FOOT</u>	<u>STATION</u>		<u>STATION</u>	<u>(DIR)</u>	<u>REMARKS</u>
	45500	1020+30	TO	1929+96	EB	10'/40' CYCLE, TWO LIFTS
	45500	1020+30	TO	1929+96	WB	10'/40' CYCLE, TWO LIFTS
	3200	1028+48	TO	1091+13	BOTH	10'/40' CYCLE, TWO LIFTS AT AUXILERY LANES
	14560	1020+30	TO	1929+96	EB	4'/100' CYCLE, TWO LIFTS ON TWO SHOULDERS
	14560	1020+30	TO	1929+96	WB	4'/100' CYCLE, TWO LIFTS ON TWO SHOULDERS
	1560	VARIOUS, ALL	. RAMPS		BOTH	4'/100' CYCLE, TWO LIFTS ON TWO SHOULDERS
TOTAL	124880					

#### 70301000 WORK ZONE PAVEMENT MARKING REMOVAL

	SQ FT	STATION		STATION	(DIR)	REMARKS
	7583	1020+30	TO	1929+96	EB	
	7583	1020+30	TO	1929+96	WB	
	533	1028+48	TO	1091+13	BOTH	
	2427	1020+30	TO	1929+96	EB	
	2427	1020+30	TO	1929+96	WB	
	260	VARIOUS, A	LL RAMPS		BOTH	
TOTAL	20813					

• (37-4,5,6) RS-2

FILE NAME =	USER NAME = grantpm	DESIGNED -	REVISED -			9	CHEDIII E	OF QUANTITIES		F.A.I.	SECTION	COUNTY	TOTAL SH	HEET
c:\pw_work\pwidot\grantpm\d0310501\D200	11-sht-schedule.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS		J	OIILDOLL	OI COANTILLO		80	*	HENRY	80	22
	PLOT SCALE = 100.000 ' / in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION								CONTRACT		
Default	PLOT DATE = Thu Aug 21 13:07:30 2014	DATE -	REVISED -		SCALE:	SHEET	OF	SHEETS STA.	TO STA.	$\vdash$	ILL INOIS FF	D. AID PROJECT		-