SCHEDULE OF QUANTITIES

X8730810 ELECTRIC CABLE IN CONDUIT, CONOGA-30003

	FOOT	STATION	<u>(DIR)</u>	<u>REMARKS</u>
	980	1100+07	BOTH	
TOTAL	980			

Z0008758 AERIAL SPEED CHECK MARKING

	FOOT	<u>STATION</u>	<u>DIR</u>	<u>REMARKS</u>
	36	1320+00	WB	AT EXISTING LOCATION
	36	1663+20	EB	AT EXISTING LOCATION
ΤΩΤΔΙ	72			

Z0004542 HOT-MIX ASPHALT REMOVAL (SPECIAL)

	SQ YD	STATION		STATION	(DIR)	REMARKS
	119	1020+30	TO	1929+96	EB/IN	EVERY 500' AND AT SAGS WHERE NECESSARY, 18" WIDE
	297	1020+30	TO	1929+96	EB/OUT	EVERY 500' AND AT SAGS WHERE NECESSARY, 18" WIDE
	119	1020+30	TO	1929+96	WB/IN	EVERY 500' AND AT SAGS WHERE NECESSARY, 18" WIDE
	297	1020+30	TO	1929+96	WB/OUT	EVERY 500' AND AT SAGS WHERE NECESSARY, 18" WIDE
TOTAL	832					

Z0028415 GEOTECHNICAL REINFORCEMENT

	<u>SQ YD</u>	<u>STATION</u>	(DIR)	<u>REMARKS</u>
	262	VAR.	BOTH	AS NEEDED TO REPLACE POOR SUBGRADE UNDER PATCHES
TOTAL	262			

								• (37-4,5,6) RS-2			
FILE NAME =	USER NAME = grantpm	DESIGNED -	REVISED -			SCHEDULE OF QUANTITIES		F.A.I.	SECTION	COUNTY T	OTAL SHEET
c:\pw_work\pwidot\grantpm\d0310501\D2	00 11-sht-schedule.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS		SUILDOLL OF GOARTITIES		80	*	HENRY	80 25
	PLOT SCALE = 100.000 ' / 10.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION					-	CONTRACT N	NO. 64G64
Default	PLOT DATE = Thu Aug 21 13:08:12 2014	DATE -	REVISED -		SCALE:	SHEET OF SHEETS STA. T	O STA.		ILL INOIS FE	FD. AID PROJECT	