INDEX OF SHEETS

1 COVER SHEET
2 INDEX OF SHEETS / STATE STANDARDS / GENERAL NOTES
3 SUMMARY OF QUANTITIES
4-5 TRAFFIC CONTROL PLAN FOR SN 081-0120
6-7 TRAFFIC CONTROL PLAN FOR SN 081-0127
8-10 TYPICAL PAVEMENT MARKINGS (DIST STD 41.1)
11 PAINTING DETAILS (DIST STD 44.1)
12-14 EXISTING PLANS FOR SN 081-0120
15-17 EXISTING PLANS FOR SN 081-0127

STATE STANDARDS

701006-05 701101-04 701400-07 701401-08 701402-09 701426-06 701901-03 704001-07 72001-01	OFF-ROAD OPERATIONS, 2L,2W, 15' (4.5m) TO 24" (600mm) FROM PAVEMENT EDGE OFF-ROAD OPERATIONS, MULTILANE, 15' (4.5m) TO 24" (600mm) FROM PAVEMENT EDGE APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY LANE CLOSURE, FREEWAY/EXPRESSWAY WITH BARRIER LANE CLOSURE, FREEWAY/EXPRESSWAY WITH BARRIER LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATIONS, FOR SPEEDS 2 45 MPH TRAFFIC CONTROL DEVICES TEMPORARY CONCRETE BARRIER BARRIER DOSTS FOR SIGNS MARKERS & DELINEATORS
720011-01 728001-01 729001-01	METAL POSTS FOR SIGNS, MARKERS & DELINEATORS TELESCOPING STEEL SIGN SUPPORT APPLICATIONS OF TYPES A & B METAL POSTS (FOR SIGNS & MARKERS)

GENERAL NOTES

A MINIMUM OF 2 AIR MONITORS WILL BE REQUIRED TO MONITOR ABRASIVE BLASTING OPERATIONS, SEE SPECIAL PROVISION FOR "CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES".

THE CONTRACTOR SHALL SEED ALL DISTURBED AREAS WITHIN THE PROJECT LIMITS. SEEDING CLASS 2A SHALL BE USED. THIS WORK WILL BE INCLUDED IN THE CONTRACT UNIT PRICE PER LUMP SUM FOR CLEANING AND PAINTING STEEL BRIDGE NO. 1.

FERTILIZER SHALL BE APPLIED TO ALL DISTURBED AREAS AND INCORPORATED INTO THE SEEDBED PRIOR TO SEEDING OR PLACEMENT OF SOD AT THE RATE SPECIFIED IN SECTIONS 250 AND 252 OF THE STANDARD SPECIFICATIONS. THIS WORK SHALL BE INCLUDED IN THE COST OF CLEANING AND PAINTING STEEL BRIDGE NO. 1.

MULCH METHOD II SHALL BE APPLIED OVER ALL SEEDED AREAS. THIS SHALL BE INCLUDED IN THE COST OF THE CLEANING AND PAINTING STEEL BRIDGE NO. 1.

ALL BORROW/WASTE/USE SITES MUST BE APPROVED BY THE DEPARTMENT PRIOR TO REMOVING ANY MATERIAL FROM THE PROJECT OR INITIATING ANY EARTHMOVING ACTIVITIES, INCLUDING TEMPORARY STOCKPILING OUTSIDE THE LIMITS OF CONSTRUCTION.

TEMPORARY IMPACT ATTENUATORS WILL BE MEASURED AS EACH FOR EACH ATTENUATOR SUPPLIED ON THE JOB AS SPECIFIED IN THE PLANS, AND SHALL INCLUDE THE COST OF RENTING/OWNING THE ATTENUATOR FOR THE TIME REQUIRED ON THE JOB PLUS HAULING TO AND FROM THE PROJECT SITE, AS WELL AS ONE PLACEMENT AND REMOVAL FROM THE ROADWAY. THIS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER EACH FOR IMPACT ATTENUATORS, TEMPORARY OF THE TYPE SPECIFIED.

RELOCATE TEMPORARY IMPACT ATTENUATOR WILL BE PAID FOR AS EACH AND WILL BE PAID FOR EACH TIME THE ATTENUATOR IS REQUIRED BY STAGING TO BE PICKED UP AND MOVED TO A DIFFERENT LOCATION ON THE PROJECT, WHETHER IT IS TO ANOTHER LOCATION ON THE ROADWAY OR TO A STORAGE/STAGING LOCATION FOR THE PROJECT. THIS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER EACH FOR IMPACT ATTENUATORS, RELOCATE OF THE TYPE SPECIFIED.

THIS WORK SHALL BE DONE IN ACCORDANCE WITH SECTION 704 OF THE STANDARD SPECIFICATIONS. TEMPORARY CONCRETE BARRIER WILL BE MEASURED IN FEET ALONG THE CENTERLINE OF THE BARRIER AND SHALL INCLUDE THE COST OF RENTING/OWNING THE BARRIER FOR THE TIME REQUIRED ON THE JOB PLUS HAULING TO AND FROM THE PROJECT SITE, AS WELL AS ONE PLACEMENT AND REMOVAL FROM THE ROADWAY IN ACCORDANCE WITH SECTION 704 OF THE STANDARD AND SPECIFICATION. THIS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER FOOT FOR TEMPORARY CONCRETE BARRIER.

RELOCATE TEMPORARY CONCRETE BARRIER WILL BE PAID FOR IN FEET ALONG THE CENTERLINE OF THE BARRIER, AND WILL BE PAID FOR EACH TIME THE BARRIER IS REQUIRED BY STAGING TO BE PICKED UP AND MOVED TO A DIFFERENT LOCATION ON THE PROJECT, WHETHER IT IS TO ANOTHER LOCATION ON THE ROADWAY OR TO A STORAGE/STAGING LOCATION FOR THE PROJECT. THIS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER FOOT FOR RELOCATE TEMPORARY CONCRETE BARRIER.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED FOR NON-EMERGENCY WORK. THE JULIE NUMBER IS 800-892-0123.

THE SSPC OP1 & OP2 CONTRACT CERTIFICATIONS WILL BE REQUIRED FOR THIS CONTRACT.

SCALE

HAZARDS BEHIND TEMPORARY CONCRETE BARRIER WALL:

NO MATERIALS, EQUIPMENT, VEHICLES OR OTHER HAZARDS SHALL BE WITHIN 3'-6" OF THE TEMPORARY CONCRETE BARRIER WALL,
MEASURED FROM THE CLOSEST POINT OF THE BARRIER WALL PERPENDICULAR TO THE HAZARD, EQUIPMENT THAT IS ACTIVELY
WORKING WITHIN 3'-6" OF THE BARRIER WALL MAY BE ALLOWED FOR A SHORT DURATION, IF APPROVED BY THE ENGINEER,
REQUIRED FOR THE WORK ACTIVITY, AND THERE IS NOT ANOTHER METHOD TO COMOPLETE THE WORK.

FILE NAME =	USER NAME = dosadd	DESIGNED	-		REVISED	-	8-18-2014 OD	\Box
& gorneel3 81X43/bnolel Jacq\eec0/88/16	Painting SN 081-0120 & 0127\CADD\DZ-sht-cov	ORAWN	-		REVISEO	-		
	PLOT SCALE * 188.0028 '/ In.	CHECKED	-		REVISEO	~		
Onfoult	PLOT DATE < Mon Aug 18 89:28:23 2014	DATE	-		REVISED			Ė

STATI	E OF	ILLINOIS
DEPARTMENT	0F	TRANSPORTATION

INDEX OF SHEETS, STATE STANDARDS &	F.A.L. SECTION COUNTY SHEETS NO.
GENERAL NOTES	88 D2 BRIDGE PAINTING 2015-1 ROCK ISLAND 17 2
Chitaliva iiveas	CONTRACT NO. 64K16
SHEET OF SHEETS STA. TO STA.	ILLINOIS FED. AID PROJECT