

URBAN
80% FED. / 20% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				BRIDGE	ROADWAY
				0011 EXIST. S. N. 032-0041	0004 URBAN
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SO YD	534		534
35501322	HOT-MIX ASPHALT BASE COURSE, 9 1/2"	SO YD	1200		1200
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	1696		1696
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2		2
40600527	LEVELING BINDER (HAND METHOD), IL-9.5FG, N50	TON	2		2
40600627	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N50	TON	108		108
40603082	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 FG, N50	TON	653		653
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	301		301
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	6019		6019
44000100	PAVEMENT REMOVAL	SO YD	1200		1200
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	3563		3563
44004250	PAVED SHOULDER REMOVAL	SO YD	267		267
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	112		112
44213204	TIE BARS 3/4"	EACH	2427		2427

FILE NAME *	USER NAME * #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -					80	132-2MBR-6	GRUNDY	98	4
#MODELNAME#		CHECKED -	REVISED -		SCALE: SHEET NO. 4 OF 98 SHEETS STA. TO STA.			CONTRACT NO. 66B27				
		DATE -	REVISED -		ILLINOIS FED. AID PROJECT							