

MILLING & RESURFACING SCHEDULE										
STATION TO STATION	AREA	HMA SURF REM	BIT MATL	LEVEL BINDER	MIX FOR CRACKS, JOINTS, & FLGWYS	LEVEL BINDER	HMA BINDER	HMA SURF CSE	AGG SHLD	
		2 1/4"	(PRM CT)	(HM)	& FLGWYS	(MM)	IL 19.OFG	MIX "C",	TY B	
	SO YD	SO YD	POUND	N50	TON	N50	TON	N50 IL 9.5	TON	TON
4+00.0 TO 6+82.0	94									9
6+82.0 TO 11+50.0	1352	1352.0	643	0.7	0.5	57		114		
11+50 TO 13+15	434	434.0	207	0.3	0.2		315	37		
13+15.0 TO 15+75.0	BRIDGE AND APPROACH PAVEMENT OMISSION									
15+75 TO 17+50	578	578.0	276	0.3	0.2		338	49		
17+50.0 TO 21+65.0	1199	1199.0	570	0.6	0.4	51		101		
21+65.0 TO 24+14.0	83									8
TOTAL		3563.0	1696	1.9	1.3	108	653	301		17

•REPLACE THE LEVELING BINDER WITH THIS MIX WHEN THE TOTAL OVERLAY THICKNESS IS OVER 3.75"

PCC BASE CSE. WID., CC&G & SIDEWALK SCHEDULE										
STATION TO STATION	RT/LT	PCC SIDEWALK 4" SO FT	CC&G TYPE B 6.24 FOOT	PAVED SHOULDER REMOVAL SO YD	PCC BASE CSE. WID.. 9" SO YD	TIE BARS 3/4" EACH	QUANTITIES FOR CCC&GUTTER OUTLET, TYPE 2			
							CLASS SI CONC. OUTLET CU YD	GRATES & COVERS, TY 2B EACH	PIPE DRAINS, 12" FOOT	
7+05.50 TO 13+48.00	RT		642.5			642.5	2.1	1.0	15.0	
15+47.53 TO 21+28.26	RT		580.7			580.7	2.1	1.0	15.0	
6+92.00 TO 12+23.60	LT	2658	531.6			531.6	2.1	1.0	15.0	
12+23.60 TO 13+14.70	LT	456	91.1			91.1				
15+74.00 TO 16+60.00	LT	430	86.0			86.0				
16+60.00 TO 21+55.00	LT	2475	495.0			495.0	2.1	1.0	15.0	
6+92.00 TO 13+14.70	LT&RT			138.0	276.0					
15+74.00 TO 21+55.00	LT&RT			129	258					
TOTALS		6019	2426.9	267.0	534.0	2427	8.3	4.0	60.0	

•REMOVE EXISTING 1' HMA SHOULDER. REPLACE IT WITH PCC BASE CSE WIDENING, 9"

••TO TIE OFF CURB TO ADJACENT PCC BSE CSE WIDENING, AND TO TIE OFF EXISTING PAVEMENT TO THE PCC BSE CSE WIDENING-24" c-c SPACING

PAVEMENT MARKING SCHEDULE					
STATION TO STATION	PAINT PAVEMENT MARKING			BARRIER WALL MARKERS TYPE A EACH	
	WHITE 4" FOOT	YELLOW 4" FOOT	YELLOW 6" FOOT		
	6+85 TO 13+15	1260	630		
13+15 TO 15+75	520	1040		7	
15+75 TO 21+15	1080	540	135		
SUB TOTALS	2860	2210	293	7	
DOUBLE PAINT APPLICATION	5720	4420	586		
TOTALS		10140	586	7	