

GENERAL NOTES

THE THICKNESS OF HMA SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA IS PLACED.

EXCEPT AS NOTED ON THE PLANS, PAVEMENT GRADES SHOWN ARE AT THE TOP OF PAVEMENT SURFACES.

THE ENGINEER WILL BE THE SOLE JUDGE CONCERNING CURING TIME FOR THE VARIOUS HMA LIFTS.

FOR STABILIZATION, ALL TYPE III BARRICADES WILL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.

SEEDING WILL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET, OR IN AN UNTILLABLE CONDITION. LOCATIONS TO BE SEEDED WILL BE DETERMINED BY THE ENGINEER.

THE FINISHED EARTHWORK SHALL HAVE A VEGETATION SUSTAINING SOIL COVERING THE TOP FOUR INCHES (100 MILLIMETERS) IN AREAS TO BE SEEDED OR SODDED. THE VEGETATION SUSTAINING SOIL REQUIRED WILL NOT BE PAID FOR SEPARATELY BUT WILL BE INCLUDED IN THE COST OF SEEDING, CLASS 2A

SHORT TERM PAVEMENT MARKING SHALL BE USED TO OUTLINE EXIT AND ENTRANCE RAMPS FOR THE PRIME COAT APPLICATION AND EACH RESURFACING LIFT.

ALL ELEVATIONS REFERRING TO U.S.G.S. MEAN SEA LEVEL DATUM.

ABANDONED UNDERGROUND UTILITIES THAT CONFLICT WITH CONSTRUCTION SHALL BE DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT OF WAY ACCORDING TO ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT WILL BE INCLUDED IN THE COST OF EARTH EXCAVATION.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES:

GRANULAR MATERIALS	2.05	TONS / CU YD
HMA RESURFACING	112	LBS / SQ YD / IN
SHORT TERM PAVEMENT MARKING	10	FT / 100 FT OF APPLICATION
MIX FOR CRACKS, JTS & FLGWYS	0.0003	TONS / SQ YD
LEVEL BINDER (HAND METHOD)	0.0005	TONS / SQ YD

COMMITMENTS

THE TEMPORARY STEEL BEAMS UNDER THE EXISTING CONCRETE BEAMS SHALL BE SALVAGED AND DELIVERED TO A DISTRICT 3 MAINTENANCE YARD. CONTACT MR. KIP RUTLEDGE OF WATSEKA MAINTENANCE YARD (815) 432-2350 FOR ADDITIONAL INFORMATION OR TO SET UP A DELIVERARY DATE. THE COST OF REMOVING THE BEAMS AND DELIVERING THEM TO THE MAINTENANCE YARD SHALL BE INCLUDED IN THE COST OF REMOVAL OF EXISTING STRUCTURES.

Revision No.

Revision No.	DESCRIPTION
00	000001 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
02	001001 AREAS OF REINFORCEMENT BARS
	001006 DECIMAL OF AN INCH AND OF A FOOT
07	280001 TEMPORARY EROSION CONTROL SYSTEMS
02	482001 HMA SHOULDER ADJACENT TO FLEXIBLE PAVEMENT
03	482011 HMA SHOULDER STRIPS/SHOULDERS WITH RS OR WIDENING & RS PROJECT
03	515001 NAME PLATE FOR BRIDGES
04	542001 CONCRETE END SECTIONS FOR PIPE CULVERTS 15" THRU 84" DIA.
03	542301 PRECAST REINFORCED CONCRETE FLARED END SECTION
01	542401 METAL END SECTIONS FOR PIPE CULVERTS
05	609006 BRIDGE APPROACH PAVEMENT (DRAIN DETAIL)
10	630001 STEEL PLATE BEAM GUARDRAIL
09	630101 GUARDRAIL MOUNTED ON EXISTING CULVERTS
06	630201 PCC/HMA STABILIZATION AT STEEL PLATE BEAM GUARDRAIL
06	630301 SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
01	635001 DELINEATORS
03	635006 REFLECTOR AND TERMINAL MARKER PLACEMENT
02	635011 REFLECTOR MARKER AND MOUNTING DETAILS
02	701001 OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' (4.5M) AWAY
05	701006 OFF-RD OPERATIONS, 2L, 2W, 15' (4.5M) TO 24" (600 MM) FROM PAVEMENT EDGE
03	701306 LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS > 45 MPH
03	701311 LANE CLOSURE, 2L, 2W, MOVING OPERATIONS - DAY ONLY
03	701901 TRAFFIC CONTROL DEVICES
01	720011 METAL POSTS FOR SIGNS, MARKERS & DELINEATORS
04	780001 TYPICAL PAVEMENT MARKINGS
03	781001 TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS

HIGHWAY STANDARDS

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE

PREPARED BY: Tom Brunk
DISTRICT STUDIES & PLANS ENGINEER

DATE: August 15, 2014

EXAMINED BY: [Signature]
DISTRICT CONSTRUCTION ENGINEER

[Signature]
DISTRICT MATERIALS ENGINEER

[Signature]
DISTRICT OPERATIONS ENGINEER

FILE NAME *	USER NAME * mcfaddenka	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\pvidot\mcfaddenka\0288918\	066892-shr-cover.dgn	DRAWN -	REVISED -			840	137-BR	IROQUOIS	24	2	
	PLOT SCALE * 100.0000 / in.	CHECKED -	REVISED -			CONTRACT NO. 66892					
	PLOT DATE * 8/12/2014	DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO