

301 21 804

SUMMARY OF QUANTITIES					
CODE NO	ITEM	UNIT	CONSTRUCTION TYPE CODE		
			80% FED. 20% STATE TOTAL QUANTITY	RDWY 0004 RURAL	038-0119 (EX.) 038-2026 (PR.) BRIDGE 0011 RURAL
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	86	86	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	50 FT	29	29	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1720	1720	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	220	220	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	10	10	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	20	20	
* 78201000	TERMINAL MARKERS - DIRECT APPLIED	EACH	4	4	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	10	10	
X0323265	REMOVE EXISTING RIP RAP	50 YD	246	246	
X0327726	MEMBRANE WATERPROOFING FOR CULVERTS	50 YD	208 . 2		208 . 2
X3550015	HOT-MIX ASPHALT BASE COURSE, (VARIABLE DEPTH)	TON	75	75	
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	50 YD	1275	1275	
X5121800	PERMANENT STEEL SHEET PILING	50 FT	1912		1912

\*Specialty Items

Rev.

FILE NAME *	USER NAME * mcfaddenka	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\pvidot\mcfaddenka\02280910	66892-ahs-schedule.dgn	DRAWN -	REVISED -			840	137-BR	ILLINOIS	24	6	
PLOT SCALE * 100.0000 1/4"	CHECKED -	REVISED -				SCALE: SHEET NO. OF SHEETS STA. TO STA.		CONTRACT NO. 66892			
PLOT DATE * 8/13/2014	DATE -	REVISED -				ILLINOIS FED. AID PROJECT					