INDEX OF SHEETS

- 1 COVER
- 2 INDEX AND GENERAL NOTES
- 3 SUMMARY OF QUANTITIES
- 4 PRAIRIE REMNANT LOCATIONS
- 5 WETLAND LOCATION

HIGHWAY STANDARDS

| 000001-06 | STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS |
|-----------|---|
| 001006 | DECIMAL OF AN INCH AND OF A FOOT |
| 701001-02 | OFF-ROAD OPERATIONS, 2L, 2W, MORE THAN 15' (4.5 M) AWAY |
| 701006-05 | OFF-ROAD OPERATIONS, 2L, 2W, 15' (4.5 M) TO 24" (600 MM) FROM PAVEMENT EDGE |
| 701201-04 | LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS >= 45 MPH |
| 701301-04 | LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS |
| 701311-03 | LANE CLOSURE, 2L, 2W, MOVING OPERATIONS - DAY ONLY |
| 701901-03 | TRAFFIC CONTROL DEVICES |

GENERAL NOTES

G.N. - 100

ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT, WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N. - 201SP

TREES TO BE REMOVED ARE TO NOT BE WITHIN THE RAILROAD RIGHT-OF-WAY. TREES THAT ARE CUT WITHIN THE IDOT RIGHT-OF-WAY SHOULD NOT BE ALLOWED TO FALL WITHIN THE RAILROAD RIGHT-OF WAY. THE CONTRACTOR IS NOT ALLOWED TO PERFORM WORK WITHIN THE RAILROAD RIGHT-OF-WAY WITHOUT AUTHORIZATION FROM THE RAILROAD. THE ENGINEER WILL MAKE FINAL DETERMINATION OF WHICH TREES ARE TO BE REMOVED.

| FILE NAME : | USER NAME t ensured | DESIGNED - | REVISED ~ | | INDEX, GENERAL NOTES | | | | | F.A.P. | SECTION | COUNTY | TOTAL | SHEET NO. | |
|---|----------------------------------|---------------------------|-----------|------------------------------|-----------------------|---------|------|-------|---------|---------|---------------------------------------|----------------------|------------|--------------|---|
| er/pu_vork/puidat/castrab/d8482165/0578 | 182-sht-indexendgenereInstes.dgn | rereinstes.dgn DRAWN - RE | | STATE OF ILLINOIS | AND HIGHWAY STANDARDS | | | | | | 71 (| 5 EAB CONTROL 2015-1 | DEWITT | 5 | 2 |
| | PLOT SCALE * 48.8288 1/ 10. | CHECKED - | REVISED - | DEPARTMENT OF TRANSPORTATION | AND DIGHTAL STANDARDS | | | | | | · · · · · · · · · · · · · · · · · · · | CONTRAC | CT NO. 7 | 28AC | |
| #MCDELNAME# | PLOT DATE = 6/24/2014 | DATE - | REVISED - | | SCALE: | SHEET 2 | OF 5 | SHEET | TS STA. | TO STA. | | ILLINOIS FED. A | ID PROJECT | | |