



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

November 10, 2014

SUBJECT: FAS Route 752/FAS Route 749 (IL 3)
Project ACRS-0752(100)
Section 101-2RS-1
Jersey County
Contract No. 76789
Item No. 100, November 21, 2014 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices
2. Revised pages ii & iii of the Table of Contents to the Special Provisions
3. Revised pages 131-134 of the Special Provisions
4. Added pages 205-210 to the Special Provisions
5. Revised sheet 12 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger" with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Jeffrey L. Keirn, Region 5, District 8; Tim Kell; Estimates

MS/kf

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

76789

State Job # - C-98-021-10

County Name - JERSEY - -

Code - 83 - -

District - 8 - -

Section Number - 101-2RS-1

Project Number

ACRS-0752/100/

*REVISED: NOVEMBER 5, 2014

Route

FAS 749

FAS 752

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-------------|---|------------|---|-------------|
| X0321461 | PILLAR REM | EACH | 4.000 | | | | |
| X0323360 | WOOD POLE REMOVAL | EACH | 2.000 | | | | |
| X0324762 | WIDE LOAD DETOUR SIGN | L SUM | 1.000 | | | | |
| X4401198 | HMA SURF REM VAR DP | SQ YD | 80,723.000 | | | | |
| X6660445 | ROW/PROPERTY CORNERS | EACH | 21.000 | | | | |
| X7010202 | TC-PROT 701321 SPL | EACH | 11.000 | | | | |
| X7801004 | WR THPL PM LINE 4 | FOOT | 103,442.000 | | | | |
| X7801024 | WR THPL PM LINE 24 | FOOT | 282.000 | | | | |
| X8420510 | REM TOWER FDN | EACH | 4.000 | | | | |
| Z0005300 | BOX CUL TO BE CLEANED | EACH | 8.000 | | | | |
| Z0007601 | BLDG REMOV NO 1 | L SUM | 1.000 | | | | |
| Z0012754 | STR REP CON DP = < 5 | SQ FT | 53.000 | | | | |
| Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1.000 | | | | |
| Z0016702 | DETOUR SIGNING | L SUM | 1.000 | | | | |
| Z0023500 | FILL EXIST CULVERTS | CU YD | 41.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

76789

State Job # - C-98-021-10

County Name - JERSEY - -

Code - 83 - -

District - 8 - -

Section Number - 101-2RS-1

Project Number

ACRS-0752/100/

*REVISED: NOVEMBER 5, 2014

Route

FAS 749

FAS 752

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|----------------------|-----------------|-------------|---|------------|---|-------------|
| Z0064505 | SECTION CORNER MKRS | EACH | 23.000 | | | | |
| Z0076600 | TRAINEES | HOUR | 2,500.000 | | 0.800 | | 2,000.000 |
| Z0076604 | TRAINEES TPG | HOUR | 2,500.000 | | 15.000 | | 37,500.000 |
| 20100110 | TREE REMOV 6-15 | UNIT | 3,732.000 | | | | |
| 20100210 | TREE REMOV OVER 15 | UNIT | 4,639.000 | | | | |
| 20100500 | TREE REMOV ACRES | ACRE | 1.000 | | | | |
| 20200100 | EARTH EXCAVATION | CU YD | 166,560.000 | | | | |
| 20200200 | ROCK EXCAVATION | CU YD | 10,519.000 | | | | |
| 20200600 | EXC & GR EX SHOULDER | UNIT | 3.000 | | | | |
| 20700220 | POROUS GRAN EMBANK | CU YD | 98.000 | | | | |
| 20800150 | TRENCH BACKFILL | CU YD | 89.000 | | | | |
| 25000305 | SEEDING CL 3A | ACRE | 39.000 | | | | |
| 25000400 | NITROGEN FERT NUTR | POUND | 3,482.000 | | | | |
| 25000500 | PHOSPHORUS FERT NUTR | POUND | 3,482.000 | | | | |
| 25000600 | POTASSIUM FERT NUTR | POUND | 3,482.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

76789

State Job # - C-98-021-10

County Name - JERSEY - -

Code - 83 - -

District - 8 - -

Section Number - 101-2RS-1

Project Number

ACRS-0752/100/

*REVISED: NOVEMBER 5, 2014

Route

FAS 749

FAS 752

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-------------|---|------------|---|-------------|
| 25100115 | MULCH METHOD 2 | ACRE | 55.750 | | | | |
| 25100630 | EROSION CONTR BLANKET | SQ YD | 114,151.000 | | | | |
| 25100635 | HD EROS CONTR BLANKET | SQ YD | 10,091.000 | | | | |
| 28000250 | TEMP EROS CONTR SEED | POUND | 11,605.000 | | | | |
| 28000305 | TEMP DITCH CHECKS | FOOT | 12,663.000 | | | | |
| 28000315 | AGG DITCH CHECKS | TON | 830.000 | | | | |
| 28000400 | PERIMETER EROS BAR | FOOT | 27,037.000 | | | | |
| 28000500 | INLET & PIPE PROTECT | EACH | 111.000 | | | | |
| 28100107 | STONE RIPRAP CL A4 | SQ YD | 2,564.000 | | | | |
| 28100109 | STONE RIPRAP CL A5 | SQ YD | 2,280.000 | | | | |
| 28200200 | FILTER FABRIC | SQ YD | 9,353.000 | | | | |
| 28300400 | AGGREGATE DITCH | TON | 3,157.000 | | | | |
| 31101000 | SUB GRAN MAT B | TON | 586.000 | | | | |
| 31101600 | SUB GRAN MAT B 8 | SQ YD | 64,602.000 | | | | |
| 31101900 | SUB GRAN MAT C | TON | 5,411.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

76789

State Job # - C-98-021-10

County Name - JERSEY - -

Code - 83 - -

District - 8 - -

Section Number - 101-2RS-1

Project Number

ACRS-0752/100/

*REVISED: NOVEMBER 5, 2014

Route

FAS 749

FAS 752

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-------------|---|------------|---|-------------|
| 35101600 | AGG BASE CSE B 4 | SQ YD | 613.000 | | | | |
| 35101800 | AGG BASE CSE B 6 | SQ YD | 2,172.000 | | | | |
| 35102000 | AGG BASE CSE B 8 | SQ YD | 880.000 | | | | |
| 35501316 | HMA BASE CSE 8 | SQ YD | 3,731.000 | | | | |
| 35600712 | HMA BC WID 9 | SQ YD | 21,711.000 | | | | |
| 40200800 | AGG SURF CSE B | TON | 2,232.000 | | | | |
| 40201000 | AGGREGATE-TEMP ACCESS | TON | 4,163.000 | | | | |
| 40600275 | BIT MATLS PR CT | POUND | 204,071.000 | | | | |
| 40600637 | LB MM IL-9.5FG N70 | TON | 5,758.000 | | | | |
| 40600982 | HMA SURF REM BUTT JT | SQ YD | 107.000 | | | | |
| 40600990 | TEMPORARY RAMP | SQ YD | 111.000 | | | | |
| 40603087 | HMA BC IL-19.0 FG N70 | TON | 610.000 | | | | |
| 40603315 | HMA SC "C" N70 | TON | 7,513.000 | | | | |
| 40800025 | BIT MATLS PR CT | POUND | 6,864.000 | | | | |
| 40800050 | INCIDENTAL HMA SURF | TON | 684.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

76789

State Job # - C-98-021-10

County Name - JERSEY - -

Code - 83 - -

District - 8 - -

Section Number - 101-2RS-1

Project Number

ACRS-0752/100/

*REVISED: NOVEMBER 5, 2014

Route

FAS 749

FAS 752

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|---------------|----------------------|-----------------|------------|---|------------|---|-------------|
| 42001300 | PROTECTIVE COAT | SQ YD | 871.000 | | | | |
| 42300200 | PCC DRIVEWAY PAVT 6 | SQ YD | 167.000 | | | | |
| 42300400 | PCC DRIVEWAY PAVT 8 | SQ YD | 446.000 | | | | |
| *REV 44000100 | PAVEMENT REM | SQ YD | 11,897.000 | | | | |
| 44000151 | HMA SURF REM 1/2 | SQ YD | 5,762.000 | | | | |
| 44000155 | HMA SURF REM 1 1/2 | SQ YD | 614.000 | | | | |
| 44000200 | DRIVE PAVEMENT REM | SQ YD | 2,506.000 | | | | |
| 44000400 | GUTTER REM | FOOT | 18,208.000 | | | | |
| 44000500 | COMB CURB GUTTER REM | FOOT | 319.000 | | | | |
| 44004000 | PAVED DITCH REMOVAL | FOOT | 50.000 | | | | |
| 44004250 | PAVED SHLD REMOVAL | SQ YD | 51.000 | | | | |
| 44200120 | PAVT PATCH T2 10 | SQ YD | 171.000 | | | | |
| 44200124 | PAVT PATCH T3 10 | SQ YD | 207.000 | | | | |
| 44200126 | PAVT PATCH T4 10 | SQ YD | 36.000 | | | | |
| 44300200 | STRIP REF CR CON TR | FOOT | 65,307.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

76789

State Job # - C-98-021-10

County Name - JERSEY - -

Code - 83 - -

District - 8 - -

Section Number - 101-2RS-1

Project Number

ACRS-0752/100/

*REVISED: NOVEMBER 5, 2014

Route

FAS 749

FAS 752

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|------------|---|------------|---|-------------|
| 48101498 | AGGREGATE SHLDS B 4 | SQ YD | 251.000 | | | | |
| 48101500 | AGGREGATE SHLDS B 6 | SQ YD | 168.000 | | | | |
| 48102100 | AGG WEDGE SHLD TYPE B | TON | 2,089.000 | | | | |
| 48203029 | HMA SHOULDERS 8 | SQ YD | 27,696.000 | | | | |
| 50100300 | REM EXIST STRUCT N1 | EACH | 1.000 | | | | |
| 50100400 | REM EXIST STRUCT N2 | EACH | 1.000 | | | | |
| 50100500 | REM EXIST STRUCT N3 | EACH | 1.000 | | | | |
| 50100600 | REM EXIST STRUCT N4 | EACH | 1.000 | | | | |
| 50100700 | REM EXIST STRUCT N5 | EACH | 1.000 | | | | |
| 50100800 | REM EXIST STRUCT N6 | EACH | 1.000 | | | | |
| 50100900 | REM EXIST STRUCT N7 | EACH | 1.000 | | | | |
| 50101000 | REM EXIST STRUCT N8 | EACH | 1.000 | | | | |
| 50101100 | REM EXIST STRUCT N9 | EACH | 1.000 | | | | |
| 50101200 | REM EXIST STRUCT N10 | EACH | 1.000 | | | | |
| 50101300 | REM EXIST STRUCT N11 | EACH | 1.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

76789

State Job # - C-98-021-10

County Name - JERSEY - -

Code - 83 - -

District - 8 - -

Section Number - 101-2RS-1

Project Number

ACRS-0752/100/

*REVISED: NOVEMBER 5, 2014

Route

FAS 749

FAS 752

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|----------------------|-----------------|----------|---|------------|---|-------------|
| 50101400 | REM EXIST STRUCT N12 | EACH | 1.000 | | | | |
| 50101410 | REM EXIST STRUCT N13 | EACH | 1.000 | | | | |
| 50101415 | REM EXIST STRUCT N14 | EACH | 1.000 | | | | |
| 50101420 | REM EXIST STRUCT N15 | EACH | 1.000 | | | | |
| 50101421 | REM EXIST STRUCT N16 | EACH | 1.000 | | | | |
| 50101422 | REM EXIST STRUCT N17 | EACH | 1.000 | | | | |
| 50101423 | REM EXIST STRUCT N18 | EACH | 1.000 | | | | |
| 50101424 | REM EXIST STRUCT N19 | EACH | 1.000 | | | | |
| 50101425 | REM EXIST STRUCT N20 | EACH | 1.000 | | | | |
| 50101426 | REM EXIST STRUCT N21 | EACH | 1.000 | | | | |
| 50101427 | REM EXIST STRUCT N22 | EACH | 1.000 | | | | |
| 50101428 | REM EXIST STRUCT N23 | EACH | 1.000 | | | | |
| 50101429 | REM EXIST STRUCT N24 | EACH | 1.000 | | | | |
| 50101430 | REM EXIST STRUCT N25 | EACH | 1.000 | | | | |
| 50102400 | CONC REM | CU YD | 131.900 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

76789

State Job # - C-98-021-10

County Name - JERSEY - -

Code - 83 - -

District - 8 - -

Section Number - 101-2RS-1

Project Number

ACRS-0752/100/

*REVISED: NOVEMBER 5, 2014

Route

FAS 749

FAS 752

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-------------|---|------------|---|-------------|
| 50104400 | CONC HDWL REM | EACH | 7.000 | | | | |
| 50105220 | PIPE CULVERT REMOV | FOOT | 1,989.000 | | | | |
| 50200400 | ROCK EXC STRUCT | CU YD | 304.700 | | | | |
| 50200450 | REM/DISP UNS MATL-STR | CU YD | 98.000 | | | | |
| 50800105 | REINFORCEMENT BARS | POUND | 115,540.000 | | | | |
| 50800205 | REINF BARS, EPOXY CTD | POUND | 8,770.000 | | | | |
| 50800515 | BAR SPLICERS | EACH | 21.000 | | | | |
| 54001004 | BOX CUL END SEC C4 | EACH | 2.000 | | | | |
| 54001013 | BOX CUL END SEC C13 | EACH | 2.000 | | | | |
| 54001016 | BOX CUL END SEC C16 | EACH | 2.000 | | | | |
| 54002020 | EXPAN BOLTS 3/4 | EACH | 544.000 | | | | |
| 54003000 | CONC BOX CUL | CU YD | 689.100 | | | | |
| 54010403 | PCBC 4X3 | FOOT | 138.000 | | | | |
| 54010503 | PCBC 5X3 | FOOT | 48.000 | | | | |
| 542A0223 | P CUL CL A 1 18 | FOOT | 48.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

76789

State Job # - C-98-021-10

County Name - JERSEY - -

Code - 83 - -

District - 8 - -

Section Number - 101-2RS-1

Project Number

ACRS-0752/100/

*REVISED: NOVEMBER 5, 2014

Route

FAS 749

FAS 752

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|----------------------|-----------------|-----------|---|------------|---|-------------|
| 542A0229 | P CUL CL A 1 24 | FOOT | 90.000 | | | | |
| 542A0235 | P CUL CL A 1 30 | FOOT | 166.000 | | | | |
| 542A0241 | P CUL CL A 1 36 | FOOT | 103.000 | | | | |
| 542D0220 | P CUL CL D 1 15 | FOOT | 2,615.000 | | | | |
| 542D0223 | P CUL CL D 1 18 | FOOT | 364.000 | | | | |
| 542D0229 | P CUL CL D 1 24 | FOOT | 696.000 | | | | |
| 542D0235 | P CUL CL D 1 30 | FOOT | 116.000 | | | | |
| 542D1060 | P CUL CL D 2 15 | FOOT | 66.000 | | | | |
| 542D1063 | P CUL CL D 2 18 | FOOT | 76.000 | | | | |
| 542D1093 | P CUL CL D 2 48 | FOOT | 100.000 | | | | |
| 54213663 | PRC FLAR END SEC 18 | EACH | 3.000 | | | | |
| 54213669 | PRC FLAR END SEC 24 | EACH | 4.000 | | | | |
| 54213675 | PRC FLAR END SEC 30 | EACH | 4.000 | | | | |
| 54213681 | PRC FLAR END SEC 36 | EACH | 4.000 | | | | |
| 54260311 | TRAVERS PIPE GRATE | FOOT | 115.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

76789

State Job # - C-98-021-10

County Name - JERSEY - -

Code - 83 - -

District - 8 - -

Section Number - 101-2RS-1

Project Number

ACRS-0752/100/

*REVISED: NOVEMBER 5, 2014

Route

FAS 749

FAS 752

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-----------|---|------------|---|-------------|
| 550A0090 | STORM SEW CL A 1 18 | FOOT | 15.000 | | | | |
| 550A0160 | STORM SEW CL A 1 36 | FOOT | 111.000 | | | | |
| 59000200 | EPOXY CRACK INJECTION | FOOT | 48.000 | | | | |
| 59300100 | CONTR LOW-STRENG MATL | CU YD | 7.100 | | | | |
| 60221100 | MAN TA 5 DIA T1F CL | EACH | 1.000 | | | | |
| 60224448 | MAN TA 7 DIA T8G | EACH | 1.000 | | | | |
| 60500060 | REMOV INLETS | EACH | 1.000 | | | | |
| 60600095 | CLASS SI CONC OUTLET | CU YD | 9.000 | | | | |
| 60602800 | CONC GUTTER TB | FOOT | 675.000 | | | | |
| 63000001 | SPBGR TY A 6FT POSTS | FOOT | 4,463.000 | | | | |
| 63000025 | SPBGR ATTACH TO STR | FOOT | 25.000 | | | | |
| 63100045 | TRAF BAR TERM T2 | EACH | 9.000 | | | | |
| 63100167 | TR BAR TRM T1 SPL TAN | EACH | 22.000 | | | | |
| 63200310 | GUARDRAIL REMOV | FOOT | 237.000 | | | | |
| 63500105 | DELINEATORS | EACH | 44.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

76789

State Job # - C-98-021-10

County Name - JERSEY - -

Code - 83 - -

District - 8 - -

Section Number - 101-2RS-1

Project Number

ACRS-0752/100/

*REVISED: NOVEMBER 5, 2014

Route

FAS 749

FAS 752

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|---------------|-----------------------|-----------------|------------|---|------------|---|-------------|
| 64200108 | SHOULDER RUM STRIP 8 | FOOT | 45,512.000 | | | | |
| 66600105 | FUR ERECT ROW MARKERS | EACH | 258.000 | | | | |
| 66700205 | PERM SURV MKRS T1 | EACH | 27.000 | | | | |
| 66700705 | FUR ERECT DRAIN MKRS | EACH | 15.000 | | | | |
| *ADD 66900200 | NON SPL WASTE DISPOSL | CU YD | 1,325.000 | | | | |
| *ADD 66900450 | SPL WASTE PLNS/REPORT | L SUM | 1.000 | | | | |
| *ADD 66900530 | SOIL DISPOSAL ANALY | EACH | 5.000 | | | | |
| 67000400 | ENGR FIELD OFFICE A | CAL MO | 32.000 | | | | |
| 67100100 | MOBILIZATION | L SUM | 1.000 | | | | |
| 70100450 | TRAF CONT-PROT 701201 | L SUM | 1.000 | | | | |
| 70100460 | TRAF CONT-PROT 701306 | L SUM | 1.000 | | | | |
| 70100500 | TRAF CONT-PROT 701326 | L SUM | 1.000 | | | | |
| 70100600 | TRAF CONT-PROT 701336 | L SUM | 1.000 | | | | |
| 70103815 | TR CONT SURVEILLANCE | CAL DA | 913.000 | | | | |
| 70106500 | TEMP BR TRAF SIGNALS | EACH | 11.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

76789

State Job # - C-98-021-10

County Name - JERSEY - -

Code - 83 - -

District - 8 - -

Section Number - 101-2RS-1

Project Number

ACRS-0752/100/

*REVISED: NOVEMBER 5, 2014

Route

FAS 749

FAS 752

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-------------|---|------------|---|-------------|
| 70106700 | TEMP RUMBLE STRIPS | EACH | 66.000 | | | | |
| 70106800 | CHANGEABLE MESSAGE SN | CAL MO | 30.000 | | | | |
| 70300100 | SHORT TERM PAVT MKING | FOOT | 2,938.000 | | | | |
| 70300220 | TEMP PVT MK LINE 4 | FOOT | 115,428.000 | | | | |
| 70300240 | TEMP PVT MK LINE 6 | FOOT | 9,550.000 | | | | |
| 70300280 | TEMP PVT MK LINE 24 | FOOT | 282.000 | | | | |
| 70301000 | WORK ZONE PAVT MK REM | SQ FT | 35,243.000 | | | | |
| 70400100 | TEMP CONC BARRIER | FOOT | 4,800.000 | | | | |
| 70400200 | REL TEMP CONC BARRIER | FOOT | 4,450.000 | | | | |
| 70500100 | TEMP SPBGR TY A | FOOT | 87.500 | | | | |
| 70500500 | TEMP SPBGR ATT TO STR | FOOT | 12.500 | | | | |
| 70600250 | IMP ATTN TEMP NRD TL3 | EACH | 24.000 | | | | |
| 70600350 | IMP ATTN REL NRD TL3 | EACH | 24.000 | | | | |
| 72000100 | SIGN PANEL T1 | SQ FT | 404.000 | | | | |
| 72000200 | SIGN PANEL T2 | SQ FT | 90.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

76789

State Job # - C-98-021-10

County Name - JERSEY - -

Code - 83 - -

District - 8 - -

Section Number - 101-2RS-1

Project Number

ACRS-0752/100/

*REVISED: NOVEMBER 5, 2014

Route

FAS 749

FAS 752

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-----------|---|------------|---|-------------|
| 72400500 | RELOC SIN PAN ASSY TA | EACH | 35.000 | | | | |
| 72400600 | RELOC SIN PAN ASSY TB | EACH | 2.000 | | | | |
| 72800100 | TELES STL SIN SUPPORT | FOOT | 212.000 | | | | |
| 72900100 | METAL POST TY A | FOOT | 209.000 | | | | |
| 73000100 | WOOD SIN SUPPORT | FOOT | 1,072.000 | | | | |
| 78100100 | RAISED REFL PAVT MKR | EACH | 411.000 | | | | |
| 78200410 | GUARDRAIL MKR TYPE A | EACH | 74.000 | | | | |
| 78201000 | TERMINAL MARKER - DA | EACH | 22.000 | | | | |
| 78300100 | PAVT MARKING REMOVAL | SQ FT | 3,996.000 | | | | |
| 78300200 | RAISED REF PVT MK REM | EACH | 411.000 | | | | |

| | |
|--|-----|
| STATUS OF UTILITIES TO BE ADJUSTED | 26 |
| HOT-MIX ASPHALT MIXTURE IL-9.5FG (BMPR) | 27 |
| HOT-MIX ASPHALT MIXTURE IL-19.0FG (BMPR) | 31 |
| BUILDING REMOVAL - CASE IV (NO ASBESTOS) (BDE) | 33 |
| STRUCTURAL REPAIR OF CONCRETE | 35 |
| WEEP HOLE DRAINS FOR ABUTMENTS, WINGWALLS, RETAINING WALLS AND CULVERTS..... | 45 |
| AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE)..... | 45 |
| CONCRETE BOX CULVERTS WITH SKEWS \leq 30 DEGREES REGARDLESS OF DESIGN FILL AND SKEWS $>$ 30 DEGREES WITH DESIGN FILLS $>$ 5 FEET (BDE)..... | 47 |
| CONCRETE GUTTER, CURB, MEDIAN, AND PAVED DITCH (BDE) | 47 |
| CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE) | 48 |
| CONTRACT CLAIMS (BDE)..... | 50 |
| DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)..... | 51 |
| FRICTION AGGREGATE (BDE) | 61 |
| GRANULAR MATERIALS (BDE)..... | 64 |
| HOT-MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS (BDE)..... | 64 |
| HOT-MIX ASPHALT – MIXTURE DESIGN COMPOSITION AND VOLUMETRIC REQUIREMENTS (BDE) | 66 |
| HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (BDE)..... | 76 |
| HOT MIX ASPHALT – PRIME COAT (BDE) | 79 |
| LRFD PIPE CULVERT BURIAL TABLES (BDE) | 84 |
| LRFD STORM SEWER BURIAL TABLES (BDE)..... | 103 |
| PAVED SHOULDER REMOVAL (BDE) | 112 |
| PAVEMENT MARKING TAPE TYPE IV (BDE) | 113 |
| PAVEMENT PATCHING (BDE)..... | 115 |
| PAYROLLS AND PAYROLL RECORDS (BDE) | 116 |
| PORTLAND CEMENT CONCRETE EQUIPMENT (BDE)..... | 118 |
| PROGRESS PAYMENTS (BDE) | 118 |
| QUALITY CONTROL/QUALITY ASSURANCE OF CONCRETE MIXTURES (BDE)..... | 119 |
| RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (BDE)..... | 119 |
| REINFORCEMENT BARS (BDE) | 130 |
| REMOVAL AND DISPOSAL OF SURPLUS MATERIALS (BDE)..... | 135 |

TRACKING THE USE OF PESTICIDES (BDE)..... 136
TRAINING SPECIAL PROVISIONS (BDE) 136
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION
(TPG) 139
TRAVERSABLE PIPE GRATE (BDE) 141
WARM MIX ASPHALT (BDE) 142
WEEKLY DBE TRUCKING REPORTS (BDE)..... 144
WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING (BDE) 144
WORKING DAYS (BDE)..... 145
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID)..... 145
FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID)..... 148
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID)..... 152
SWPPP 156
404 PERMIT 165
PROJECT LABOR AGREEMENT - QUARTERLY EMPLOYMENT REPORT 188
PROJECT LABOR AGREEMENT 189
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES.....205

Add the following sentence to the end of the first paragraph of Article 508.06(c) of the Standard Specifications:

“In addition, the total slip of the bars within the splice sleeve of the connector after loading in tension to 30 ksi (207 MPa) and relaxing to 3 ksi (20.7 MPa) shall not exceed 0.01 in. (254 microns).”

Revise Article 1042.03(d) of the Standard Specifications to read:

“(d) Reinforcement and Accessories: The concrete cover over all reinforcement shall be within $\pm 1/4$ in. (± 6 mm) of the specified cover.

Welded wire fabric shall be accurately bent and tied in place.

Miscellaneous accessories to be cast into the concrete or for forming holes and recesses shall be carefully located and rigidly held in place by bolts, clamps, or other effective means. If paper tubes are used for vertical dowel holes, or other vertical holes which require grouting, they shall be removed before transportation to the construction site.”

Revised 11/10/14

--This page intentionally left blank—

Revised 11/10/14

--This page intentionally left blank--

Revised 11/10/14

--This page intentionally left blank—

Revised 11/10/14

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

Revise Article 669.01 of the Standard Specifications to read:

“669.01 Description. This work shall consist of the transportation and proper disposal of contaminated soil and water. This work shall also consist of the removal, transportation, and proper disposal of underground storage tanks (UST), their content and associated underground piping to the point where the piping is above the ground, including determining the content types and estimated quantities.”

Revise Article 669.08 of the Standard Specifications to read:

“669.08 Contaminated Soil and/or Groundwater Monitoring. The Contractor shall hire a qualified environmental firm to monitor the area containing the regulated substances. The affected area shall be monitored with a photoionization detector (PID) utilizing a lamp of 10.6eV or greater or a flame ionization detector (FID). Any field screen reading on the PID or FID in excess of background levels indicates the potential presence of contaminated material requiring handling as a non-special waste, special waste, or hazardous waste. No excavated soils can be taken to a clean construction and demolition debris (CCDD) facility or an uncontaminated soil fill operation with detectable PID or FID meter readings that are above background. The PID or FID meter shall be calibrated on-site and background level readings taken and recorded daily. All testing shall be done by a qualified engineer/technician. Such testing and monitoring shall be included in the work. The Contractor shall identify the exact limits of removal of non-special waste, special waste, or hazardous waste. All limits shall be approved by the Engineer prior to excavation. The Contractor shall take all necessary precautions.

Based upon the land use history of the subject property and/or PID or FID readings indicating contamination, a soil or groundwater sample shall be taken from the same location and submitted to an approved laboratory. Soil or groundwater samples shall be analyzed for the contaminants of concern, including pH, based on the property's land use history or the parameters listed in the maximum allowable concentration (MAC) for chemical constituents in uncontaminated soil established pursuant to Subpart F of 35 Illinois Administrative Code 1100.605. The analytical results shall serve to document the level of soil contamination. Soil and groundwater samples may be required at the discretion of the Engineer to verify the level of soil and groundwater contamination.

Samples shall be grab samples (not combined with other locations). The samples shall be taken with decontaminated or disposable instruments. The samples shall be placed in sealed containers and transported in an insulated container to the laboratory. The container shall maintain a temperature of 39 °F (4 °C). All samples shall be clearly labeled. The labels shall indicate the sample number, date sampled, location and elevation, and any other observations.

Added 11/10/14

The laboratory shall use analytical methods which are able to meet the lowest appropriate practical quantitation limits (PQL) or estimated quantitation limit (EQL) specified in "Test Methods for Evaluating Solid Wastes, Physical/Chemical Methods", EPA Publication No. SW-846 and "Methods for the Determination of Organic Compounds in Drinking Water", EPA, EMSL, EPA-600/4-88/039. For parameters where the specified cleanup objective is below the acceptable detection limit (ADL), the ADL shall serve as the cleanup objective. For other parameters the ADL shall be equal to or below the specified cleanup objective."

Replace the first two paragraphs of Article 669.09 of the Standard Specifications with the following:

"669.09 Contaminated Soil and/or Groundwater Management and Disposal. The management and disposal of contaminated soil and/or groundwater shall be according to the following:

(a) Soil Analytical Results Exceed Most Stringent MAC. When the soil analytical results indicate that detected levels exceed the most stringent maximum allowable concentration (MAC) for chemical constituents in uncontaminated soil established pursuant to Subpart F of 35 Illinois Administrative Code 1100.605, the soil shall be managed as follows:

(1) When analytical results indicate inorganic chemical constituents exceed the most stringent MAC but they are still considered within area background levels by the Engineer, the excavated soil can be utilized within the construction limits as fill, when suitable. Such soil excavated for storm sewers can be placed back into the excavated trench as backfill, when suitable, unless trench backfill is specified. If the soils cannot be utilized within the construction limits, they shall be managed and disposed of off-site as a non-special waste, special waste, or hazardous waste as applicable.

(2) When analytical results indicate chemical constituents exceed the most stringent MAC but do not exceed the MAC for a Metropolitan Statistical Area (MSA) County, the excavated soil can be utilized within the construction limits as fill, when suitable, or managed and disposed of off-site as "uncontaminated soil" at a CCDD facility or an uncontaminated soil fill operation within an MSA County provided the pH of the soil is within the range of 6.25 - 9.0, inclusive.

(3) When analytical results indicate chemical constituents exceed the most stringent MAC but do not exceed the MAC for an MSA County excluding Chicago, or the MAC within the Chicago corporate limits, the excavated soil can be utilized within the construction limits as fill, when suitable, or managed and disposed of off-site as "uncontaminated soil" at a CCDD facility or an uncontaminated soil fill operation within an MSA County excluding Chicago or within the Chicago corporate limits provided the pH of the soil is within the range of 6.25 - 9.0, inclusive.

(4) When analytical results indicate chemical constituents exceed the most stringent MAC but do not exceed the MAC for an MSA County excluding Chicago, the excavated soil can be utilized within the construction limits as fill, when suitable, or managed and disposed of off-site as "uncontaminated soil" at a CCDD facility or an uncontaminated soil fill operation within an MSA County excluding Chicago provided the pH of the soil is within the range of 6.25 - 9.0, inclusive.

Added 11/10/14

(5) When the Engineer determines soil cannot be managed according to Articles 669.09(a)(1) through (a)(4) above, the soil shall be managed and disposed of off-site as a non-special waste, special waste, or hazardous waste as applicable.

(b) Soil Analytical Results Do Not Exceed Most Stringent MAC. When the soil analytical results indicate that detected levels do not exceed the most stringent MAC, the excavated soil can be utilized within the construction limits or managed and disposed of off-site as "uncontaminated soil" according to Article 202.03. However the excavated soil cannot be taken to a CCDD facility or an uncontaminated soil fill operation for the following reason.

(1) The pH of the soil is less than 6.25 or greater than 9.0.

(2) The soil exhibited elevated photoionization detector (PID) utilizing a lamp of 10.6eV or greater or a flame ionization detector (FID) readings.

(c) Soil Analytical Results Exceed Most Stringent MAC but Do Not Exceed TACO Residential. When the soil analytical results indicate that detected levels exceed the most stringent MAC but do not exceed TACO Tier 1 Soil Remediation Objectives for Residential Properties pursuant to 35 IAC 742 Appendix B Table A, the excavated soil can be utilized within the right-of-way or managed and disposed of off-site as "uncontaminated soil" according to Article 202.03. However the excavated soil cannot be taken to a CCDD facility or an uncontaminated soil fill operation.

(d) Groundwater. When groundwater analytical results indicate the detected levels are above Appendix B, Table E of 35 Illinois Administrative Code 742, the most stringent Tier 1 Groundwater Remediation Objectives for Groundwater Component of the Groundwater Ingestion Route for Class 1 groundwater, the groundwater shall be managed off-site as a special waste.

All groundwater encountered within lateral trenches may be managed within the trench and allowed to infiltrate back into the ground. If the groundwater cannot be managed within the trench it must be removed as a special or hazardous waste. The Contractor is prohibited from managing groundwater within the trench by discharging it through any existing or new storm sewer. The Contractor shall install backfill plugs within the area of groundwater contamination.

One backfill plug shall be placed down gradient to the area of groundwater contamination. Backfill plugs shall be installed at intervals not to exceed 50 ft (15 m). Backfill plugs are to be 4 ft (1.2 m) long, measured parallel to the trench, full trench width and depth. Backfill plugs shall not have any fine aggregate bedding or backfill, but shall be entirely cohesive soil or any class of concrete. The Contractor shall provide test data that the material has a permeability of less than 10⁻⁷ cm/sec according to ASTM D 5084, Method A or per another test method approved by the Engineer."

Added 11/10/14

Revise Article 669.14 of the Standard Specifications to read:

“669.14 Final Environmental Construction Report. At the end of the project, the Contractor will prepare and submit three copies of the Environmental Construction Report on the activities conducted during the life of the project, one copy shall be submitted to the Resident Engineer, one copy shall be submitted to the District's Environmental Studies Unit, and one copy shall be submitted with an electronic copy in Adode.pdf format to the Geologic and Waste Assessment Unit, Bureau of Design and Environment, IDOT, 2300 South Dirksen Parkway, Springfield, Illinois 62764. The technical report shall include all pertinent information regarding the project including, but not limited to:

(a) Measures taken to identify, monitor, handle, and dispose of soil or groundwater containing regulated substances, to prevent further migration of regulated substances, and to protect workers,

(b) Cost of identifying, monitoring, handling, and disposing of soil or groundwater containing regulated substances, the cost of preventing further migration of regulated substances, and the cost for worker protection from the regulated substances. All cost should be in the format of the contract pay items listed in the contract plans (identified by the preliminary environmental site assessment (PESA) site number),

(c) Plan sheets showing the areas containing the regulated substances,

(d) Field sampling and testing results used to identify the nature and extent of the regulated substances,

(e) Waste manifests (identified by the preliminary environmental site assessment (PESA) site number) for special or hazardous waste disposal, and

(f) Landfill tickets (identified by the preliminary environmental site assessment (PESA) site number) for non-special waste disposal.”

Revise the second paragraph of Article 669.16 of the Standard Specifications to read:

“The transportation and disposal of soil and other materials from an excavation determined to be contaminated will be paid for at the contract unit price per cubic yard (cubic meter) for NON-SPECIAL WASTE DISPOSAL, SPECIAL WASTE DISPOSAL, or HAZARDOUS WASTE DISPOSAL.”

Qualifications. The term environmental firm shall mean an environmental firm with at least five (5) documented leaking underground storage tank (LUST) cleanups or that is pre-qualified in hazardous waste by the Department. Documentation includes but not limited to verifying remediation and special waste operations for sites contaminated with gasoline, diesel, or waste oil in accordance with all Federal, State, or local regulatory requirements and shall be provided to the Engineer for approval. The environmental firm selected shall not be a former or current consultant or have any ties with any of the properties contained within and/or adjacent to this construction project.

Added 11/10/14

General. This Special Provision will likely require the Contractor to subcontract for the execution of certain activities.

All contaminated materials shall be managed as either “uncontaminated soil” or non-special waste. This work shall include monitoring and potential sampling, analytical testing, and management of a material contaminated by regulated substances. The Environmental Firm shall continuously monitor all soil excavation for worker protection and soil contamination. Phase I Preliminary Engineering information is available through the District’s Environmental Studies Unit. Soil samples or analysis without the approval of the Engineer will be at no additional cost to the Department. The lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit whichever is less.

The Contractor shall manage any excavated soils and sediment within the following areas:
ISGS Site 2277-2 – Jersey County Recycling Center

- Station 421+20 to Station 423+50, 0 to 40 feet LT along IL 3 (Jersey County Recycling Center, PESA Site 2277-2, 25700 block of IL 3 and 15000 block of IL 109) - This material meets the criteria of Article 669.09(a)(2) and shall be managed in accordance to Article 669.09. COCs sampling parameters: Arsenic.
- Station 423+50 to Station 424+60, 0 to 90 feet LT along IL 3 (Jersey County Recycling Center, PESA Site 2277-2, 25700 block of IL 3 and 15000 block of IL 109) - This material meets the criteria of Article 669.09(a)(1) and shall be managed in accordance to Article 669.09. COCs sampling parameters: Arsenic.

ISGS Site 2277-26 – Farmstead

- Station 318+50 to Station 320+00, 0 to 55 feet RT along IL 3 (Farmstead, PESA Site 2277-26, 3899 IL 3, Dow) - This material meets the criteria of Article 669.09(a)(5) and shall be managed in accordance to Article 669.09. COCs sampling parameters: Arsenic.
- Station 320+00 to Station 321+25, 0 to 55 feet RT along IL 3 (Farmstead, PESA Site 2277-26, 3899 IL 3, Dow) - This material meets the criteria of Article 669.09(a)(1) and shall be managed in accordance to Article 669.09. COCs sampling parameters: Arsenic.
- Station 321+25 to Station 322+00, 0 to 55 feet RT along IL 3 (Farmstead, PESA Site 2277-26, 3899 IL 3, Dow) - This material meets the criteria of Article 669.09(a)(2) and shall be managed in accordance to Article 669.09. COCs sampling parameters: Arsenic.

ISGS Site 2277-42 – Farmstead

- Station 214+00 to Station 215+40, 0 to 60 feet LT along IL 3 (Farmstead, PESA Site 2277-42, 21876 IL 3, Grafton) - This material meets the criteria of Article 669.09(b)(1) and shall be managed in accordance to Article 669.09.
- Station 216+65 to Station 217+90, 0 to 60 feet LT along IL 3 (Farmstead, PESA Site 2277-42, 21876 IL 3, Grafton) - This material meets the criteria of Article 669.09(a)(2) and shall be managed in accordance to Article 669.09. COCs sampling parameters: Arsenic.

Added 11/10/14

ISGS Site 2277-56 – Residence and Grafton Material Service

- Station 153+50 to Station 154+50, 0 to 65 feet LT along IL 3 (Residence and Grafton Material Service, PESA Site 2277-56, 20855 IL 3, Grafton) - This material meets the criteria of Article 669.09(a)(1) and shall be managed in accordance to Article 669.09. COCs sampling parameters: Arsenic.
- Station 154+50 to Station 156+50, 0 to 65 feet LT along IL 3 (Residence and Grafton Material Service, PESA Site 2277-56, 20855 IL 3, Grafton) - This material meets the criteria of Article 669.09(b)(1) and shall be managed in accordance to Article 669.09.
- Station 154+25 to Station 155+05, 0 to 75 feet RT along IL 3 (Residence and Grafton Material Service, PESA Site 2277-56, 20855 IL 3, Grafton) - This material meets the criteria of Article 669.09(b)(1) and shall be managed in accordance to Article 669.09.

ISGS Site 2277-59 – Residence

- Station 136+80 to Station 137+80, 0 to 60 feet LT along IL 3 (Residence, PESA Site 2277-59, 20628 IL 3, Grafton) - This material meets the criteria of Article 669.09(a)(2) and shall be managed in accordance to Article 669.09. COCs sampling parameters: Arsenic.
- Station 137+80 to Station 138+80, 0 to 60 feet LT along IL 3 (Residence, PESA Site 2277-59, 20628 IL 3, Grafton) - This material meets the criteria of Article 669.09(b)(1) and shall be managed in accordance to Article 669.09.

ISGS Site 2277-62 – Residence

- Station 121+10 to Station 122+10, 0 to 20 feet LT along IL 3 (Residence, PESA Site 2277-62, 20450 IL 3, Grafton) - This material meets the criteria of Article 669.09(a)(2) and shall be managed in accordance to Article 669.09. COCs sampling parameters: Arsenic.

ISGS Site 2277-65 – Farmstead

- Station 107+85 to Station 109+85, 0 to 60 feet LT along IL 3 (Farmstead, PESA Site 2277-65, 20242 IL 3, Grafton) - This material meets the criteria of Article 669.09(a)(2) and shall be managed in accordance to Article 669.09. COCs sampling parameters: Arsenic and lead.

Added 11/10/14