

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				80/20 FED / STATE ROADWAY 0004 RURAL	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	4463	4463	
* 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	25	25	
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	9	9	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	22	22	
63200310	GUARDRAIL REMOVAL	FOOT	237	237	
63500105	DELINEATORS	EACH	44	44	
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	45512	45512	
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	258	258	
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	27	27	
66700705	FURNISHING AND ERECTING DRAINAGE MARKERS	EACH	15	15	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	32	32	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	

14

* SPECIALTY ITEM

* FAS 752/FAS 749

FILE NAME =	USER NAME = harbaughd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.S. RTE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
e:\pwork\pvs\dott\harbaughd\0130105\0176789-415-500.dgn		DRAWN -	REVISED -		•	101-2RS-1	JERSEY	438	12				
PLOT SCALE = 100.0000' / 1" =		CHECKED -	REVISED -		SCALE: N/A				SHEET NO. 10 OF 14 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT
PLOT DATE = 8/22/2014		DATE -	REVISED -						CONTRACT NO. 76789				