

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				80/20
				FED / STATE
				ROADWAY
				0004
				RURAL
70500500	TEMPORARY STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	12.5	12.5
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	24	24
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	24	24
* 72000100	SIGN PANEL - TYPE 1	50 FT	404	404
* 72000200	SIGN PANEL - TYPE 2	50 FT	90	90
* 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	35	35
* 72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	2	2
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	212	212
* 72900100	METAL POST - TYPE A	FOOT	209	209
* 73000100	WOOD SIGN SUPPORT	FOOT	1072	1072
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	411	411
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	74	74
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	22	22
78300100	PAVEMENT MARKING REMOVAL	50 FT	3996	3996

* SPECIALTY ITEM

* FAS 752/FAS 749

FILE NAME =	USER NAME = harbaughd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.S.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pvc\work\pvidot\harbaughd\0130185\076789-ent-500.dgn	76789-ent-500.dgn	DRAWN -	REVISED -		*	101-2RS-1	JERSEY	438	14	CONTRACT NO. 76789			
PLOT SCALE = 100.0000' / 1" =	CHECKED -	REVISED -			SCALE: N/A	SHEET NO. 12 OF 14 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				
PLOT DATE = 8/22/2014	DATE -	REVISED -											